

Iowa Communications Network Statement of Work HENRY COUNTY CLINIC PROJECTS

OSP Log 44220405, New Link 1625, 12 Fiber Cable Henry County, New London, Health Clinic, 111 W. Washington St.

44220405 Project Overview:

THE ICN INTENDS TO INSTALL A 12-STRAND ARMORED CABLE CONNECTION FROM THE HENRY COUNTY HEALTH CLINIC DATA ROOM, 111 W. WASHINGTON ST, NEW LONDON, IA, TO THE EXISTING ICN HANDHOLE AT THE INTERSECTION OF E. CLEVELAND ST AND E. ADAMS ST, NEW LONDON, IA. THIS WILL REQUIRE CONDUIT OF APPROXIMATELY 3,008 FEET AND A TOTAL CABLE FOOTAGE OF APPROXIMATELY 3,408 FEET.

OSP Log 44220305, New Link 1624, 12 Fiber Cable Henry County, Wayland, Health Clinic, 227 W. Main St, Suite #103

44220305 Project Overview:

THE ICN INTENDS TO INSTALL A 12-STRAND ARMORED CABLE CONNECTION FROM WACO JR/SR HIGH SCHOOL DATA ROOM, 706 N. PEARL ST, WAYLAND, IA TO THE HENRY COUNTY HEALTH CLINIC DATA ROOM, 227 W. MAIN ST, WAYLAND, IA. THIS WILL REQUIRE CONDUIT OF APPROXIMATELY 3,594 FEET AND A TOTAL CABLE FOOTAGE OF APPROXIMATELY 4,094 FEET.

Please see the maps and pictures in the attached CONSTRUCTION DRAWING(S). All work to be completed per the attached STANDARD INSTALLATION REQUIREMENTS and TYPICALS except where noted within this STATEMENT OF WORK (SOW). Upon notification of completion, the ICN will perform a review using the attached PUNCHLIST. Any corrections will need to be made prior to ICN issuing payment for work completed.

FIBER OPTIC CABLE SPLICING EXCLUDED FROM THIS CONSTRUCTION BID

ICN Responsibilities:

1. Project Management
2. ICN will secure all necessary DOT, County, or City ROW permits.
3. **ICN Provided Materials per attached table in construction drawings:** Contractor shall pick up ICN-provided materials at the ICN warehouse in Des Moines. Contact the ICN warehouse 48 hours in advance to pick up materials; contact Paul Damage (515-725-4749) to ensure availability.

Contractor Responsibilities:

1. Contractor shall supply all other materials required for proper installation, including but not limited to: Handholes, HDPE, Grounding and Tracer Wires, Rock, Wire Mesh, etc.
2. Construction and/or excavation permits and/or bonds as required by ROW jurisdiction.

Bid/Job Showing: N/A

Work Start Date: Work may begin upon award of the bid and completion of the contract. The ICN anticipates work to begin in May 2022.

Completion Date: Expected completion June 17th, 2022 but not later than June 30th, 2022.

Only written modifications to this Scope of Work are binding - Verbal changes to this scope of work by any person or persons are not binding, unless confirmed in writing.

Quotes:

1. Quotes must be received by Sheri Stephens, ICN Contracting, **NLT 2PM on April 20, 2022.**
2. **CONTRACTOR SHALL PROVIDE A BID FOR EACH PROJECT; THE PROJECTS WILL BE AWARDED AS A WHOLE BASED ON TOTAL BID**
3. Contractors must submit a quote for Construction Bid as outlined in the SOW and per the Engineering drawings. ICN requires a breakdown of lump sum bids into labor and materials.

Quotes may be faxed, e-mailed or delivered to:
Sheri Stephens

ICN Contracting
Grimes State Office Building
400 East 14th Street
Des Moines, IA 50319
Fax: 515-725-4774
E-Mail: sheri.stephens@iowa.gov

Completion of Work:

1. Upon notification of construction completion, ICN will have 2 weeks to complete the Punch List.
2. Upon initial completion of Punch List, the Contractor will have 2 weeks to correct any issues identified on the Punch List.
3. Upon notification of corrections, the ICN will have 1 week to verify corrections were completed to the ICN's satisfaction.
4. No payment will be made until all work is completed per the contract unless agreed upon by both parties.

Attachments: The following are included by reference and as provided within Bid Documents.

Statement of Work (SOW), this document

Construction Drawings (includes Materials list and Typical Installation Drawings); 44220405 and 44220305

Punch Lists 44220405 and 44220305