

# Rock Creek State Park

## Culvert Replacement

Attachment C

Sawcut asphalt to remove 22'x22' and dispose offsite. Remove 18"x50' CMP, dispose offsite. Install 24"x48' RCP plus two 24" aprons. Bed pipe in class "A" crushed stone and backfill trench under road with compacted rock. Use class "A" stone for pavement subbase. Pour 6" PCC to replace roadway. Place class "E" riprap around inlet and below outlet.

Google Earth

Image © 2025 Airbus



600 ft