



IOWA DEPARTMENT OF AGRICULTURE & LAND STEWARDSHIP

Division of Soil Conservation and Water Quality

Cover Page: Pre-Bid Minutes, Questions, Addenda

To:	All plan holders	From:	Tracy Blocker, Division
Pages:		Phone:	515-344-6279
Re:	Wri922420DNutrient Reduction Wetland (Bid 26-05)	Date:	July 12, 2026

Comments:	Page
• Cover Page	1
• Addendum No. 1 with Attachments 1, 2 &3	2 - 89
• Pre-Bid Meeting Minutes	90 - 97
• Pre-Bid meeting attendance list	98
• Updated plan holders list	99 - 101
• Electronic files for grading can be obtained by e-mail by contacting Andrew Schippers with Ducks Unlimited at 832-704-3286 or aschippers@ducks.org .	

- END OF COVER PAGE -



July 9, 2026

Division of Soil Conservation and Water Quality
1305 E Walnut Street
Des Moines, IA 50319

TO: Prospective Bidders

Subject: Addendum **No. 1** to Bid Documents
WRI922420D Nutrient Reduction Wetland Project – Bid No. 26-05
Wright County, Iowa

This addendum forms a part of the bidding contract documents and modifies the original bidding documents posted on June 14, 2026. An updated bidding form, Document CC– Proposal and Schedule of Prices is attached with the addendum acknowledged. This updated bidding form must be used for 26-05 and all bidders must acknowledge this addendum on Page CC-2. **FAILURE TO DO SO WILL SUBJECT BIDDER TO DISQUALIFICATION.**

Description:

DOCUMENT CC– PROPOSAL AND SCHEDULE OF PRICES, 26-05 (See Attachment No.1)

- Please use the updated Document CC, to acknowledge Addendum No. 1 (See Attachment No. 1):

Plans (See Attachment No. 2)

- Revisions have been made to Bid items 5, 21, 22, 23, 28 and a new Bid item 29 has been added.
- These changes are included in Plans C002 and C101. See new Plan set dated '2026-07-09'.

Specifications (See Attachment No. 3)

- With the revised plan set, the Technical Specifications have also been updated. These changes are included in Specifications CS-006, CS-008, CS-051 and CS-061.
- See the revised Technical Specifications booklet, dated 07-09-2026.

Sincerely,

Sara Smith, P.E.
Water Resources Bureau

Attachment No. 1 – Updated Document CC
Attachment No. 2 – Revised set of Plans dated 07-09-2026
Attachment No. 3 – Revised Specifications booklet dated 07-09-2026

End of Addendum No. 1

Time and Date for Bid Submissions: 3:00:00 PM, 07/16/2026
BIDDER LOGIN –
<https://solutions.scquest.com/apps/Router/SupplierLogin?CustOrg=DASIowa>

Time and Date of Bid Opening: 3:00 PM, July 16, 2026

Bid Opening TEAMS: 469-998-7627, code 596080221#

Project Description and Location: Wri922420D Nutrient Reduction Wetland Project
Section 20, Township 92 North, Range 24 West
Wright County, Iowa

PROPOSAL AND SCHEDULE OF PRICES

Proposal of _____
(PRINT Name of Bidder: COMPANY & CONTACT)

Located at _____
(FULL Address) (Telephone Number)

Amount of Proposal Guarantee	Description of Work	Specified Completion Date	Liquidated Damages
10% of Base Bid	All Work Except Seeding	June 15, 2027	\$175.00 Per Day
	Seeding - Buffer Seeding – Structure	06/30/2027 09/15/2027	\$125.00 Per Day

The undersigned hereby agrees, if awarded the contract, to execute the proposed contract and to furnish satisfactory Performance Bond in an amount not less than one hundred percent (100%) of the contract award within fourteen (14) days from the date when Notice-of-Award is received, and to provide all supervision, labor, materials, and equipment required to complete the project designated above, for the prices hereinafter set forth, in strict compliance with the Contract Documents prepared by the Division.

Further, the parties agree and acknowledge as follows:

- The amount of loss or damages likely to be incurred by Division are uncertain and said loss is incapable or very difficult to quantify and estimate;
- The amount specified for liquidated damages herein bear a reasonable relationship to, and are not plainly or grossly disproportionate to, the probable loss likely to be incurred by Division in connection with any delay on part of the Contractor;
- The amount of liquidated damages fixed herein bears a reasonable relationship to Division's anticipated losses and/or actual losses;
- The amount of liquidated damages herein fairly approximates Division's loss at the time of making of this Agreement;
- The amount of liquidated damages fixed herein are fair and reasonable and it approximates to the extent possible the actual loss to Division as a result of any delay on the part of Contractor; and
- Division and Contractor are sophisticated parties and negotiated this Agreement at arm's length.

Now therefore, in consideration of the mutual obligations set forth herein, the receipt and sufficiency of which is hereby acknowledged, the parties agree as follows:

- Contractor will commence the work after the Preconstruction Conference and by the Construction Start Date approved by Division in the Construction Progress Schedule.
- Contractor will complete the work within the specified time period identified in the contract, or as amended, or be responsible for liquidated damages per day as set forth in the above table.
- The liquidated damages may be withheld from payments made to the Contractor by the Division upon written notice that liquidated damages have begun to accrue, and such damages are in addition to other remedies available as provided for in this contract and applicable law.

A Proposal Guarantee in the amount stipulated herein is included with this proposal, to be forfeited to the Division, if the undersigned fails or refuses to execute the contract and furnish satisfactory Performance Bond, if awarded the contract.

By _____

(Signed)

(PRINT NAME)

(Title)

(Date)

In executing this proposal, Bidder acknowledges receipt of Addendum Number 1 dated July 9, 2026

In executing this proposal, Bidder acknowledges receipt of Addendum Number _____ dated _____

In executing this proposal, Bidder acknowledges receipt of Addendum Number _____ dated _____

THE FOLLOWING AFFIDAVIT MUST BE COMPLETED AND NOTARIZED, OR THIS BID WILL BE REJECTED

AFFIDAVIT

The signatory, being duly sworn, does depose and say that the undersigned is an authorized representative of:

(Name of Firm)

Located at _____

hereinafter referred to as "Bidder" and does hereby affirm to have personal knowledge that said Bidder has thoroughly examined the Contract Documents, carefully prepared the Proposal and Schedule of Prices form, and has checked the same in detail before submitting; and that said Bidder, or the agents, officers, or employees thereof, have not, either directly or indirectly, entered into any agreement, participated in any collusion or fraud, or otherwise taken any action in restraint of free competitive bidding in connection with this bid.

(Signed)

(PRINT name)

Subscribed and sworn to before me this _____ day
of _____, 20____

(Signed, Notary)

My Commission Expires _____, 20____

Must include notary stamp

SCHEDULE OF PRICES

Wri922420D Project
 Contract No. 26-05
 Section 20, Township 92 North, Range 24 West, Wright County, Iowa

Name of Bidder:

	Item No.	Work or Material	Spec No.	Est Quantity	Unit	Unit Price	Total
1.1	1	Stripping	IA CS-001	1	LS		
	2	Crop Damage	IA CS-001	0.0	AC		
1.2	3	Structure Seeding	IA CS-006	1.1	AC		
1.3	4	Buffer Seeding	IA CS-006	25.2	AC		
1.4	5	Mobilization & Demobilization	CS-008	1	LS		
1.5	6	Drainage Tile Investigation	IA CS-009	1	LS		
1.6	7	Steel Sheet Piling	IA CS-013	932	SF		
1.7	8	Excavation (General)	IA CS-021	1,741	CY-P		
1.8	9	Earthfill (General)	IA CS-023	554	CY-P		
1.9	10	Earthfill (General Dam)	IA CS-023	2,828	CY-P		
1.10	11	Earthfill (Dam Core)	IA CS-023	1,476	CY-P		
1.11	12	Drainfill (sand)	IA CS-024	80.0	TN		
1.12	13	Topsoil Placement	IA CS-026	6,349	CY-P		
1.13	14	Toe Drain (6" Perforated CPP)	IA CS-046	430	LF		
1.14	15	8"Ø HDPE Dual-Wall	IA CS-046	125	LF		
1.15	16	15"Ø HDPE Dual-Wall	IA CS-046	1,138	LF		
1.16	17	18"Ø HDPE Dual-Wall	IA CS-046	667	LF		
1.17	18	Alum. CMP Draw-Down Structure	IA CS-051	1	LS		
1.18	19	Alum. CMP Draw-Down Inlet/Outlet	IA CS-051	57	LF		
1.19	20	Stoplog Storage Structure	IA CS-046	1	LS		
1.20	21	CMP Outlet - 10"Ø	IA CS-051	20	LF		
1.21	22	CMP Outlet - 18"Ø	IA CS-051	40	LF		
1.22	23	CMP Outlet - 20"Ø	IA CS-051	20	LF		
1.23	24	Riprap (IA DOT Class E)	IA CS-061	552.0	TN		
1.24	25	Cement Grout	IA CS-062	106	CY		
1.25	26	36"Ø Alum. CMP Riser Inlet (at wetland)	IA CS-051	1	LS		
1.26	27	18"Ø Alum. CMP Riser Inlet (at stilling basin)	IA CS-051	1	LS		
1.27	28	Septic System Modification	CS-008	1	LS		
1.28	29	CMP Outlet - 8"Ø	IA CS-051	40	LF		

TOTAL BASE BID \$_____

Worksheet purposes only. Bids will only be accepted through the on-line Iowa Management of Procurement & Contracts System (IMPACS).

To register and learn about IMPACS, go to:


<https://solutions.sciquest.com/apps/Router/SupplierLogin?CustOrg=DASIowa>

END OF DOCUMENT CC

WRI922420D Nutrient Reduction Wetland Project
Bid No. 26-05


Attachment No. 2

Revised set of Plans dated 07-09-2026



NOT FOR CONSTRUCTION

NOTICE: CONSTRUCTION SITE SAFETY IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR. DUCKS UNLIMITED, INC. SHALL NOT ASSUME ANY RESPONSIBILITY FOR THE SAFETY OF THE WORK PERFORMED. PERSONS ENGAGED IN THE WORK, NEARBY STRUCTURES, OR OF OTHER PERSONS ON-SITE. THIS MATERIAL, DATA AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. AND IS NOT TO BE REPRODUCED OR REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO WARRANTY, REPRESENTATION OR GUARANTEE, EXPRESS OR IMPLIED, AS TO THE ACCURACY, COMPLETENESS, RELIABILITY, OR FITNESS FOR ANY PARTICULAR PURPOSE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF. THE USER OF THIS MATERIAL, DATA AND INFORMATION IS AT THE USER'S SOLE RISK. BY USING ANY OF THIS MATERIAL, DATA AND INFORMATION, THE USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF. THE USER SHALL BE RESPONSIBLE FOR THE SAFETY OF THE WORK PERFORMED, THE DATE OF SUCH ALTERATION, AND A SPECIFIC DESCRIPTION OF THE ALTERATION. C:\Users\woodbury\Documents\Iowa - Documents\Iowa\02_C3D Projects\IA-340-2 CREP Projects\Wright-Peterson-Topo.dwg, 7/19/2026 11:59 AM, Lucas Woodbury, Topo C051, None



OCTOBER 20, 2022

US-1A-340-8, WRIGHT COUNTY - PETERSON
Topographic Survey Field Book: CREP

HORIZONTAL CONTROL
Coordinates are NAD 83 (2011), Iowa State Plane North Zone 1401, and units of measurement are in U.S. Survey Feet. Raw data was collected for 5 hours on October 20, 2022 using a Trimble R12 GPS base receiver. Coordinates were initially established from an autonomous survey, and post-processed with the NGS OPUS (National Geodetic Survey, Online Positioning User Service) solution for the occupied Control Point 01.

VERTICAL CONTROL
Elevations were established from the OPUS solution for Control Point 01 using (GEOID18) CONUS file, elevation 1224.299 on the NAVD 88.

FIELD WORK TIMELINE:
October 20, 2022 - Initial Topographic Survey; Control Points Set, Obtained OPUS Solution.
March 29-30, 2023 - Tile Investigation and Test Pits.
April 24, 2023 - Soil Borings by CTs.

CONTROL POINT DATA				
POINT #	ELEVATION	NORTHING	EASTING	DESCRIPTION
01	1224.299	3740484.655	4868702.195	SET CAPPED REBAR
02	1205.411	3740368.792	4866123.355	SET CAPPED REBAR
03	1202.219	3741652.248	4867398.756	SET CAPPED REBAR

TEST PIT SOIL DATA						
LOCATION	TEST PIT #1	TEST PIT #2	TEST PIT #3	TEST PIT #4	TEST PIT #5	TEST PIT #6
TOP	36" TOPSOIL	26" TOPSOIL	24" TOPSOIL	31" TOPSOIL	34" TOPSOIL	25" TOPSOIL
ELEV. RANGE	1203.1–1206.0	1199.5–1201.7	1193.8–1195.7	1201.7–1204.3	1192.8–1195.6	1201.4–1203.5
MIDDLE	MINIMAL TRANSITION	MINIMAL TRANSITION	LIGHT BROWN/GRAY CLAY MIXED W/SAND	LIGHT BROWN CLAY MIX W/ SAND	MINIMAL TRANSITION	LIGHT BROWN CLAY MIX (W/SAND)
ELEV. RANGE	N/A	N/A	1190.3–1193.8	1200.6–1201.7	N/A	1199.7–1201.4
BOTTOM	LIGHT BROWN CLAY (SOME SAND CONTENT)	LIGHT BROWN SOIL WITH LIGHT GRAY PARTICLES (CLAY & SOME SAND)	ORANGE SAND OVER GRAY/BLUE CLAY	DARK ORANGE AND BROWN CLAY	LIGHT BROWN CLAY (SOME SAND)	DARK ORANGE AND BROWN CLAY
ELEV. RANGE	1197.3–1203.1	1192.5–1199.5	1187.3–1190.3	1195.1–1200.6	1187.1–1192.8	1195.2–1199.7

*TEST PIT DIMENSIONS MEASURED APPROXIMATELY 20' LONG, 3' WIDE, & 3.5' DEEP.

SOIL BORING SOIL DATA			
LOCATION	B1	B2	B3
TOP	12" TOPSOIL	12" TOPSOIL	12" TOPSOIL
ELEV. RANGE	1196.3–1197.3	1191.8–1192.8	1191.9–1192.9
MIDDLE	LEAN CLAY WITH SAND,	FAT CLAY	FAT CLAY
ELEV. RANGE	1191.3–1196.3	1188.3–1191.8	1189.4–1191.9
BOTTOM	LEAN CLAY WITH SAND AND GRAVEL	LEAN CLAY WITH SAND	SANDY LEAN CLAY TO LEAN CLAY WITH SAND
ELEV. RANGE	1182.3–1191.3	1167.8–1188.3	1167.9–1189.4

GREAT LAKES/ATLANTIC REGIONAL OFFICE
7322 NEWMAN BOULEVARD, BUILDING 2
DEXTER, MICHIGAN 48130
(734) 623-2000
www.ducks.org

AFFIX SEAL: DUCKS UNLIMITED, INC.
ON:

TOPOGRAPHY & EXISTING
CONDITIONS
PROJECT NO. WR1922420D
WRIGHT COUNTY
IOWA

Revision	Sheet	Revisions	Date	By
1		NRCG/DALS REVIEW UPDATES	9-19-24	A.S.

CAD FILE:
Wright-Peterson-Topo
DESIGNED BY: A.S.
DRAWN BY: C.K.
SURVEYED BY: A.S., J.W.
REVIEWER: T.P.
DATE:
6-19-24
PROJECT NUMBER:
IA-340-8
C051

NOT FOR CONSTRUCTION

NOTE:
CONSTRUCTION SITE ACCESS WILL BE ON 200TH
ST. ALONG THE EASEMENT BOUNDARY.

PROPOSED BERM
TOP ELEV. 1198.7'

TILE #4 - DAYLIGHT 15"Ø
HDPE DUAL WALL
E:4866533.3880
N:3740536.4073
INV. ELEV. 1195.1'
INSTALL APPROX. 617 L.F. @ 0.14%
SLOPE; PROVIDE 3' MIN. GROUND
COVER OVER PIPE.

ASADY FAMILY
REVOCABLE TRUST

PETERSON, RICK E.

PROPOSED SEDIMENTATION BASIN; BOTTOM OF
BASIN ELEVATION 1192.0 W/ 3:1 SIDE SLOPES;
BASIN BOTTOM DIMENSIONS 15' WIDE X 30' LONG

BREAK EXISTING 12"Ø CLAY TILE
FROM INTERCEPT LOCATION FOR 100' IN
DOWNSTREAM DIRECTION
(CLAY; CRUSH EXISTING TILE IN PLACE)

EV. 1197.6'

CROWE FARMS, LLC

TILE #2 - INTERCEPT EXISTING 12" Ø
CLAY TILE AND RE-ROUTE W/
18" Ø HDPE DUAL-WALL PIPE
AT 0.10% SLOPE FOR 667 L.F.
TIE IN INVERT ELEV. 1195.76'
OUTLET INVERT ELEV. 1195.1'
EASTING: 4867507.9640
NORTHING: 3742372.6300

TILE #2 - DAYLIGHT 18"Ø
HDPE DUAL WALL
E: 4867026.6688
N: 3741991.7798
INV. ELEV. 1195.1'
INSTALL APPROX. 667 L.F.
SLOPE; PROVIDE 3' MIN. G
COVER OVER PIPE.

APPROX. PROPERTY LINE

50' TILE BREAK ON
5" Ø EXISTING CLAY TILE
(CLAY; CRUSH EXISTING TILE)

BREAK EXISTING 12"Ø CLAY TILE
FROM INTERCEPT LOCATION FOR 100' IN
DOWNSTREAM DIRECTION
(CLAY; CRUSH EXISTING TILE IN PLACE)

TILE #3 - INTERCEPT EXISTING 12" Ø
CLAY TILE AND RE-ROUTE W/
15" Ø HDPE DUAL-WALL PIPE
AT 0.30% SLOPE FOR 522 L.F.
TIE IN INVERT ELEV. 1196.69'
OUTLET INVERT ELEV. 1195.1'
EASTING: 4867270.4969
NORTHING: 3741416.1053

LE #3 - DAYLIGHT 15"Ø
PIPE DUAL WALL
4866754.0391
3741494.9597
V. ELEV. 1195.1'
STALL APPROX. 522 L.F.
PIPE; PROVIDE 3' MIN. C
OVER OVER PIPE.

PROPOSED WETLAND GRADING AREA;
GRADE DOWN TO ELEV. 1193.0'

PROPOSED EDGE OF NWL ELEVATION
4.99 ACRES @ 1194.1' FSL

PETERSON, RICK E.

PROPOSED BORROW AREA FOR CLAY CORE;
TRIP FIRST 2-3' TOPSOIL BEFORE EXCAVATING BORROW;
ESTIMATED DEPTH OF 6-7' AFTER REMOVAL OF CLAY MATERIAL
TO BE BACKFILLED WITH WASTE MATERIAL AND COMPACTED,

- EASEMENT BOUNDARY

THIS AREA SHALL BE SLOPED TO
DRAIN TOWARDS THE WETLAND

200TH STREET

PROPOSED 200TH STREET SITE ACCESS

TILE #4 - DAYLIGHT 15"Ø
HDPE DUAL WALL
E:4866533.3880
N:3740536.4073
INV. ELEV. 1195.1'
INSTALL APPROX. 617 L.F. @ 0.14%
SLOPE; PROVIDE 3' MIN. GROUND
COVER OVER PIPE.

#4 - INTERCEPT EXISTING 12" Ø
TILE AND RE-ROUTE W/
Ø HDPE DUAL-WALL PIPE
.14% SLOPE FOR 617 L.F.
IN INVERT ELEV. 1196.00'
LET INVERT ELEV. 1195.1'
ING: 4866643.8385
THING: 3739930.1590

	APPROXIMATE PROPERTY LINE
	PROPOSED DIKE
	PROPOSED CHANNEL/DITCH
	PROPOSED MAJOR CONTOUR
	PROPOSED MINOR CONTOUR
	PROPOSED UNDERGROUND ELECTRIC
	PROPOSED OVERHEAD ELECTRIC
	PROPOSED PIPE
	PROPOSED WATER CONTROL STRUCTURE
	PROPOSED HEADWALL / ENDWALL
	PROPOSED SOIL BORING
	PROPOSED MANHOLE
	PROPOSED SPOT ELEVATION
	PROPOSED FULL SERVICE LEVEL (FSL)
	PROPOSED RIPRAP
	PROPOSED SPOIL AREA
	PROPOSED BORROW AREA
	PROPOSED DITCH
	PROPOSED DIKE

DESIGN CRITERIA			
DESIGN CRITERIA	VALUE	UNIT	REQUIREMENT/NOTES
WATERSHED AREA	626	ACRES	500 MIN.
POOL NORMAL WATER LEVEL (NWL) ELEVATION	1194.1	FT.	
DESIGNED WETLAND POOL AREA (@ NWL)	4.99	ACRES	
PERCENT POOL AREA TO WATERSHED AREA	0.8	%	>=0.50%
MAX. POOL DEPTH	1.2	FT.	
AVG. POOL DEPTH	1.2	FT.	
DEEP WATER AREA (DEPTH >3 FT)	0	ACRES	
PERCENT DEEP WATER TO POOL AREA	0	%	<25%
POOL STORAGE VOLUME AT NWL	7.192	ACRE-FT	
BERM ELEVATION	1198.7	FT.	
POOL STORAGE VOLUME AT TOP OF BERM	55.303	ACRE-FT	
MAX BERM HEIGHT	7.3	FT.	
AVG. BERM HEIGHT	3.3	FT.	
BERM LENGTH	1120	FT.	
PRIMARY WEIR ELEVATION	1194.1	FT.	
PRIMARY WEIR LENGTH	60	FT.	
10-YEAR STORM HWL IN POOL	1196.57	FT.	
10-YEAR PEAK INFLOW	899.34	CFS	
10-YEAR PEAK OUTFLOW	809.43	CFS	
25-YEAR STORM HWL IN POOL	1197.02	FT.	
25-YEAR PEAK INFLOW	1164.43	CFS	
25-YEAR PEAK OUTFLOW	1052.24	CFS	
100-YEAR STORM HWL IN POOL	1197.58	FT.	
100-YEAR PEAK INFLOW	1641.74	CFS	
100-YEAR PEAK OUTFLOW	1505.66	CFS	

WETLAND POOL CHARACTERISTICS			
WETLAND POOL DEPTH (FT.)	ELEV. (FT.)	INCREMENTAL AREA (ACRE)	CUMULATIVE VOLUME (ACRE-FT)
0.0	1192	0	-
1.0	1193	4.360	2.181
2.0	1194	4.690	6.708
2.1	1194.1	4.997	7.192
3.0	1195	5.272	11.813
4.0	1196	7.894	18.396
5.0	1197	12.049	28.368
6.0	1198	16.333	42.559
6.7	1198.7	20.079	55.303

GREAT LAKES/ATLANTIC REGIONAL OFFICE
7322 NEWMAN BOULEVARD, BUILDING 2, STE. 200
DEXTER, MICHIGAN 48130
(734) 623-2000

AFFIX SEAL: DUCKS UNLIMITED, INC.
ON:

SITE PLAN
PROJECT NO. WRI922420D
WRIGHT COUNTY
IOWA

[illegible]

CAD FILE:	
Wright-Peterson-Site Pla	
DESIGNED BY: A.S.	
DRAWN BY: C.K.	
SURVEYED BY: A.S., J.W.	
BIOLOGIST: T.P.	
DATE:	
6-19-24	
PROJECT NUMBER:	
IA-340-8	
C101	

NOT FOR CONSTRUCTION



 7322 NEWMAN BOULEVARD, BUILDING 2, STE. 200
DEXTER, MICHIGAN 48130
(734) 623-2000
www.ducks.org

AFFIX SEAL: DUCKS UNLIMITED, INC.

EMBANKMENT PLAN & PROFILE
PROJECT NO. WRI22420D
WRIGHT COUNTY
IOWA

Revision	Sheet	Revisions	Date	By
1		NRCS/IDALS REVIEW UPDATES	9-19-24	A. S.
CAD FILE: Wright-Peterson-Site Plan				
DESIGNED BY: A.S.				
DRAWN BY: C.K.				
SURVEYED BY: A.S., J.W.				
BIOLOGIST: T.P.				
DATE: 6-19-24				
PROJECT NUMBER: IA-340-8				
C201				

NOT FOR CONSTRUCTION














PROFILE - EMBANKMENT AT PRIMARY SPILLWAY

NOTICE: DRAWING AND INFORMATION IS THE PROPERTY OF DUCKS UNLIMITED, INC. IT MAY NOT BE REPRODUCED FOR ANY PURPOSE WITHOUT THE PRIOR WRITTEN CONSENT OF AN AUTHORIZED AGENT OF DUCKS UNLIMITED, INC. DUCKS UNLIMITED, INC. MAKES NO WARRANTY, REPRESENTATION OR GUARANTEE AS TO THE ACCURACY, COMPLETENESS, RELIABILITY, OR VALIDITY OF THIS MATERIAL, DATA AND INFORMATION. USER SHALL USE OF THE MATERIAL, DATA AND INFORMATION IS AT HIS OR HER SOLE RISK. BY USING ANY OF THIS MATERIAL, DATA AND INFORMATION, USER AGREES THAT DUCKS UNLIMITED, INC. IS NOT RESPONSIBLE FOR THEIR USE OF THE MATERIAL, DATA AND INFORMATION OR THE RESULTS THEREOF. IF IT IS A VIOLATION OF LAW FOR ANY PERSON, UNDER THESE TERMS, TO ALTER OR TRANSMIT IN ANY WAY, IF AN ITEM BEARING THE STAMP OF A LICENSED PROFESSIONAL IS ALtered, THE Altering Engineer, Architect, LANDSCAPE ARCHITECT OR LAND SURVEYOR, AND A SPECIFIC DISCLOSURE OF THE ALTERATION.

(C) Users' Woodbury Ducks Unlimited Incorporated/Woodbury Documents\01A-340-2 CREP PROJECTS\WRIGHT-PETERSON-Site Plan.dwg, 7/9/2026 12:02 PM, Woodbury, C201 Embankment Plan, None

C:\Users\woodbury\Documents\Iowa\02_C3D Projects\IA-340-2 CREP Projects\WRIGHT PETERSON\Site Plan.dwg, 7/9/2026 12:01 PM, Lucas Woodbury, C202 Riprap and Draw-Down Plan, None



GREAT LAKES/ATLANTIC REGIONAL OFFICE
7322 NEWMAN BOULEVARD, BUILDING 2, STE. 200
DEXTER, MICHIGAN 48130
(734) 623-2000


 AFFIX SEAL: DUCKS UNLIMITED, INC.
 ON:

IRIPRAP & DRAW-DOWN PLAN
PROJECT NO. WRI922420D
WRIGHT COUNTY
IOWA

Revision	Sheet	Revisions	Date	By
1		NKCS/IDALS REVIEW UPDATES	9-19-24	A.S.

CAD FILE:

Wright-Peterson-Site Plan

DESIGNED BY: A.S.

DRAWN BY: C.K.

SURVEYED BY: A.S., J.W.

BIOLOGIST: T.P.

DATE:
6-19-24

PROJECT NUMBER:
IA-340-8

C202


NOT FOR CONSTRUCTION

C:\Users\woodbury\Ducks Unlimited Incorporated\Iowa - Documents\Iowa-02_C3D Projects\IA-340-2 CREP PROJECTS\WRIGHT-PETERSON-Site Plan.dwg, 7/9/2026 12:01 PM, Lucas Woodbury, C203 Inlet Channel Plan & Profile, None




NOT FOR CONSTRUCTION

C:\Users\woodbury\Documents\Iowa - Documents\Wright-Peterson-Site Plan.dwg, 7/9/2026 12:00 PM, Lucas Woodbury, C204 Wetland Profiles, None



WETLAND PROFILE #1 - ALONG FLOW PATH

5:1 VERTICAL EXAGGERATION
SCALE: 1" = 50'



WETLAND PROFILE #2 - ACROSS GRADING AREA

5:1 VERTICAL EXAGGERATION
SCALE: 1" = 20'

GREAT LAKES/ATLANTIC REGIONAL OFFICE
7322 NEWMAN BOULEVARD, BUILDING 2, STE. 200
DEXTER, MICHIGAN 48130
(734) 623-2000
www.ducks.org



AFFIX SEAL: DUCKS UNLIMITED, INC.

WETLAND PROFILES
PROJECT NO. WRI922420D
WRIGHT COUNTY
IOWA

	Revision	Sheet	Revisions	Date	By
	1		NRCS/DALS REVIEW UPDATES	9-19-24	A.S.
CAD FILE:					
Wright-Peterson-Site Plan					
DESIGNED BY: A.S.					
DRAWN BY: C.K.					
SURVEYED BY: A.S., J.W.					
BIOLOGIST: T.P.					
DATE: 6-19-24					
PROJECT NUMBER: IA-340-8					
C204					

NOT FOR CONSTRUCTION



C:\Users\woodbury\Ducks Unlimited Incorporated\Iowa - Documents\Iowa\02_C3D Projects\IA-340-2 CREP PROJECTS\WRIGHT-PETERSON\C3D_DRAWING\WRIGHT-PETERSON\C205 Tile 1 Plan & Profile, None



	BIOLOGIST: T.P.
	DATE: 6-19-24
	PROJECT NUMBER:


NOT FOR CONSTRUCTION

C:\Users\woodbury\Documents\Iowa - Documents\Iowa02_C3D Projects\IA-340-2 CREP Projects\WRIGHT-PETERSON-Site Plan.dwg, 7/9/2026 12:00 PM, Lucas Woodbury, C206 Tile 2 Plan & Profile, None

[illegible]



NOT FOR CONSTRUCTION

C:\Users\woodbury\Documents\Iowa - Documents\Iowa Unlimited Incorporated\I02_C3D Projects\IA-340-2 CREP PROJECTS\WRIGHT-PETERSON\C3D_DRAWING\WRIGHT-PETERSON\C207 Tile 3 Plan & Profile, None



NOT FOR CONSTRUCTION

C:\Users\woodbury\Documents\Iowa - Documents\Iowa\02_C3D Projects\IA-340-2 CREP Projects\WRIGHT PETERSON-Site Plan.dwg, 7/9/2026 12:00 PM, Lucas Woodbury, C208 Title 4 Plan & Profile, None



NOT FOR CONSTRUCTION




- PROFILE - SHEET PILE CENTERLINE (N.T.S.)

CAD FILE:
Wright-Peterson-Site Plan
DESIGNED BY: A.S.
DRAWN BY: C.K.
SURVEYED BY: A.S., J.W.
BIOLOGIST: T.P.
DATE: 6-19-24
PROJECT NUMBER: IA-340-8
C301


NOT FOR CONSTRUCTION

[illegible]

C:\Users\woodbury\Documents\Iowa - Documents\Wright-Peterson-Site Plan.dwg, 7/9/2026 12:01 PM, Lucas Woodbury, C302 Construction Details, None



TOE DRAIN; PLACE AS SHOWN ON
EMBANKMENT PLAN VIEW, OR, WHERE
EMBANKMENT IS AT LEAST 3.5' IN HEIGHT



SCORE TRENCH SHALL BE 4' DEPTH
TYPICAL



6.0'



12" SITE PREPARATION

NOT FOR CONSTRUCTION

C:\Users\Woodbury\Documents\Iowa - Documents\Iowa\02_C3D Projects\IA-340-2 CREP Projects\WRIGHT PETERSON\C3D_DRAWING\WCS Details.dwg, 7/9/2026 12:00 PM, Lucas Woodbury, WCS - 1, None



3/16" WALL

2"

6"

1/4"

8"

2 1/2"

2 1/2"

8"

2"

1/4"

1/2"Ø BAR WELDED TO STOPLOGS AS SHOWN
(2 REQ'D PER STOPLOG)

NOTE: 1. WELD 1/2Ø BAR IN STOPLOGS.

2. STOPLOGS SHALL BE 1" SHORTER THAN WIDTH BETWEEN STOPLOG GUIDES.

3. FABRICATOR TO PROVIDE 1-2" & 1-3" STOPLOG IN ADDITION TO STOPLOGS SPECIFIED.


NOT TO SCALE

-
- Technical drawings of a circular culvert cross-section and side view.
- Cross-section view (left):** A circular culvert with diameter C . The wall thickness is t . BOLT SLOTS are 7/16" WIDE and 1" LONG FOR 3/8" SS BOLTS. Dimensions A and B are indicated for the wall thickness.
- Side view (right):** A side view of the culvert showing the WELD ON O.D. OF CULVERT.




BASIC SIZE IN.	ALUM.	O.D. (A) FLANGE	I.D. (B) FLANGE	NO. HOLES	BOLT CIRC. (C)	GASKET NO SECT
6	3/16	10	6	6	8	1
8	3/16	12	8	6	10	1
12	3/16	16	12	14	10	1
15	3/16	19	15	12	17	1
18	3/16	22	18	14	20	1
21	3/16	25	21	16	23	1
24	3/16	28	24	18	26	1
30	3/16	34	30	22	32	2
36	3/16	40	36	26	38	2
42	1/4	46	42	30	44	2
48	1/4	52	48	34	50	2

- NOTES: 1. 6"- 36" FLANGES CUT FROM 3/16 ALUMINUM PLATE.
2. GASKETS DIE CUT FROM 1/8" PVC NITRILE FOAM ENSOLITE AND MATCHED TO CORRESPONDING FLANGE DIMENSIONS (BXD)(E) & NO HOLES.
3. 2 WASHERS PER SLOT.

NOT TO SCALE





NOT TO SCALE




LOCKING ROD SLOT DETAIL

NOT TO SCALE



STOPLOG GUIDE DETAIL

NOT TO SCALE



STOPLOG STORAGE BOX DETAIL

NOT TO SCALE





NOT TO SCALE


NOTE: L1 AND L2 EQUAL HEIGHT OF RISER PLUS 1'
MAX LENGTH FOR EACH 5'. AFTER ADD A SECOND EXTENSION L3
2 PER STRUCTURE

[illegible]


C:\Users\woodbury\Documents\Incorporated\Iowa - Ducks Unlimited Incorporated\Iowa02_C3D Projects\IA-340-2 CREP Projects\WRIGHT PETERSON\C3D_DRAWING\WRIGHT PETERSON\C3D_Filter Dia. Details, None



ELEVATION DETAIL - FILTER DIAPHRAGM




SECTION DETAIL - FILTER DIAPHRAGM




PLAN - FILTER DIAPHRAGM

5:1 VERTICAL EXAGGERATION
SCALE 1" = 10'



SECTION DETAIL - FILTER DIAPHRAGM FILTER ENVELOPE



PROFILE DETAIL - FILTER DIAPHRAGM END SECTION

GREAT LAKES/ATLANTIC REGIONAL OFFICE
7322 NEWMAN BOULEVARD, BUILDING 2, 5TE. 200
DEXTER, MICHIGAN 48130
(734) 623-2000
www.ducks.org

AFFIX SEAL: DUCKS UNLIMITED, INC.
ON:

FILTER DIAPHRAGM DETAILS
PROJECT NO. WRI922420D
WRIGHT COUNTY
IOWA

Revision	Sheet	Revisions	Date	By
1		NRCS/IDALS REVIEW UPDATES	9-19-24	A.S.
CAD FILE: Wright-Peterson-Site Plan				
DESIGNED BY: A.S.				
DRAWN BY: C.K.				
SURVEYED BY: A.S., J.W.				
BIOLOGIST: T.P.				
DATE: 6-19-24				
PROJECT NUMBER: 1A-340-8				
C306				

NOT FOR CONSTRUCTION


C:\Users\woodbury\Documents\Iowa - Ducks Unlimited Incorporated\Iowa02_C3D Projects\UA-340-2 CREP PROJECTS\WRIGHT PETERSON-Site Plan.dwg, 7/9/2026 11:59 AM, Lucas Woodbury, C401 Seeding Plan, None



STRUCTURE SEEDING

BUFFER SEEDING

NOTE:
BUFFER SEEDING: 25.2 ACRES
STRUCTURE SEEDING: 1.1 ACRES



DATE:	6-19-24
PROJECT NUMBER:	IA-340-8

AFFIX SEAL: DUCKS UNLIMITED, INC.
ON:



SEEDING PLAN
PROJECT NO. WRI922420D
WRIGHT COUNTY
IOWA

NOT FOR CONSTRUCTION

WRI922420D Nutrient Reduction Wetland Project
Bid No. 26-05

Attachment No. 3


Revised Technical Specifications booklet dated 07-09-2026

PROJECT SPECIFICATIONS

for

Wri922420D Peterson Project

IA-340-8



July 9, 2026

Prepared by:

Ducks Unlimited, Inc.

I hereby certify that this engineering document was prepared by me or under my direct personal supervision and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.

Andrew Schippers, P.E.

Date

My license number is P26317

My license renewal date is December 31, 2025

Pages of sheets covered by this seal: 1-63

Table of Contents

1. IA CS-001 Site Preparation	3
2. IA CS-005 Pollution Control	5
3. IA CS-006 Seeding and Mulching for Protective Cover	8
4. CS-008 Mobilization and Demobilization	12
5. IA CS-009 Subsurface Drain Investigation, Removal, and Repair	16
6. IA CS-011 Removal of Water	20
7. IA CS-013 Steel Sheet Piling	22
8. IA CS-021 Excavation	24
9. IA CS-023 Earthfill	27
10. IA CS-024 Drainfill (Sand)	32
11. IA CS-026 Topsoiling	35
12. IA CS-031 Concrete	37
13. IA CS-046 Tile Drains for Land Drainage	43
14. IA CS-051 Corrugated Metal Pipe Conduits	47
15. IA CS-061 Loose Rock Riprap	53
16. IA CS-062 Concrete Grout for Riprap	55
17. IA CS-081 Metal Fabrication and Installation	58
18. IA CS-095 Geotextile	60

Construction Specification 000 IA CS-00-1 Site Preparation

1. SCOPE

Site preparation work shall consist of clearing, grubbing, stripping, refuse removal, bank sloping and structure removal on the site as necessary to rid the site of all undesirable materials on or near the surface and prepare the site for the structure. All woody growth within the construction area shall be cleared and all stumps and roots one inch in diameter or larger shall be grubbed from the site. In addition, all areas within 25 feet of the footprint of the structure shall be cleared and grubbed except as directed by the Engineer. The work shall also consist of the removal and disposal of structures (including fences) that must be removed to perform other items of work.

For wetland restoration, enhancement, or creation projects, the wetland area shall be disturbed as little as possible and existing naturally vegetated spillway areas shall not be disturbed.

2. FOUNDATION PREPARATION

The construction areas shall be stripped a minimum of 6 inches to remove all unsuitable materials such as organic matter, grasses, weeds, sod, debris, and stones larger than 6 inches in diameter.

In an earth embankment foundation area, all channel banks and sharp breaks shall be sloped to no steeper than 1.5 horizontal to 1 vertical.

The foundation area shall be thoroughly scarified before placement of fill material. The surface shall have moisture added or shall be compacted if necessary so that the first layer of fill material can be compacted and bonded to the foundation.

3. STRIPPED MATERIAL DISPOSAL

Suitable soil material shall be stockpiled for use as topsoil. The other stripped materials shall be buried, removed from the site, or disposed of as directed by the owner or Engineer. Whenever possible, material shall not be disposed of in the pool area created by the structure.

Stockpiled materials around a construction site should be placed so as not to hinder subsequent construction operations.

4. DISPOSAL OF REFUSE MATERIALS

Waste materials from clearing and structure removal shall be burned or buried at locations approved by the owner. Buried materials shall be covered with a minimum of 2 feet of earthfill. Whenever possible, material shall not be disposed of in any pool area created by the structure.

All refuse shall be disposed of in a manner which complies with all local and state regulations.

5. SALVAGE

Items to be salvaged shall be as shown on the drawings. Structures and fencing materials that are designated to be salvaged shall be carefully removed and neatly placed in the specified storage areas.

6. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Bid Item No. 1 – Stripping

This item will consist of work to remove and dispose of existing material to remove vegetation on areas to be excavated or filled. Total depth of vegetative stripping and topsoil stripping shall equal a combined depth of 12", with the estimated cubic yards of 9,467 topsoil removal as shown in the plans. The topsoil replacement quantity shall be paid separately.

Topsoil stripping areas include but are not limited to below the berm footprint, wetland grading area, inlet channel, and sedimentation basins.

This item will also include any tree and brush removal along with any fences. These shall be considered incidental to site stripping.

This item will be paid out as a lump sum.

2. Bid Item No. 2 – Crop Damage

This item consists of crop damage that results from construction activities. It is recommended contractor remove corn residue rather than knock it down.

Payment for crop damage will be made to the nearest 0.1 acre as measured by the Engineer or their representative. The unit rate for crop damage will be determined by the Division near the completion of construction and added to the contract with a Change Order. Payment will be made to contractor who will pay landowner.

Construction Specification

000 IA CS-005 Pollution Control 2011

1. SCOPE

The work shall consist of installing measures or performing work to control erosion and minimize the production of sediment and other pollutants to water and air during construction operations.

2. MATERIALS

All materials furnished shall meet the requirements shown on the drawings or in the specifications.

3. EROSION AND SEDIMENT CONTROL MEASURES AND WORKS

The measures and works shall include, but are not limited to, the following:

Staging of Earthwork Activities: The excavation and moving of soil materials shall be scheduled so that areas unprotected from erosion will be minimized. These areas will be unprotected for the shortest time feasible.

Seeding: Structures and disturbed areas shall be seeded as soon as possible after construction is completed.

Temporary seedings may be used as an alternative to other stabilization measures as approved by the Engineer and NRCS.

Mulching: Construction areas that have been disturbed but have no construction activity scheduled for 21 days or more shall have erosion protection measures applied by the 14th day. This erosion protection may be mulching or other approved temporary measures. Construction areas shall not be left open during a winter shutdown period and shall be protected by mulching.

All seeding and mulching shall be completed in accordance with the seeding plan and Iowa Construction Specification IA-6, Seeding and Mulching for Protective Cover.

The following works may be temporary. If they are installed as a temporary measure, they shall be removed and the area restored to its original state when they are no longer needed or when permanent measures are installed.

Diversions: Diversions may be required to divert clean runoff water away from work areas and to collect runoff from work areas for treatment and safe disposition.

Stream Crossings: Culverts or bridges may be required where construction equipment must cross streams.

Sediment Basins: Sediment basins may be required to settle and filter out sediment from eroding areas to protect properties and streams below the construction site.

Sediment Filters: Straw bale filters, geotextile sediment fences, or other equivalent methods may be used to trap sediment from areas of limited runoff. Sediment filters shall be properly anchored to prevent erosion under them.

Waterways: Waterways may be required for the safe removal of runoff from fields, diversions, and other structures or measures

4. CHEMICAL POLLUTION

The Contractor shall provide watertight tanks or barrels or construct a sump sealed with plastic sheets to be used to dispose of chemical pollutants, such as drained lubricating or transmission oils, greases, soaps, concrete mixer wash water, asphalt, etc., produced as a by-product of the construction work.

At the completion of the construction work, sumps shall be removed and the area restored without causing pollution.

Sanitary facilities such as chemical toilets or septic tanks shall not be placed adjacent to live streams, wells, or springs. They shall be located at a distance sufficient to prevent contamination of any water sources. At the completion of construction work, facilities shall be disposed of without causing pollution.

5. AIR POLLUTION

The burning of brush or trash or disposal of other materials shall adhere to local and state regulations.

Fire prevention measures shall be taken to prevent the start or the spreading of wild fires, which result from project work. Fire breaks or guards shall be constructed at locations shown on the drawings.

All public access or haul roads used by the contractor during construction of the project shall be sprinkled or otherwise treated to fully suppress dust. All dust control methods shall insure safe operations at all times. If chemical dust suppressants are used, the material shall be a commercially available product specifically designed for dust suppression and the application shall follow manufacturer's requirements and recommendations. A copy of the product data sheet and manufacturer's recommended application procedures shall be provided to the Engineer five working days before use.

6. MAINTENANCE, REMOVAL, AND RESTORATION

All pollution control measures and works shall be adequately maintained in a functional condition as long as needed during the construction operation. All temporary measures shall be removed and the site restored to as near original conditions as practical.

7. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Subsidiary Item - Pollution Control

This item shall consist of applying and performing all construction activities in a manner that will minimize water pollution, air pollution and soil erosion.

No separate payment will be made for Pollution Control. Compensation for this item will be other items as appropriate.

Construction Specification

000 IA-6 Seeding and Mulching for Protective Cover

1. SCOPE

The work shall consist of seeding, mulching, and fertilizing all disturbed areas and other areas as indicated on the drawings or otherwise designated.

2. SEEDBED PREPARATION AND APPLICATION

The entire area to be seeded shall be reasonably smooth and all washes and gullies shall be filled to conform to the desired cross-section before actual seedbed preparation is begun. At this stage of the operation, the required fertilizer and lime shall be applied uniformly and incorporated into the top 3 inches of the soil with suitable tillage equipment. The seedbed preparation operation shall be suspended when the soil is too wet or too dry. The seedbed shall be loosened to a depth of at least three inches.

On side slopes steeper than 2-1/2 horizontal to 1 vertical, the 3 inch minimum depth of seedbed preparation is not required, but the soil shall be worked enough to insure sufficient loose soil to provide adequate seed cover.

Unless otherwise specified, the seeding operation shall be performed immediately after preparation of the seedbed. The seed shall be drilled or broadcast by equipment that will insure uniform distribution of the seed.

3. MATERIALS

The seeding, fertilizing, and mulching requirements are as specified on Form IA-CPA-4.

Straw from cereal grains or hay will be used as mulching material. It shall be relatively free of weeds.

4. MULCH APPLICATION

The required mulching shall be performed as soon as possible after seeding unless otherwise specified. The mulch shall be applied uniformly over the area. The type and rate shall be as specified. When mulching is required, all areas seeded during any one day shall be mulched within 24 hours. The mulch may be spread by any means that results in a uniform cover.

The mulch shall be anchored. Anchoring of the mulch may be performed by a mulch anchoring tool or regular farm disk weighted and set nearly straight, by installation of mulch netting, or by other methods approved by the Engineer.

5. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Bid Item No. 3 – Structure Seeding

This item will consist of hydroseeding the dike except the upstream side slope below the weir elevation, auxiliary spillway, the tile outlet channel side slopes and any other disturbed areas noted on the plans or as determined by engineer.

All seed must be clean and weed free. Seeding rates are expressed in bulk pounds per acre. Seed quality shall not drop below 70% Pure Live Seed (PLS) where PLS = (percent germination plus percent dormant seed) times percent purity.

Seeding rates are as follows:

Smooth Brome grass	25 pounds/acre
--------------------	----------------

Seed shall be applied with a drill and placed at ¼ to ½ inch deep.

Fertilizer shall be applied on the entire seeding area at the following rate:

Nitrogen (N)	30 pound/acre
Phosphorus (P ₂ O ₅)	30 pounds/acre
Potassium (K ₂ O)	40 pounds/acre

Hydro mulch shall be applied at a rate of 2 tons per acre on all areas receiving structure and channel seeding.

Seeding shall be completed during the following seeding periods:

Spring	March 1 to May 15
Summer	August 1 to September 15
Fall	November 15 to Freeze-up

If construction is completed during any other time of the year, the seeding shall be performed at the next seeding period.

If seeding is completed during the spring seeding period, a companion crop of oats shall be seeded at a rate of 1-1/2 bushels per acre.

Measurement will be based on the areas successfully seeded to the nearest 0.1 acre.

2. Bid Item No. 4 – Buffer Seeding

This item will consist of seeding the areas designated on the plans as buffer seeding and include borrow areas, disturbed areas not seeded as part of structural seeding, and other

areas within the easement. Buffer seeding is not required in area below normal pool elevation established by the weir elevation.

Some areas of the site may have existing CRP vegetation or steep slopes with existing vegetation. Local NRCS personnel will determine if these areas will be included as part of the buffer seeding areas for this project or will be left as is. This may affect the bid quantity and Contractor will verify with Engineer the number of acres that will require buffer seeding.

All seed must be clean and weed free. Seeding rates are expressed in pounds of pure live seed per acre. All seed must be yellow-tagged Iowa ecotype unless approved otherwise by IDALS-DSCWQ.

Seeding mixture shall include a minimum of 5 native grasses and 10 native forbs. The mixture shall provide a minimum of 30 grass seeds per square foot and 10 forbs seeds per square foot. Number of seeds will be based on Iowa Conservation Practice 327 "Native Species for Wildlife". Contractor's proposed seed mix shall be submitted to Engineer and local NRCS office for approval at least 2 weeks before seed is to be applied.

Seeding shall be completed during the following seeding periods:

Spring	April 1 to June 30
Fall	November 15 to Freeze-up

The seed bed shall be properly prepared prior to seeding:

- (a) Any weed control measures shall be completed prior to seeding. If spraying is used, then a span of two weeks shall be allowed between spraying and seeding.
- (b) If the land was in soybeans, no additional tillage is required. If the land was in corn or other vegetation, areas to be seeded shall be disked to thoroughly loosen and pulverize the soil to a depth of 3 inches. This may require multiple passes of equipment. If the land was used for pasture and has a smooth surface, the preparation in non-disturbed areas to be seeded shall include mowing any vegetation taller than 12 inches and applying an appropriate herbicide at the labeled rates to emergent growth 2 to 4 weeks after mowing. After the vegetation has died, the area shall be disked thoroughly loosen and pulverize the soil depth of 3 inches. If emergent growth occurs prior to seeding, the areas shall receive a second application of herbicide. Seeding shall not occur until the existing vegetation has died (about 1 week).
- (c) If deeper disking is used at the site, a lighter disk or spring harrow shall be used to remove deep furrows.
- (d) After disking operations and prior to seed application, the seedbed shall be firmed with a cultipacker or similar piece of equipment.
- (e) No lime or fertilizer is to be applied.

Sow seed with contour using a grassland or rangeland drill set for the specified seeding rates. The drill shall be equipped with double coulter furrow openers. The drill shall be subject to acceptance by Engineer. Overlap each successive seeding pass to ensure complete coverage.

Plant seed not more than 1/4 inch deep; some seed may be seen on the surface after seeding.

Broadcasting by centrifugal-type or hydroseeder broadcasters, or by hand shall be allowed in areas not accessible to drills or other equipment. Once broadcast, the seed must be covered with soil to a depth no greater than 1/4 inch by means of hand rakes or other approved methods.

Upon completion of the seeding operation, cultipack the seedbed to provide a positive seed-soil contact. If the drill seeder is equipped with an approved cultipacker or press wheels, separate operations shall not be necessary. The type of cultipacker/seeder to be used shall be subject to acceptance by Engineer.

No mulch shall be required.

Measurement will be based on the area successfully seeded and measured to the nearest 0.1 acre.

3. Subsidiary Item - Weed Control

Weed control may be needed in portions of this site depending upon the start date of the contract, the initiation of grading, and the seeding dates.

Weed control will be added to the contract with a change order to be negotiated between Contractor and Division based on conditions observed and the type of weed control used and will be paid only once. If delays require additional weed control, this will be paid for at Contractor's own expense.

Weed control may include placement of a cover crop such as oats or rye, spraying with appropriate chemicals, or disking. If thistles are present, only spraying is allowed for weed control and shall include appropriate chemicals designed to control thistles.

NATURAL RESOURCES CONSERVATION SERVICE CONSTRUCTION SPECIFICATION

Construction Specification 8—Mobilization and Demobilization

1. SCOPE

The work consists of the mobilization and demobilization of the contractor's forces and equipment necessary for performing the work required under the contract. It does not include mobilization and demobilization for specific items of work for which payment is provided elsewhere in the contract. Mobilization will not be considered as work in fulfilling the contract requirements for commencement of work.

2. EQUIPMENT AND MATERIAL

Mobilization shall include all activities and associated costs for transportation of contractor's personnel, equipment, and operating supplies to the site; establishment of offices, buildings, and other necessary general facilities for the contractor's operations at the site; premiums paid for performance and payment bonds including coinsurance and reinsurance agreements as applicable; and other items specified in section 4 of this specification.

Demobilization shall include all activities and costs for transportation of personnel, equipment, and supplies not required or included in the contract from the site; including the disassembly, removal, and site cleanup of offices, buildings, and other facilities assembled on the site specifically for this contract.

This work includes mobilization and demobilization required by the contract at the time of award. If additional mobilization and demobilization activities and costs are required during the performance of the contract as a result of changed, deleted, or added items of work for which the contractor is entitled to an adjustment in contract price, compensation for such costs will be included in the price adjustment for the item or items of work changed or added.

3. PAYMENT

Payment will be made as the work proceeds, after presentation of paid invoices or documentation of direct costs by the contractor showing specific mobilization and demobilization costs and supporting evidence of the charges of suppliers, subcontractors, and others. When the total of such payments is less than the lump sum contract price, the balance remaining will be included in the final contract payment. Payment of the lump sum contract price for mobilization and demobilization will constitute full compensation for completion of the work.

Payment will not be made under this item for the purchase costs of materials having a residual value, the purchase costs of materials to be incorporated in the project, or the purchase costs of operating supplies.

4. ITEMS OF WORK AND CONSTRUCTION DETAILS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Bid Item No. 5 – Mobilization & Demobilization

This item shall consist of mobilizing and demobilizing personnel and equipment in preparation to perform the work within the scope of this contract.

Any work that is necessary to provide access to the site including, but not limited to, grading, temporary culverts, and clearing will be included in this item. When construction is completed access areas will be restored, as close as practical, to its original condition.

Any fence removed for access and /or to provide work area shall be replaced with same or like materials as approved by the engineer.

The Contractor shall exercise caution to minimize the amount of damage caused by the grading and clearing operations.

Site Access will be located along 200th Street within the easement boundary. All work, permit fees, restoration, and additional costs required to provide this temporary access are the contractors responsibility.

Portable toilets shall be provided at the construction site and used for the sanitary facilities.

This item shall not include transportation of personnel, equipment and operating supplies within the work limits areas of this contract.

Payment will constitute full compensation for related subsidiary item, Pollution Control.

Payment will be made as the work proceeds and will paid out on the percent of the project complete as the work progresses. Payment of the lump sum contract price for mobilization and demobilization will constitute full compensation for the completion of the work.

Contractor is to contact "Iowa One Call" for utility locations a minimum of two (2) days prior to any excavation/construction. The ticket number must be provided to Engineer.



2. Bid Item No. 28 – Septic System Modification

This bid item for septic system modification shall include all material, equipment, and labor necessary for the removal of existing 5" CPP septic line and disconnecting the septic system from the county tile. Removal is limited to the pipe that is located within the easement boundary

This bid item will be paid on a lump sum basis.

3. Subsidiary Item - Sign Installation

This item shall include all labor, materials, equipment and Iowa One Call notifications to install sign provided by Iowa Department of Agriculture and Land Stewardship, as shown on the plans or on next page.



SIGNAGE NOTES:

1. DIVISION WILL FURNISH SIGN PANEL. CONTRACTOR IS RESPONSIBLE FOR PROVIDING POSTS, HARDWARE, AND INSTALLATION .
2. ALL EXPOSED WOOD SHALL BE SEALED WITH THOMPSON'S WATER SEAL OR EQUAL MEETING ASTM D-4446-08.
3. ALL STEEL HARDWARE PIECES SHALL BE GALVANIZED OR RUST RESISTANT.
4. NYLON AND STEEL WASHERS SHALL BE USED AS SHOWN ON THE BOLT, WASHER, NUT FASTENER DETAIL ABOVE.
5. CLEAR UTILITIES WITH IOWA ONE-CALL AT 811 OR (800) 292-8989 BEFORE EXCAVATING FOR POSTS.
6. SECURE DIVISION AND LANDOWNERS APPROVAL FOR SIGN LOCATION BEFORE INSTALLATION.
7. COSTS FOR POSTS, HARDWARE, WOOD SEALANT AND SIGN INSTALLATION SHALL BE INCIDENTAL TO MOBILIZATION.
8. CONTRACTOR SHALL INSTALL SIGN POSTS USING A PLYWOOD OR OTHER SUITABLE TEMPLATE TO MAINTAIN ACCURATE POST SPACING AND ALIGNMENT DURING BACKFILLING OF THE POST HOLES. TO AVOID BENDING OF THE SIGN PANELS, POSTS SHALL NOT BE INSTALLED OR BACKFILLED WITH SIGN PANELS ATTACHED.
9. ONE (1) PROJECT SIGN SHALL BE INSTALLED UNLESS NOTED OTHERWISE.

STANDARD DETAIL FOR SIGN INSTALLATION

DIVISION OF SOIL CONSERVATION AND WATER QUALITY

NATURAL RESOURCES CONSERVATION SERVICE CONSTRUCTION SPECIFICATION

IA-9 SUBSURFACE DRAIN INVESTIGATION, REMOVAL, AND REPAIR

1. SCOPE

The work shall consist of investigation, location, repair, and/or removal of subsurface drains (tile) near new or existing animal waste storage facilities or in wetland restoration, enhancement, or creation project areas, or other situations where subsurface drains may be present.

2. INVESTIGATION AND LOCATION

An inspection trench at least 10 inches wide shall be dug at the location shown on the drawings or as directed by the engineer or his representative. The trench shall be at least 6 feet deep measured from the original ground line, unless otherwise shown on the plans. The Engineer or his representative shall examine the trench and excavated material to identify tile lines.

Size, material, operating condition and direction of flow of each conduit shall be documented. Location and flow line elevation of each conduit shall be surveyed with horizontal and vertical control based on benchmarks shown on the plans.

The inspection trench shall be documented by surveying the natural ground and trench bottom location and elevations at the beginning, end, and every 50 feet for trenches longer than 50 feet.

Backfilling shall not be started without approval of the Engineer. See Section 5 for backfill specifications.

Trench shields, shoring and bracing, or other methods necessary to safeguard the workers and work, and to prevent damage to the existing improvements shall be furnished, placed, and subsequently removed by the contractor.

3. TILE REPAIR

Unless designated for removal, replace damaged conduit with new conduit having equal or greater capacity using material specified in Section 6 or 7. When replacing short sections of clay or concrete tile with single-wall corrugated polyethylene pipe, use the next larger nominal size.

Make connections with manufactured fittings and tight joints. Where joints have gaps that would allow soil to enter, cover the joint with a permanent type material such as coal tar pitch treated roofing paper, fiber glass sheet or mat, or plastic sheet.

If the investigation trench has been excavated below the existing drain grade, backfill the trench with gravel or well-pulverized soil in layers not over four (4) inches thick and tamp by hand or manually directed power tamper to provide a firm foundation for the conduit at the existing grade. Do not backfill with any soil containing broken tile fragments.

Using selected soil free of hard clods, rocks, or frozen soil, hand tamp the backfill material around the haunch of the pipe in layers not over four (4) inches thick to provide support. Hold the conduit in place mechanically while

placing excavated material around and over the conduit to ensure proper alignment and grade is maintained. Complete the backfill operation according to Section 5.

4. TILE REMOVAL

Remove conduits as shown on the plans or directed by the Engineer or his representative, including envelope filter material or other flow enhancing material when present.

Cap or plug the open ends of the disconnected conduit to prevent soil entry when the conduit will continue to function downstream, or otherwise shown on the plans. For a minimum distance of two feet around each sealed conduit end, backfill in layers not over four (4) inches thick and tamp by hand or manually directed power tamper to a density equal to or greater than the surrounding undisturbed soil. Do not backfill with any soil containing broken tile fragments, large stones, frozen material, or large dry clods.

Where tile are located beneath an existing animal waste facility, remove the tile or fill the entire length of tile with concrete or Portland cement grout as shown on the plans. When tile removal is specified, the owner shall contact the Iowa Department of Natural Resources (IDNR) for permission to remove the drainage tile under the structure. The structure shall be emptied of waste or lowered to a point below the tile prior to its removal. The structure must be retested for percolation and the results submitted to IDNR and approval received prior to reusing the structure.

If shown on the plans or directed by the engineer, reroute upstream drain lines so the capacity of the upstream drainage system is maintained. Install conduit in accordance with Iowa Construction Specification IA-46, Tile Drains for Land Drainage.

5. BACKFILL

Compact soil around disturbed tile as specified in Section 3 (Tile Repair) and Section 4 (Tile Removal). Keep the backfill within 5 feet of the conduit free from large stones, frozen material, and large dry clods. Unless otherwise shown on the plans, backfill the remainder of the trench as follows:

For trenches located under or near structures, backfill in 12-inch layers and compact each layer to a density equal to or greater than the surrounding undisturbed soil.

For other locations, backfill the remainder of each trench with the excavated soil material which shall extend above the ground surface and be well rounded over the trench.

6. MATERIALS

Unless otherwise shown on the plans, conduit and fittings used for repair shall conform to the specifications listed in Table 1. Perforated pipe shall have a water inlet area of at least 1 square inch per foot, provided by perforations spaced uniformly along the long axis of the pipe. The perforations shall be circular or slots. Circular perforations shall not exceed 3/16 inch in diameter. Slots shall not be more than 1/8 inch wide.

Table 1. Acceptable pipe for subsurface drain repair

Kind of Pipe[#]	Specification
Corrugated Polyethylene (PE) Pipe and Fittings, 3 to 6 inch	ASTM F 405
Corrugated Polyethylene (PE) Pipe and Fittings, 3 to 24 inch	ASTM F 667
Corrugated Profile Wall (Dual Wall) Polyethylene (PE) pipe, 2 to 60 inch	ASTM F 2648 ^{\$}
Corrugated Profile Wall (Dual Wall) Polyethylene (PE) pipe, 12 to 60 inch	ASTM F 2306 ^{\$}
Polyvinyl Chloride (PVC) Plastic Pipe, Schedules 40, 80 and 120	ASTM D 1785
PVC Pressure-Rated Pipe (SDR Series)	ASTM D 2241
Clay drain tile	ASTM C 4
Concrete drain tile	ASTM C 412

[#]Pipe sizes are nominal and the ranges are inclusive

^{\$}Pipe conforming to AASHTO M 252 (3 to 10 inch), or AASHTO M 294 (12 to 60 inch) is acceptable.

7. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Bid Item No. 6 – Drainage Tile Investigation

This item will consist of the excavation necessary to locate and remove all tile under the embankment and to locate and determine the tie-in locations for the tile locations shown on the plans. This item shall also include backfilling of the trenches.

This item does not include the additional excavation required to excavate the embankment core trench, if included in the project. Excavation of the core trench is covered under Specification IA-21, Excavation.

The extent of the tile investigation shall be as shown on the drawings. If extra work is required to locate additional tile not shown on the drawings, the Contractor can request additional compensation, but it must be first approved by the Division.

The investigation should reveal where the tile crosses the embankment footprint or where it is located if it does not cross the embankment footprint

Payment for Drainage Tile Investigation and removal shall be made as noted in the plans.

Construction Specification 000 IA-11 Removal of Water

1. SCOPE

The work shall consist of the removal of surface water and ground water as needed to perform the required construction in accordance with the plans and specifications.

2. DIVERTING SURFACE WATER

The Contractor shall build, maintain and operate all cofferdams, channels, diversions, flumes, sumps, and other temporary protective works needed to divert surface water away from the construction site while construction is in progress.

3. DEWATERING THE CONSTRUCTION SITE

Foundations, cutoff trenches, borrow areas and other parts of the construction site shall be dewatered as needed for proper execution of the construction work. The Contractor shall furnish, install, operate and maintain all works and equipment needed to perform the dewatering.

4. EROSION AND POLLUTION CONTROL

Removal of water from the construction site, including the borrow areas shall be accomplished in such a manner that erosion and the transmission of sediment and other pollutants are minimized.

5. REMOVAL OF TEMPORARY WORKS

After temporary works have served their purposes and before the Contractor leaves the site, they shall be removed.

6. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Subsidiary Item - Dewatering

This item shall include all costs to divert, pump, dam or other means to dewater the site as needed to complete construction activities.

No separate payment will be made for Removal of Water. Compensation for this item shall be made subsidiary to other bid items requiring removal of water in order to complete.

Construction Specification 000 IA-13 Sheet Piling

1. SCOPE

The work shall consist of furnishing and driving the specified sheet piling at the location shown on the drawings.

2. MATERIALS

Sheet piling shall conform to the requirements of ASTM A328 (Steel Sheet Piling), A572 (High-Strength Low-Alloy Columbium-Vanadium Structural Steel), or A690 (High-Strength Low-Alloy steel H-Piles and Sheet Piling for Use in Marine Environments). The sheet piling provided shall meet the required cross-section, section modulus, thickness, and steel grade shown on the drawings. Fabrication of sheet piles from shorter lengths of pile stock is not permitted.

3. DRIVING SHEET PILE

The piling shall be driven in a manner so as to insure perfect interlocking throughout the entire length of each pile. The piles shall be held in proper alignment during driving by means of suitable temporary guide structures which shall be removed when they have served their purpose.

Piling shall be driven to the full depth shown on the drawings unless otherwise approved by the engineer.

4. CUTTING OFF PILES

The contractor shall cut the piling off at the specified elevations. Piling length shall be sufficient to permit removal of all materials damaged by driving.

5. DEFECTIVE PILING

Any piling damaged in driving, driven out of its proper location, driven below the specified cut off elevation, or inaccurately cut off shall be pulled and replaced or re-driven. Any piling ruptured in the interlock or otherwise damaged during driving shall be pulled and replaced.

6. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Bid Item No. 7 – Steel Sheet Piling

Payment will be made based on the submitted unit price based on the area of sheet pile walls, acceptably placed, computed to the nearest square foot within the neat lines shown on the drawings. Payment will be made at the contract unit price for each type, kind and weight of piling. Such payment will constitute full payment for all labor, materials, equipment and all other items necessary and incidental to the completion of the work.

This item shall consist of furnishing and installing the steel sheet piling shown on the drawings. This item shall include field cutting the side slopes of the sheet piling to the specified slope shown on the drawings along with any damaged portion from driving.

The sheet piling will be installed starting from the center of the weir section and progressing away from centerline.

Sheet piling shall have the requirements specified in the plans.

The sheet pile minimum requirements have been determined for in-place stresses. The Contractor is responsible for making sure the sheet pile provided can be adequately placed without excessive damage based on expected stresses experienced during placement.

Sheet piling shall have the following minimum requirements, unless otherwise approved by the Engineer:

Type: SCZ Piling.
Minimum Section Modulus: 4.4 in³/ft.
Minimum Moment of Inertia: 8.1 in⁴/ft.
Minimum Thickness: 0.25 in.
Minimum Steel Grade: 50 ksi.

Engineer Recommends the following Sheet piling:

Type: SCZ 21N (or approved equal); 28.5" width and 10" height/depth.
Section Modulus: 21.43 in³/ft.
Moment of Inertia: 107.13 in⁴/ft.
Thickness: 0.375 in.
Steel Grade: 50 ksi.

If the contractor chooses to use a different sheet pile than recommended sheet piling, shop drawings are required to be submitted for approval by the engineer.

The sheet pile minimum requirements have been determined for in-place stresses. The Contractor is responsible for making sure the sheet pile provided can be adequately placed without excessive damage based on expected stresses experienced during placement.

2. Subsidiary Item - Steel Pile Cap

Furnishing and Installation of the steel sheet pile cap (See IA-81), including angles, plates, welds, etc. shall be included within this bid item.

Construction Specification 000 IA-21 Excavation

1. SCOPE

The work shall consist of the excavation required by the drawings and specifications and disposal of the excavated materials. The cutoff trench and any other required excavations shall be dug to the lines and grades shown on the drawings or as staked in the field. Structure or trench excavations will conform to all safety requirements of OSHA.

2. USE OF EXCAVATED MATERIALS

Suitable materials from the specified excavations shall be used in the construction of required permanent earth fill. The suitability of materials for specific purposes shall be determined by the Engineer/Inspector.

3. DISPOSAL OF WASTE MATERIAL

All surplus or waste material shall be disposed of in areas shown on the drawings or as approved by the Engineer/Inspector. The waste material shall be smoothed and sloped to provide drainage.

4. STRUCTURE AND TRENCH EXCAVATION

Structure or trench excavations will conform to all safety requirements of OSHA.

5. BORROW EXCAVATION

When the quantities of suitable materials obtained from specified excavations are insufficient to construct the specified fills, additional materials shall be obtained from the designated borrow areas as shown on the drawings or as approved by the Engineer and the landowner. On wetland projects, borrow shall not be taken from the wetland area within 10 feet of the embankment or as shown on the drawings.

Borrow areas shall be excavated and grading completed in a manner to eliminate steep or unstable side slopes or hazardous or unsightly conditions.

6. OVER-EXCAVATION

Excavation beyond the specified lines and grades shall be corrected by filling the resulting voids with compacted earthfill, except that if the earth is to become the subgrade for riprap, sand or gravel bedding or drainfill, the voids shall be filled with material conforming to the specifications for the riprap, bedding or drainfill, as appropriate.

7. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

The volume of excavation as provided in the bid quantities has been determined from the topographic information shown on the Drawings using a computer program. Payment will be made based on the planned quantities provided unless additional excavation is directed by the Engineer. Excavation resulting from the contractor's improper construction operations, as determined by the Engineer, is not included for measurement and payment.

B. Items of Work and Construction Details

1. Bid Item No. 8 – Excavation (General)

This item will consist of excavation and grading of material needed for the following typical items as shown in the plans:

- Core trench
- Establishing pool final grade
- Sedimentation basin(s)
- Inlet/Outlet channel
- Stilling basin(s)

Excavations required for the placement of toe drain, tile exploration, new tile installation, riprap placement, are not included in this bid quantity and will not be measured for payment. The cost of excavation for these items are incidental and should be included as part of their corresponding bid items.

This item does not include the excavation for site stripping or topsoil, which is covered under Specification IA-CS-001. "Site Preparation".

This item includes the hauling of excavated material to be used as earthfill or spoil.

The material excavated with suitable quality shall be used within the dike as directed by engineer.

Suitable excess excavated material shall be disposed of along top of banks for tile outlet channels or in designated areas by Engineer or Engineer's Representative.

See Specification IA-CS-023 for compaction method.

Payment will be based on plan quantity. If unsuitable material is found at the bottom of the core trench, the over excavation shall be measured and paid in a change order.

Payment will constitute full compensation for the following related Subsidiary items: Pollution Control; Removal of Water; and Structure Excavation.

2. Subsidiary Item - Borrow Excavation

This item will consist of excavation of the borrow area for placement of cohesive material in the embankment core and compacted clay liner, if included and as shown in the plans. The cost for excavation and transporting of borrow shall be included in corresponding bid Items listed in Specification IA-CS-023 "Earthfill".

Borrow from any other area will not be allowed unless directed and approved by the Engineer.

The topsoil from the borrow area shall be removed to a minimum depth of 6" and stockpiled. When the borrow operations have been completed, grades shall be returned to that indicated on the plans and the topsoil shall be uniformly spread over the entire borrow area to a depth of 6".

No separate payment will be made for strip or respread of topsoil over borrow area.

3. Subsidiary Item - Structure Excavation

This item shall consist of the excavation necessary to install the steel sheet pile, riprap, corrugated metal pipe (CMP) conduit, CMP tile outlets and water control structure in the locations and as shown on the drawings.

No separate payment will be made for Structure Excavation. Compensation for this item will be included in payment with the corresponding bid items for CMP conduit; CMP water control structure; steel sheet pile; and riprap.

Construction Specification 000 IA-23 Earthfill

1. SCOPE

The work shall consist of the construction of earth fills required by the drawings and specifications. The completed work shall conform to the lines, grades, and elevations shown on the drawings or as staked in the field.

2. MATERIALS

All fill materials shall be obtained from required excavations and designated borrow areas. Fill materials shall contain no sod, brush, roots or other bio-degradable materials. Rocks larger than 6 inches in diameter shall be removed prior to compaction of the fill.

3. FOUNDATION PREPARATION

Foundations for earthfill shall be stripped a minimum of 6 inches to remove vegetation and other unsuitable materials. Foundation surfaces shall be scarified to a minimum depth of 2 inches prior to placing fill material.

Foundation and abutment surfaces shall not be sloped steeper than 1.5 horizontal to 1 vertical unless otherwise shown on the drawings.

4. PLACEMENT

Fill shall not be placed until the required excavation and foundation preparation have been completed and the foundation has been inspected and approved by the Engineer. Fill shall not be placed upon a frozen surface, nor shall snow, ice, or frozen material be incorporated in the fill.

Adjacent to structures or pipes, fill shall be placed in a manner which will prevent damage. The height of the fill adjacent to structures or pipes shall be increased at approximately the same rate on all sides.

The materials used throughout the earth fill shall be essentially uniform. Selective placement shall be as shown on the drawings or approved by the Engineer.

If the surface of any layer becomes too hard and smooth for proper bond with the succeeding layer, it shall be scarified to a minimum depth of 2 inches before the next layer is placed.

The top surfaces of embankments shall be maintained approximately level during construction, except that a cross-slope of approximately 2% shall be maintained to ensure effective drainage.

When moving fill material from the borrow area(s) to the embankment by use of bulldozers only, the following steps shall be followed:

- Immediately after the borrow material is pushed to the embankment, it shall be spread in horizontal lifts placed parallel to the centerline of the embankment.
- Compactive effort will then be applied by operating equipment parallel to the centerline of the fill or embankment.
- Lift thicknesses shall be in strict compliance with Clause 6, below.

Sectional fills are not allowed unless they are shown on the construction drawings.

5. CONTROL OF MOISTURE CONTENT

The moisture content of the fill material shall be adequate for obtaining the required compaction. Material that is too wet shall be dried to meet this requirement, and material that is too dry shall have water added and mixed until the requirement is met.

The moisture content of the fill material shall be such that a ball formed with the hands does not crack or separate when struck sharply with a pencil and will easily ribbon out between the thumb and finger.

Earth foundations under and adjacent to concrete structures shall be prevented from drying and cracking before concrete and backfill are placed.

The application of water to the fill materials shall be accomplished at the borrow areas insofar as possible.

6. COMPACTION

Earth fill shall be compacted by one of the following methods as specified on the plans or in Section 8, Special Specifications. If no method is specified, compaction will be in accordance with Method 1.

- Method 1 - Earthfill shall be placed so that the wheels or tracks of the loaded hauling equipment, traveling in a direction parallel to the centerline of fill, pass over the entire surface of each layer being placed. Low ground pressure vehicles shall not be used for this purpose.
- Method 2 - Two (2) complete passes of a tamping-type roller will be made over each layer. The roller shall be capable of exerting a minimum force of two hundred (200) pounds per square inch.
- Method 3 - Minimum density shall be 90% of the maximum density as determined by ASTM D 698 and as shown on the plans.

The maximum thickness of a lift of fill before compaction shall be 9 inches, unless otherwise indicated on the drawings.

Fill adjacent to structures, pipe conduits, and appurtenances shall be placed in layers not more than 4 inches thick and compacted to a density equivalent to that of the surrounding fill. Methods used to obtain compaction for fine or coarse grained materials are as follows:

- For fine grained materials, hand tamping or manually directed power tampers may be used. Hand compaction only shall be used to compact the earthfill under the bottom half of circular pipes. Manually directed power tampers shall not be used in tight spaces where applying full compactive effort will result in direct contact of the tamper plate with the pipe. Care should be taken so that compaction around the spillway pipe does not cause uplift of the pipe resulting in a void beneath the pipe.
- For coarse grained materials (sands and gravels), vibratory plate compactors shall be used for obtaining compaction. However, hand tamping shall be used to compact the material under the bottom half of circular pipes.

In all cases, follow manufacturer instructions for the specific compaction equipment being used. Heavy equipment shall not be operated within 2 feet of any structure or pipe.

Compacting of fill adjacent to concrete structures shall not be started until the concrete is 7 days old.

7. ISLANDS, MOUNDS, AND LOAFING AREAS ON WETLAND RESTORATION, ENHANCEMENT, OR CREATION PROJECTS

Islands shall be randomly located within the wetland area at locations shown on the drawings or as staked in the field. The orientation of island shorelines shall be random with attention given to prevailing

winds to limit wave damage. In general, the side of the island with the longest dimension shall be parallel to the prevailing wind direction. Side slopes of islands shall be as shown on the drawings, but in no case shall be steeper than 6 horizontal to 1 vertical. Island shapes shall be irregular.

Loafing areas shall be constructed in the areas shown on the drawings or as staked in the field and shall be graded to drain runoff water. The elevation of at least one loafing area should be above the maximum water level whenever possible.

Excavated material not suitable for embankments, wetland dikes, or islands can be used to create mounds or blended into surrounding topography to create a natural appearance. Spoil material shall not be spread on existing wetland areas.

Organic soils shall not be used to construct islands, loafing areas, dikes, or embankments.

8. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

For items of work which specific unit prices are established in the contract, the volume of earthfill will be computed to the nearest cubic yard by the method of average cross-sectional end areas. No deduction in volume will be made for embedded items, such as, conduits inlet structures and their appurtenances. The pay limits for computation shall be as shown on the drawings with the further provisions that earthfill voids resulting from over excavation of the foundation, outside specified lines and grades, will be included in the measurement for payment only under the following conditions:

- Where such over excavation is directed by the engineer to remove unsuitable material, and
- Where the unsuitable condition is not a result of the contractor's improper construction operations as determined by the engineer.

Earthfill beyond the specified lines and grades to backfill excavation required for compliance with OSHA requirements will be considered subsidiary to the earthfill bid item(s).

Payment for each type and compaction class of earthfill and earth backfill is made at the contract unit price for that type and compaction class of earthfill. Such payment will constitute full compensation for all labor, material, equipment, and all other items necessary and incidental to the performance of the work.

Compensation for any item of work described in the contract, but not listed in the bid schedule is included in the payment for the item of work to which it is made subsidiary. Such items and the items to which they are made subsidiary are identified in this specific section.

B. Items of Work and Construction Details

Items of work to be performed in conformance with this specification and the construction details therefore are:

1. Bid Item No. 9 – Earthfill (General)

This item shall consist of the earthfill necessary to construct the submerged berms and additional fill to be placed over the tile to provide adequate cover. Cohesive material found during general grading and compacted liner removal can be used for these areas. Sand and gravel found on site shall not be used for this earthfill.

Compaction shall be Method 1.

Rocks larger than 6" shall be removed prior to compaction.

Payment for these items shall be based on plan quantity unless additional length or location of tile varies from what is shown on the plans. The plan quantity is based on neat lines and does not account for any shrinkage.

Payment will constitute full compensation for the following related Subsidiary items: Pollution Control, Removal of Water, and Backfill Required Excavation.

2. Bid Item No. 10 – Earthfill (General Dam)

This item will consist of earthfill placement and compaction necessary to construct the portion of the embankment that is not considered part of the embankment core. Cohesive material found during general grading and compacted liner removal can be used for this area. Sand and gravel found on site shall not be used for fill for these items

Compaction shall be Method 1.

Rocks larger than 6" shall be removed prior to compaction.

Payment for this item shall be based on plan quantity. The plan quantity is based on neat lines and does not account for any shrinkage.

Payment will constitute full compensation for the following related Subsidiary items: Pollution Control, Removal of Water, and Backfill Required Excavation.

3. Bid Item No. 11 – Earthfill (Dam Core)

This item will consist of earthfill placement and compaction necessary to construct the portion of the embankment designated the embankment core, including the core trench. Cohesive material taken from the designated borrow area should be used for this area. Sand and gravel found on site shall not be used for fill for these items.

Compaction shall be Method 2.

Rocks larger than 6" shall be removed prior to compaction.

Payment for this item shall be based on plan quantity. The plan quantity does include a shrinkage value of 25%.

Payment will constitute full compensation for the following related Subsidiary items: Pollution Control, Removal of Water, and Backfill Required Excavation.

4. Subsidiary Item - Backfill Required Excavation

This item shall consist of backfilling the areas excavated to install the other components related to the project such as piping or structures and to locate and remove the tile lines.

Compaction adjacent to the structures shall be as indicated above. All other compaction shall be Method 1 or equivalent.

No separate payment will be made for Backfill of Structure Excavation. Compensation for this item will be included in payment for Corrugated Metal Pipe; CMP Drawdown Structure; Riser Inlet Structure, Tile Investigation and Removal and Dual Wall HDPE.

Construction Specification 000 IA-24 Drainfill

1. SCOPE

The work shall consist of furnishing and placing drainfill required in the construction of structure drainage systems and filter diaphragms around conduits.

2. MATERIALS

Drainfill shall be sand, gravel, or crushed stone. It shall be composed of clean, hard, durable mineral particles free from organic matter, clay balls, soft particles, or other substances that would interfere with their free-draining properties. Aggregates of crushed limestone may be used only for coarse drainfill but shall be thoroughly washed and screened so that not more than 3 percent by weight is finer than a No. 4 sieve.

Coarse drainfill shall be graded as follows:

U.S. Sieve Designation	Percent Passing Sieve
1 1/2	100
3/4	75-100
1/2	25-80
3/8	20-60
No. 4	0-10
No. 8	0-5
No. 100	0-3

Fine drainfill shall be graded as follows:

U.S. Sieve Designation	Percent Passing Sieve
3/8	100
No. 4	95-100
No. 8	75-95
No. 16	50-70
No. 30	25-50
No. 50	10-20
No. 100	0-6
No. 200	0-3

3. BASE PREPARATION

Foundation surfaces and trenches shall be free of organic matter, loose soil, foreign substances, and standing water when the drainfill is placed.

4. PLACEMENT

Drainfill shall not be placed until the trench excavation has been inspected and approved by the Engineer. Installation of the drainage conduit shall be inspected and approved by the Engineer before covering it

with drainfill. No foreign materials shall be allowed to become intermixed with or otherwise contaminate the drainfill. Drainfill material shall be placed in a manner to avoid segregation of particles by size.

5. COMPACTION

1. Foundation Trench Drain
 - a. No compaction will be required beyond that resulting from the placing and spreading operations.
2. Filter Diaphragm
 - a. Each layer of sand material shall be flooded with clean water prior to compaction.
 - b. Compaction shall be accomplished while the material is wet from step (1) above.
 - c. Each layer shall be compacted by a minimum of 2 passes of a hand directed vibratory plate compactor over the entire layer surface.
 - d. Layer thickness shall not exceed 12 inches after compaction.
3. Filter Diaphragm Outlet
 - a. Sand material shall be placed so the layer thickness does not exceed 4 inches after compaction.
 - b. Each layer shall be compacted by a minimum of 2 passes of a hand directed vibratory plate compactor over the entire layer surface.

6. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Bid Item No. 12 - Drainfill

This item is part of the construction of the toe drains, including backfill with material meeting the requirements of fine drainfill, as shown in the plans. However, payment for the excavation, furnishing and installation of the toe drain(s), is covered under the listed bid items in Specifications IA-CS-046.

Measurement and payment shall be on a plan quantity. Plan quantity listed in the proposal will be used to measure and pay for the bid.

Payment will constitute full compensation for the following related subsidiary items: Site Preparation and Pollution Control.

2. Subsidiary Item - Filter Diaphragm

The filter diaphragm and diaphragm outlet shall consist of material meeting the Fine Drainfill requirements, except for the end of the diaphragm outlet, where Coarse Drainfill is shown on the plans.

The cost to excavate the portion needed for the filter diaphragm and placement of Fine and Coarse Drainfill material in the diaphragm and diaphragm outlet are considered incidental and shall be included with the cost of installing the wetland drawdown outlet pipe.

Construction Specification 000 IA-26 Topsoiling

1. SCOPE

The work shall consist of salvaging topsoil from borrow areas or required excavations and spreading it on the exposed disturbed areas.

2. QUALITY OF TOPSOIL

Topsoil shall consist of friable surface soil reasonably free of grass, roots, weeds, sticks, stones, or other foreign materials.

3. EXCAVATION

After the site has been cleared and grubbed, the topsoil shall be removed from borrow areas and required excavation areas to the depth as shown on the drawings. Topsoil shall be stockpiled at locations approved by the Engineer.

4. SPREADING

Spreading shall not be done when the ground or topsoil is frozen, excessively wet, or otherwise in a condition detrimental to the work. Surfaces designated to be covered shall be lightly scarified just prior to the spreading operation. Where compacted fills are designated to be covered by topsoil, the topsoil shall be placed concurrently with the fill and shall be bonded to the compacted fill with the equipment.

Topsoil shall be placed to the minimum depth shown on the drawings. After the spreading operation is completed, the surface shall be finished to a reasonably smooth surface.

5. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Bid Item No. 13 – Topsoil Placement

This item will consist of spreading salvaged and stockpiled topsoil as the surface layer of all excavations and earthfills that will be seeded. Topsoil shall be placed as final lift.

Areas to receive a minimum of 6-inch layer of topsoil include areas of the embankment that are do not have riprap, borrow area and additional fill placed over new tile and any other areas noted in the plans.

Measurement and payment for Topsoiling shall be on a plan quantity. Plan quantity listed in the proposal will be used to measure and pay for the bid.

Grading areas with less than 6 inches of cut will not require topsoil resspreading unless required by engineer.

Payment will constitute full compensation for the following related subsidiary items: Site Preparation and Pollution Control.

Construction Specification 000 IA-31 Concrete

1. SCOPE

The work shall consist of furnishing, forming, placing, finishing, and curing Portland cement concrete including steel reinforcement.

2. MATERIALS

Portland Cement shall conform to ASTM C 150 and shall be Type I or Type II.

Fine Aggregates shall conform to ASTM C 33 and shall be composed of clean, uncoated grains of material.

Coarse Aggregates shall be gravel or crushed stone conforming to ASTM C 33 and shall be clean, hard, durable and free from clay or coating of any character. The maximum size of coarse aggregate shall be 1 1/2 inches or as shown on the drawings.

Water shall be clean and free from injurious amounts of oil, acid, salt, alkali, organic matter, or other deleterious substances.

Air entraining agent shall conform to ASTM C 260.

Fly ash may be used as a partial substitution for Portland cement and shall be in strict compliance with ASTM C 618, Class F or C. The loss by ignition shall not exceed 4.0 percent.

Blast-furnace slag may be used as a partial substitution for Portland cement and shall be in conformance with ASTM C 989 for ground granulated blast-furnace slag (GGBF slag).

Water-reducing admixtures shall conform to ASTM C 494 and may be the following types:

1. Type A - Water-reducing admixture
2. Type D - Water-reducing and retarding admixture
3. Type F - Water-reducing, high range admixture (superplasticizer).
4. Type G - water-reducing, high range, and retarding admixture (superplasticizer).

Type D or G admixture may be used when the air temperature is over 80 degrees F. at the time of mixing and/or placement.

Calcium Chloride or other antifreeze compounds or accelerators will not be allowed.

Preformed expansion joint filler shall be a commercially available product made of bituminous, sponge rubber or closed cell foam materials with a minimum thickness of 1/2 inch.

Reinforcing steel shall be free from loose rust, oil, grease, paint, or other deleterious matter. Reinforcing steel shall conform to one or more of the following:

1. Reinforcing Bars - ASTM A 615 or A 996, Grade 40 or greater, deformed.
2. Welded Wire Fabric - ASTM A 185 or A 497.

Waterstops shall be either metallic or nonmetallic. Metallic waterstops shall be fabricated from sheets of copper or galvanized steel. Nonmetallic waterstops shall be made of natural or synthetic rubber or vinyl chloride polymer or copolymer. Rubber, polymer and copolymer waterstops shall have ribbed or bulb-type

anchor flanges and a hollow tubular center bulb, unless otherwise shown on the drawings. All waterstops shall be of the sizes shown on the drawings.

Curing compound shall be a liquid membrane-forming compound suitable for spraying on the concrete surface. The curing compound shall meet the requirements of ASTM C 309 Type 2 (white pigmented).

3. CONCRETE DESIGN MIX

The contractor will be responsible for the determining the design mix proportions in accordance with the requirements included in this paragraph and shall provide a copy of the mix to the Engineer at Natural Resources Conservation Service least 3 days prior to placing any concrete. The concrete mix shall be of such proportions as to provide a minimum strength of 3500 p.s.i. in 28 days, unless otherwise shown on the drawings. The air content shall be 4 to 8 percent of the volume of the concrete at the time of placement. The slump shall be 2 to 5 inches except when superplasticizer is used. The slump shall be 3 inches or less prior to the addition of superplasticizer admixture and shall not exceed 7 1/2 inches following addition and mixing. The fine aggregate shall be 30-50 percent of the total combined aggregate based on oven dry weights. The contractor shall provide tests to verify that the design mix meets the requirements. In lieu of this, one of the following mix proportions per cubic yard may be used:

Mix Number	Minimum Cement, Pounds	Fly Ash, Pounds	GBF Slag, Pounds	Maximum **Water, Gallons
1	564	0	0	33
2	470	45-90	0	31-34
3	517	129	0	31*
4	366	114	91	31*
5	259	103	155	31*
** Total of available aggregate moisture, mixing water added at the plant and mixing water added at the job site (one gallon equals 8.33 pounds).				
* Requires water reducing admixture.				

4. MIXTURES AND MIXING

Ready-mixed concrete shall be batched, mixed and transported in accordance with ASTM C 94. Concrete shall be uniform and thoroughly mixed when delivered to the forms. No mixing water in excess of the amount shown for the design mix or in an amount that would cause the maximum slump to be exceeded shall be added to the concrete during mixing, hauling or after arrival at the point of delivery. The concrete shall be batched and mixed so that the temperature of the concrete at the time of placing shall be between 50 and 90 degrees F.

5. BATCH TICKET

The contractor shall obtain from the supplier a delivery ticket for each batch of concrete before unloading at the site. The following information shall be included on the ticket: name of concrete supplier, job name or location, date, truck number, amount of concrete, time loaded or time of first mixing cement, aggregate, and mixing water added at the plant, type and amount of cement, type and amount of admixtures, oven dry weights of fine and coarse aggregate, and moisture content(%) or weight of water contained in the aggregates.

The following information shall be added to the batch ticket on site: mixing water added on site, time concrete arrived on site and time concrete was unloaded.

Upon completion of the concrete placement, copies of all batch tickets shall be provided to the Engineer.

6. REINFORCING STEEL

Before reinforcement is placed, the surfaces of the bars or mesh shall be cleaned to remove any loose, flaky rust, mill scale, oil, grease, or other foreign substances. After placement, the reinforcement shall be maintained in a clean condition until it is completely embedded in the concrete.

Reinforcing bars shall be cut and bent according to ACI Standard 315.

Tack welding of bars shall not be permitted. Reinforcement shall be accurately placed as shown on the drawings and secured in position in a manner that will prevent its displacement during placement of concrete. Metal chairs, metal hangers, metal spacers or concrete chairs shall be used to support reinforcement. Precast concrete chairs shall be manufactured from concrete equal in quality to the concrete being placed. Precast concrete chairs shall be moist at the time concrete is placed

Splices of reinforcing bars shall be made only at the locations shown on the drawings, unless otherwise approved by the Engineer. All reinforcing splices and placement shall be in accordance with ACI 318 and as shown on the drawings.

After placement of the reinforcement, concrete shall not be placed until the reinforcement has been inspected and approved by the Engineer.

7. PREPARATION OF FORMS AND SUBGRADE

Prior to placement of concrete, the forms and subgrade shall be free of woodchips, sawdust, debris, water, ice, snow, extraneous oil, mortar, or other harmful substances or coatings. Any oil on the reinforcing steel or other surfaces required to be bonded to the concrete shall be removed. All surfaces shall be firm and damp prior to placing concrete. Placement of concrete on mud, dried earth, uncompacted fill, or frozen subgrade will not be permitted.

The forms and associated false-work shall be substantial and unyielding and shall be constructed so that the finished concrete will conform to the specified dimensions and elevations. Forms will be mortar tight. Forms with torn surfaces, worn edges, dents or other defects will not be used. Forms shall be coated with a nonstaining form release agent before being set into place. Excess form coating material shall not stand in puddles in the forms or come in contact with the steel reinforcement or hardened concrete against which fresh concrete is to be placed.

Form accessories to be partially or wholly embedded in the concrete, such as ties and hangers, shall be of a commercially manufactured type. Non fabricated wire shall not be used. Form ties shall be constructed so that the ends or end fasteners can be removed without causing spalling at the surface of the concrete.

Metal form ties used within the forms on structures with a total volume of concrete exceeding fifteen cubic yards shall be equipped with cones or other devices that permit their removal to a depth of at least one inch without damage to the concrete. The holes resulting from cones and other devices shall be patched in accordance with Section 9.

Form ties except those specifically covered by the preceding paragraph shall be broken off flush with the formed surface. Any surface areas which have been spalled or otherwise damaged shall be repaired in accordance with Section 9.

Steel tying and form construction adjacent to new concrete shall not be started until concrete has cured at least 12 hours.

Concrete joints shall be of the type and at the locations shown on the drawings. Splices in metal waterstops shall be brazed, welded or overlapped and bolted.

Splices in nonmetallic waterstops shall be cemented or joined as recommended by the manufacturer.

8. PLACING CONCRETE

Concrete shall not be placed until the subgrade, forms, and steel reinforcement have been inspected and approved by the Engineer/Inspector. Any deficiencies are to be corrected before the concrete is delivered for placement.

Concrete shall be delivered to the site and discharged into the forms within 1 1/2 hours after the introduction of the cement to the aggregates. When a superplasticizer is used, the concrete shall be discharged within the manufacturer's recommended time limit for discharge after addition of the admixture. In hot weather or under conditions contributing to quick setup of the concrete, discharge of the concrete shall be accomplished in 45 minutes unless a set-retarding admixture is used, in which case the manufacturer's recommended time limit will apply.

Addition of water at the job site may be done at the beginning of placement of each load of concrete in order to obtain allowable slump, provided that the maximum water content and water/cement ratio in the design mix is not exceeded. Addition of water will not be permitted after placement of the load has started.

The concrete shall be deposited as closely as possible to its final position in the forms and shall be worked into corners and around reinforcement and other embedded items in a manner which prevents segregation. Formed concrete shall be deposited in layers 24 inches or less in depth and shall be continuously deposited so that no concrete will be deposited on concrete which has hardened sufficiently to cause the formation of "cold joints". Concrete containing superplasticizer shall be placed in lifts not exceeding 5 feet in depth. If the surface layer of concrete sets during placement to the degree that it will not flow and merge with the succeeding layer when tamped or vibrated, the contractor shall discontinue placing concrete and install a construction joint. Construction joints shall be completed as shown on the drawings or by one of the following methods:

1. The joint shall be constructed using a 6 inch wide by 1/4 inch steel plate. The surfaces of the construction joint shall be prepared by washing and scrubbing with a wire brush or wire broom to expose coarse aggregate. The steel plate shall be embedded 3" in the concrete.
2. The joint surface shall be cleaned to expose coarse aggregate by sandblasting or air-water cutting after the concrete has gained sufficient strength to prevent displacement of the coarse aggregate or cement fines. The surface of the concrete shall not be cut so deep as to undercut the coarse aggregate. The joint shall be washed to remove all loose material after cutting.

The surfaces of all construction joints shall be kept continuously moist for at least 1 hour prior to placement of the new concrete. The new concrete shall be placed directly on the cleaned and washed surface. New concrete shall not be placed until the hardened concrete has cured at least 12 hours.

Concrete shall not be dropped more than 5 feet vertically unless suitable equipment is used to prevent segregation. Concrete containing superplasticizer shall not be dropped more than 12 feet vertically.

Immediately after the concrete is placed in the forms, it shall be consolidated by vibration, spading or hand tamping as necessary to insure smooth surfaces and dense concrete. Care should be taken not to over-vibrate concrete containing superplasticizer. Vibration shall not be supplied directly to the reinforcing steel, the forms or concrete which has hardened to the degree that it does not insure a monolithic bond with the preceding layer. The use of vibrators to transport concrete in the forms or conveying equipment will not be permitted.

9. FORM REMOVAL AND FINISHING

Forms shall be left in place for at least 24 hours after placing concrete. Forms shall be removed in such a way as to prevent damage to the concrete. Supports shall be removed in a manner that will permit concrete to take the stresses due to its own weight uniformly and gradually.

Immediately after removal of the forms, concrete which is honey combed, damaged or otherwise defective shall be repaired or replaced. All cavities or depressions resulting from form tie removal shall be patched with a non-shrink grout, mortar mix or epoxy-type sealer. Non-shrink grout consists of 1 part cement and 2-1/2 parts sand that will pass a No. 16 sieve. Only enough water shall be added to produce a filling which is at the point of becoming rubbery when the material is solidly packed.

All repaired and patched areas shall be cured as required in Section 10.

10. CURING

Concrete shall be cured for a period of not less than 7 consecutive days by one of the following approved methods:

1. **Membrane Curing:** Concrete shall be cured with white pigmented curing compound. The compound shall be sprayed on moist concrete as soon as free water has disappeared, but shall not be applied to any surface until patching, repairs and finishing of that surface are completed. Curing compound shall not be applied to surfaces requiring bond to subsequently placed concrete, such as construction joints, shear plates, reinforcing steel, and other embedded items. Surfaces subjected to heavy rainfall or running water within 3 hours after curing compound has been applied or surfaces damaged by subsequent construction operations during the curing period, shall be reapplied in the same manner as the original application.
2. **Moist Curing:** Concrete shall be cured by maintaining all surfaces continuously wet for the entire curing period.
3. **Cover:** Adequately cover an exposed structure with burlap mats, or other material and continually soak with water.

11. BACKFILLING

Backfilling may begin when the curing period has ended. Backfill against the structure will be placed in no more than 4-inch layers and compacted by hand tamping or with manually directed power tampers or plate vibrators. Layers compacted in this manner shall extend not less than 2 feet from any part of the concrete structure.

12. HOT AND COLD WEATHER CONCRETING

When the atmospheric temperature may be expected to drop below 40° F. at the time concrete is delivered to the work site, during placement, or at any time during curing period, concrete shall be mixed, placed and protected in accordance with ACI Standard 306, "Recommended Practice for Cold Weather Concreting."

When climatic or other conditions are such that the temperature of the concrete may reasonably be expected to exceed 90° F. at the time of delivery to the work site, during placement or during the first 24 hours after placement, concrete shall be mixed, placed and protected in accordance with ACI Standard 305, "Recommended Practice for Hot Weather Concreting."

13. SPECIFIC SITE REQUIREMENTS

- A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Subsidiary Item - Concrete

This item shall consist of all necessary concrete, reinforcing steel, formwork, materials, and labor to place poured concrete and reinforced concrete as shown in the drawings including, but not limited to, the Water Control Structure(s) and concrete collars around pipe connections.

No separate payment will be made for Concrete. Compensation for this item will be included in the payment for the Water Control Structure and Tile Installation.

However, concrete structures that meet the Iowa Statewide Urban Design and Specifications (SUDAS), will be paid as discussed below.

**NATURAL RESOURCES CONSERVATION SERVICE
CONSTRUCTION SPECIFICATION**

IA-46 TILE DRAINS FOR LAND DRAINAGE

1. SCOPE

The work shall consist of furnishing and installing drainage tubing and tile and the necessary fittings and appurtenances.

2. MATERIALS

Concrete drain tile shall conform to the requirements of ASTM C 412 and clay drain tile shall conform to the requirements of ASTM C 4.

Corrugated polyethylene (PE) pipe (tubing) and fittings shall conform to ASTM F 405 (3" to 6") or F 667 (3" to 24"), as appropriate. Corrugated profile wall (dual wall) polyethylene (PE) pipe shall meet or exceed the requirements of ASTM F 2648 (2" to 60") or ASTM F 2306 (12" to 60"). Pipe conforming to AASHTO M 252 (3" to 10") or AASHTO M 294 (12" to 60") is acceptable. Perforated tubing shall have a water inlet area of at least 1 square inch per foot, provided by perforations spaced uniformly along the long axis of the tubing. The perforations shall be circular or slots. Circular perforations shall not exceed 3/16 inch in diameter. Slots shall not be more than 1/8 inch wide.

3. EXCAVATION

Unless otherwise specified, excavation for and subsequent installation of each drain line shall begin at the outlet end and progress upstream.

The trench or excavation for the tile shall be constructed to the line, depths, cross sections, and grade shown on the drawings or as directed by the Engineer/Inspector. The trench bottom shall be smooth and free of exposed rock. If rock is encountered in the trench bottom, over-excavate the trench and place at least 6 inches of compacted earth or sand bedding in the trench to bring it up to the conduit grade.

If not otherwise shown on the drawings, trench width at the top of the conduit shall be the minimum required to permit installation and provide bedding conditions suitable to support the load on the conduit, but with not less than three (3) inches of clearance on each side of the conduit. Maximum trench width shall be the conduit diameter plus 12 inches measured at the top of the conduit, unless approved bedding is installed.

Trench shields, shoring and bracing, or other methods, necessary to safeguard the workers and work, and to prevent damage to the existing improvements shall be furnished, placed, and subsequently removed by the contractor.

Plow installation is allowed. Minimum trench width shall be two (2) inches wider than the conduit on each side. Grade control and bedding conditions shall be closely inspected during plow installation. Boulders, cobbles, or cemented soil can cause the plow to jump or lose grade. These hardpoints can also puncture or dimple and deform the pipe.

4. PREPARING THE BEDDING

Unless otherwise specified, no filter or envelope is required. In stable soils the bottom of the trench shall be shaped to form a semicircular, trapezoidal, or 90 degree "V" groove in its center. The groove shall be shaped to fit the size of tile. The 90-degree "V" groove shall not be used on conduits greater than 6 inches in diameter.

If the bottom of the trench does not provide a sufficiently stable or firm foundation for the drain tile, a sand-gravel mix or other approved materials shall be used to stabilize the bottom of the trench.

5. FILTER OR ENVELOPE MATERIAL

When a filter is specified, the shape of the bottom of the trench, gradation and the thickness of the filter or envelope material to be placed around the tile will be as shown on the drawings. The envelope or filter material shall be placed in the bottom of the trench just prior to the laying of the tile. The tile shall then be laid and the envelope or filter material placed over the tile.

6. PLACEMENT AND JOINT CONNECTIONS

All drains shall be laid to grade.

Joints between lateral drain tile shall vary with soil type as follows:

- a. Peat and muck - 1/4 inch preferred, 3/8 inch maximum
- b. Clay - 1/8 inch preferred, 1/4 inch maximum
- c. Silt and loam - 1/16 inch preferred, 1/8 inch maximum
- d. Sand - tightest possible fit.

Joint between main drain tile which serve only to collect and transport drainage water from lateral tile lines should be the tightest fit possible.

Where the joint width exceeds the maximum above, the joint shall be covered with a permanent type material such as coal tar pitch treated roofing paper, fiber glass sheet or mat, or plastic sheet.

After placement and blinding of plastic tubing, but prior to backfilling, sufficient time shall elapse to allow the tubing to reach the ambient temperature of the trench. All split fittings shall be securely tied with nylon cord before backfill is placed. When corrugated plastic tubing is used, no more than 5% stretch will be allowed.

7. CONNECTIONS

Lateral connections will be made with manufactured appurtenances (wyes, tees, etc.) comparable in strength and durability with the specified tile or tubing unless otherwise shown on the drawings.

Existing tile lines not shown on the drawings but encountered during installation shall be bridged across the trench or connected into the new line, as directed by the Engineer.

Connections with the outlet pipe shall be made watertight.

8. OUTLETS

A continuous section of non-perforated conduit at least 20 feet long shall be used at the outlet. At least two-thirds of the outlet pipe shall be buried in the ditch bank, and the cantilever section must extend to the toe of the ditch side slope or the side slope protected from erosion. Acceptable materials for use at the outlet include the following:

- a. Corrugated metal pipe, galvanized or aluminum, 16 gauge minimum;
- b. Smooth steel pipe with a minimum wall thickness of 3/16 inch;
- c. Smooth plastic pipe, polyvinyl chloride (PVC), with a SDR of 26 or less or schedule 40 or heavier; or
- d. Corrugated profile wall (dual wall) polyethylene pipe (PE).

All plastic (PVC) and polyethylene pipe (PE) outlets shall include ultra-violet stabilizer. PVC or PE pipe outlets shall not be used where burning vegetation on the outlet ditch bank is likely to create a fire hazard.

The outlet shall be equipped with a flap-gate type rodent guard.

9. BLINDING

After the tubing or tile is placed in the excavated groove, friable material from the sides of the trench shall be placed around the tubing, completely filling the trench to a depth of not less than three inches over the top of the tubing. For material to be suitable it must not contain hard clods, rocks, frozen soil, or fine material which will cause a silting hazard to the drain. Tubing placed during any one day shall be blinded by the end of the day's work.

10. BACKFILLING

The backfilling of the trench shall be completed as rapidly as consistent with the soil conditions. Automatic backfilling machines may be used. Backfill shall extend above the ground surface and be well rounded over the trench.

Unless otherwise shown on the plans, in mineral soils, the minimum cover over subsurface drains shall be 2.4 feet. In organic soils, the minimum depth of cover after initial subsidence shall be 3.0 feet.

11. SPECIAL SPECIFICATIONS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Bid Item No. 15 – 8"Ø HDPE Dual-Wall

This item will consist of furnishing and installing 8"Ø corrugated profile wall (Dual wall) Polyethylene pipe (non-perforated) used as a drain tile as shown on the drawings.

Measurement and payment for the corrugated profile wall (Dual wall) Polyethylene pipe shall be on an installed linear foot basis, and shall include all necessary fittings and adapters.

Payment will also include all subsidiary items required for installation such as trench excavations, backfill, site preparation, and removal of water, and concrete collar at joint. Additional fill required to provide adequate cover as needed is included in Earthfill, General.

2. Bid Item No. 16 – 15"Ø HDPE Dual-Wall

This item will consist of furnishing and installing 15"Ø corrugated profile wall (Dual wall) Polyethylene pipe (non-perforated) used as a drain tile as shown on the drawings.

Measurement and payment for the corrugated profile wall (Dual wall) Polyethylene pipe shall be on an installed linear foot basis, and shall include all necessary fittings and adapters.

Payment will also include all subsidiary items required for installation such as trench excavations, backfill, site preparation, and removal of water, and concrete collar at joint. Additional fill required to provide adequate cover as needed is included in Earthfill, General.

3. Bid Item No. 17 – 18"Ø HDPE Dual-Wall

This item will consist of furnishing and installing 18"Ø corrugated profile wall (Dual wall) Polyethylene pipe (non-perforated) used as a drain tile as shown on the drawings.

Measurement and payment for the corrugated profile wall (Dual wall) Polyethylene pipe shall be on an installed linear foot basis, and shall include all necessary fittings and adapters.

Payment will also include all subsidiary items required for installation such as trench excavations, backfill, site preparation, and removal of water, and concrete collar at joint. Additional fill required to provide adequate cover as needed is included in Earthfill, General.

4. Bid Item No. 20 – Stoplog Storage Structure

This item will consist of furnishing and installing a vertical section of non-perforate dual wall corrugated polyethylene pipe as shown on the drawings. This bid item shall include the gravel base, metal lid, and lock. Excavation and backfill needed for installation is incidental to this bid item.

Measurement and payment will be based on lump sum provided in the contract documents.

5. Bid Item No. 14 – Toe Drain

This item will consist of furnishing and installing perforated corrugated polyethylene tubing used as a toe drain, as shown on the drawings. Drainfill (fine) backfill around the toe drain shall be paid under a separate bid item (See IA-24). The metal outlet shall be paid under a separate bid item (See IA-51).

Measurement and payment for this pipe shall be on an installed linear foot basis, and shall include all necessary fittings and adapters.

Payment will also include all subsidiary items required for installation such as trench excavations, site preparation, removal of water, and concrete collar at joint.

Construction Specification

000 IA-51 Corrugated Metal Pipe Conduits

1. SCOPE

The work shall consist of furnishing and placing circular, arched or elliptical corrugated metal pipe and the necessary fittings.

2. MATERIALS

Metallic-coated steel corrugated pipe and fittings shall be zinc-coated or aluminized, Type 2, and shall conform to the requirements of ASTM A 760 and A 929 for the specified type and size of pipe. Aluminum corrugated pipe shall conform to the requirements of ASTM B 745 for the specified type and size of pipe. All pipe is subject to the following additional requirements:

1. When polymer coating is specified, pipe, coupling bands and anti-seep collars shall be coated in accordance with ASTM A 762. All riveted joints shall be caulked as described in paragraph B.
2. Pipe with annular corrugations shall be furnished with caulked seams. Riveted pipe joints shall be caulked with a bituminous mastic material during fabrication to provide a watertight joint. All circumferential and longitudinal seams shall be caulked before riveting. This shall be accomplished by applying a uniform bead of the mastic compound to the inner lap surface before riveting such that when the rivets are in place, all voids are filled and a coating of mastic is between the lap surfaces. The inner surface of coupling bands shall be asphalt coated in the field prior to installation. A neoprene gasket having a minimum thickness of 3/8 inch and a minimum width of 7 inches may be used in lieu of mastic coated coupling bands.
3. Welded or lock seams in helical corrugated pipe are considered to be watertight.
4. When close riveted pipe is specified: (1) the pipe shall be fabricated so that the rivet spacing in the circumferential seams shall not exceed 3 inches, except that 12 rivets will be sufficient to secure the circumferential seams in 12-inch pipe, and (2) in those portions of the longitudinal seams that will be covered by the coupling bands, the rivets shall have finished flat heads or the rivets and holes shall be omitted and the seams shall be connected by welding to provide a minimum of obstruction to the seating off the coupling bands.
5. Double riveting or double spot welding of pipe less than 42 inches in diameter may be required. If specified, the riveting or welding shall be done in the manner specified for pipe 42 inches or greater in diameter.

3. COUPLING BANDS

Coupling bands shall meet the requirements of the table below or have detailed drawings submitted for approval by the State Conservation Engineer. Coupling bands shall be of the same minimum thickness (gage) as the pipe being connected.

4. FABRICATION

Fabrication of all appurtenances shall be done as shown on the drawings. All appurtenances shall be made of metallic-coated steel when corrugated steel pipe is used and aluminum when used with aluminum pipe. Dissimilar metals shall not be installed in contact with each other.

Description of Coupling Band	Maximum Fill Height, Ft.	Maximum Pipe Diam., In.
24-inch wide coupling band with four 1/2-inch Diam. galvanized rods with tank lugs for annular or helical corrugated metal pipe. Bands shall have a minimum lap of 3 inches.	All	All
Hugger band from Armco Steel Corp. for helical corrugated metal pipe with reformed ends; and for annular corrugated pipe. Bands include O-ring gaskets and two 1/2-inch Diam.	35	48
Hugger band without rods and lugs but	20	24
Angles riveted or welded to a coupling band and drawn tight with bolts. Bands shall be a minimum of 7 corrugations wide and have a minimum lap of 2 inches.	35	15
Flanged couplings for helical corrugated 25 12 pipe welded to the ends of the pipe and field assembled by a minimum of 3/8-inch Diam. bolts. A joint sealer shall be placed between the flanges to ensure water tightness	25	12
1/ Use is limited to sites where soft foundation and conduit elongation is not anticipated.		

5. REPAIR OF DAMAGED COATINGS

The Contractor shall place the pipe without damaging the pipe or coatings. The pipe shall be transported and handled in a manner to prevent damage to the pipe or coating. Breaks, scuffs, or other damage to the various coatings shall be repaired as follows:

1. Metallic Coating - by thoroughly wire brushing the damaged area and cleaning with solvent, and then painting two coats of one of the following paints:
 - a. Zinc Dust - Zinc Oxide Primer conforming to ASTM D 79 and D 520.
 - b. Single package, moisture cured urethane prime in silver metallic color.
 - c. Zinc-rich cold galvanized compound, brush, or aerosol applications.
2. Polymer Coating - apply two coats of polymer material similar to and compatible with the durability, adhesion and appearance of the original polymer coating. The repair coating shall be a minimum thickness of 0.010 (10 mils) after drying and shall bond securely to the pipe.

6. LAYING AND BEDDING THE PIPE

The pipe shall be laid to the line and grade shown on the drawings and shall be firmly and uniformly bedded throughout its entire length. Details of the bedding are as shown on the drawings.

The pipe shall be laid with the outside laps of circumferential joints pointing upstream and with longitudinal laps on the sides at approximately the vertical mid-height of the pipe. Field welding of corrugated galvanized steel pipe will not be permitted. The pipe sections shall be joined with coupling bands.

7. BACKFILLING

Special care shall be taken during backfill operations not to disturb the grade and alignment.

The pipe shall be tied down or loaded sufficiently during backfilling around the sides to prevent its being lifted from the bedding.

Backfill material shall have sufficient moisture so that optimum compaction can be obtained. Backfill around the pipe shall be placed in layers not more than 4 inches thick before compaction.

Each layer of backfill shall be compacted with power tampers, hand tampers, or plate vibrators to the same density requirements as specified for the adjacent embankment. Backfill over and around the pipe shall be brought up uniformly on all sides. The passage of earth moving equipment will not be allowed over the pipe until backfill has been placed above the top of the pipe surface to a depth of two (2) feet.

8. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Bid Item No. 18 – Aluminum CMP Draw-Down Structure

This item will consist of providing and installing the aluminum water control structure, stop logs, and concrete base, as shown on the drawings.

Provide detailed shop drawings of the water control structure and all appurtenances. Contractor shall furnish two metal lifting rods with hook end and handles capable of lifting supplied stop logs while standing on the surface above the drawdown structure. The length of the lifting rod shall allow for storage in the drawdown structure while allowing for reaching the lower stop log.

Measurement and payment for water control structure shall be on a lump sum basis.

Subsidiary items include concrete base, connections, fittings, excavation and backfill, and control of water.

2. Bid Item No. 19 – Aluminum CMP Draw-Down Inlet/Outlet

This item will consist of providing and installing the 15-inch diameter aluminum CMP outlet pipe as shown on the drawings.

The corrugated metal outlet pipe shall be 12 gage, closed riveted caulk seam (CRCS) round pipe with 2-2/3" and 1/2" annular corrugation and shall conform to ASTM A760.

This bid item shall include flange coupler installation, as well as all other necessary materials and labor required to provide the aluminum CMP inlet/outlet pipes, in conjunction with the aluminum CMP draw-down structure (separate bid item).

Installation shall include filter diaphragm and filter diaphragm outlet as shown on the drawings.

Measurement and payment shall be on an installed linear foot basis.

Subsidiary items include water-tight coupling bands, drainage diaphragm, rodent guard, excavation and backfill, and control of water.

Bid Item No. 21 – CMP Outlet – 10"Ø

This item will consist of furnishing and installing the 10"Ø CMP pipe and fittings shown on the plans for tile outlets, including animal guard at outlet end of pipe.

The corrugated metal pipe shall be 16-gauge minimum, zinc coated or aluminum coated with annular or helical corrugations.

Connect dissimilar pipes with manufactured adapters or couplings if available. A concrete collar shall be used as shown on the plans. Connections shall be watertight.

Installation shall be so at least two-thirds of the outlet pipe shall be buried in the ditch bank, and the cantilever section must extend to the toe of the ditch side slope or the side slope protected from erosion.

Measurement and payment shall be on an installed foot basis will constitute full compensation for this bid item and related subsidiary items.

Payment will constitute full compensation for the following related items: Pollution Control, Removal of Water, Animal Guard, Riprap, and Geotechnical Fabric.

3. Bid Item No. 22 – CMP Outlet – 18"Ø

This item will consist of furnishing and installing the 18"Ø CMP pipe and fittings shown on the plans for tile outlets, including animal guard at outlet end of pipe.

The corrugated metal pipe shall be 16-gauge minimum, zinc coated or aluminum coated with annular or helical corrugations.

Connect dissimilar pipes with manufactured adapters or couplings if available. A concrete collar shall be used as shown on the plans. Connections shall be watertight.

Installation shall be so at least two-thirds of the outlet pipe shall be buried in the ditch bank, and the cantilever section must extend to the toe of the ditch side slope or the side slope protected from erosion.

Measurement and payment shall be on an installed foot basis will constitute full compensation for this bid item and related subsidiary items.

Payment will constitute full compensation for the following related items: Pollution Control, Removal of Water, Animal Guard, Riprap, and Geotechnical Fabric.

4. Bid Item No. 23 – CMP Outlet – 20"Ø

This item will consist of furnishing and installing the 20"Ø CMP pipe and fittings shown on the plans for tile outlets, including animal guard at outlet end of pipe.

The corrugated metal pipe shall be 16-gauge minimum, zinc coated or aluminum coated with annular or helical corrugations.

Connect dissimilar pipes with manufactured adapters or couplings if available. A concrete collar shall be used as shown on the plans. Connections shall be watertight.

Installation shall be so at least two-thirds of the outlet pipe shall be buried in the ditch bank, and the cantilever section must extend to the toe of the ditch side slope or the side slope protected from erosion.

Measurement and payment shall be on an installed foot basis will constitute full compensation for this bid item and related subsidiary items.

Payment will constitute full compensation for the following related items: Pollution Control, Removal of Water, Animal Guard, Riprap, and Geotechnical Fabric.

5. Bid Item No. 26 – 36"Ø Aluminum CMP Riser Inlet (at wetland)

This item will consist of providing and installing the 36"Ø aluminum CMP riser inlet Structure, as shown on the drawings. This item will consist of furnishing and installing the CMP and fittings shown on the plans, including HD bar guard at riser inlet.

The corrugated metal outlet pipe shall be 12 gauge, closed riveted caulk seam (CRCS) round pipe with 2-2/3" and 1/2" annular corrugation and shall conform to ASTM A760.

Connect dissimilar pipes with manufactured adapters or couplings if available. A concrete collar shall be used as shown on the plans. Connections shall be watertight.

Measurement and payment for aluminum CMP riser inlet structure shall be on a lump sum basis.

Subsidiary items include concrete base, excavation and backfill, and control of water.

6. Bid Item No. 27 – 18"Ø Aluminum CMP Riser Inlet (at stilling basin)

This item will consist of providing and installing the 18"Ø aluminum CMP riser inlet Structure, as shown on the drawings. This item will consist of furnishing and installing the CMP and fittings shown on the plans, including bar guard at riser inlet.

The corrugated metal outlet pipe shall be 12 gauge, closed riveted caulk seam (CRCS) round pipe with 2-2/3" and 1/2" annular corrugation and shall conform to ASTM A760.

Connect dissimilar pipes with manufactured adapters or couplings if available. A concrete collar shall be used as shown on the plans. Connections shall be watertight.

Measurement and payment for aluminum CMP riser inlet structure shall be on a lump sum basis.

Subsidiary items include concrete base, excavation and backfill, and control of water.

7. Subsidiary Item - CMP Animal Guard

This item will consist of furnishing and installing the CMP animal guard, for each size tile such as AgriDrain RG series or IDALS approved equal.

No separate payment will be made for the CMP animal guard. Compensation for this item shall be included in the payment for CRCS and CMP tile outlet pipes.

8. Subsidiary Item - Corrugated Metal Water-tight Coupling Bands

This item will consist of furnishing and installing the corrugated metal coupling bands for connections of all pipe sections and structure stubouts.

No separate payment will be made for the CMP coupling bands. Compensation for this item shall be included in the payment for CRCS metal outlet pipe.

9. Bid Item No. 29 – CMP Outlet –8"Ø

This item will consist of furnishing and installing the 8"Ø CMP pipe and fittings shown on the plans for tile outlets, including animal guard at outlet end of pipe.

The corrugated metal pipe shall be 16-gauge minimum, zinc coated or aluminum coated with annular or helical corrugations.

Connect dissimilar pipes with manufactured adapters or couplings if available. A concrete collar shall be used as shown on the plans. Connections shall be watertight.

Installation shall be so at least two-thirds of the outlet pipe shall be buried in the ditch bank, and the cantilever section must extend to the toe of the ditch side slope or the side slope protected from erosion.

Measurement and payment shall be on an installed foot basis will constitute full compensation for this bid item and related subsidiary items.

Payment will constitute full compensation for the following related items: Pollution Control, Removal of Water, Animal Guard, Riprap, and Geotechnical Fabric.

Construction Specification 000 IA-61 Loose Rock Riprap

1. SCOPE

The work shall consist of the construction of loose rock riprap revetments, structures and blankets, including filter layers or bedding where specified.

2. MATERIALS

Rock for loose rock riprap, filter layers or bedding shall come from sources approved by the Engineer. The rock shall be excavated, selected and handled as necessary to meet the quality and grading requirements of this specification and the construction drawings.

Individual rock fragments shall be dense, sound and free from cracks, seams and other defects conducive to accelerated weathering. The rock fragments shall be angular to sub rounded in shape. The least dimension of an individual rock fragment shall not be less than 1/3 the greatest dimension of the fragment unless otherwise specified on the construction drawings.

3. SUBGRADE PREPARATION

The subgrade surfaces on which the riprap or bedding is to be placed shall be cut or filled and graded to the lines and grades shown on the drawings. When fill to subgrade lines is required, it shall consist of approved materials and shall be compacted to a density equal to the adjacent existing soil material.

Rock materials shall not be placed until the foundation preparation is completed and the subgrade surfaces have been inspected and approved by the Engineer.

4. EQUIPMENT-PLACED ROCK RIPRAP

Rock shall be placed by equipment on the surfaces and to the depths specified. The riprap shall be constructed to the full thickness in one operation and in such a manner as to avoid serious displacement of the underlying materials. The rock shall be delivered and placed in a manner that will ensure that the riprap in place shall be reasonably homogeneous with the larger rocks uniformly distributed and firmly in contact, one to another, with the smaller rocks and spalls filling the voids between the larger rocks. Placement of rock shall begin at the bottom of the slope or downstream end of the structure.

Riprap shall be placed in a manner to prevent damage to structures. Hand placing will be required to the extent necessary to prevent damage to adjacent structures.

5. HAND-PLACED RIPRAP

Rock shall be placed by hand on the surfaces and to the depths specified. It shall be securely bedded with the larger rocks firmly in contact, one to another. Spaces between the larger rocks shall be filled with smaller rocks and spalls. Smaller rocks shall not be grouped as a substitute for larger rock. Flat slab rock shall be laid on edge unless otherwise specified. Placement of rock shall begin at the bottom of the slope or downstream end of the structure.

6. FILTER LAYERS OR BEDDING

When the drawings specify filter layers or bedding beneath riprap, the filter or bedding material shall be spread uniformly on the prepared subgrade surfaces to the depth specified. Compaction of filter layers or

bedding will not be required, but the surface of such layers shall be finished reasonably free of mounds, dips or windrows.

7. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Bid Item No. 24 – Riprap (IA DOT Class E)

This item shall consist of furnishing and placing the rock riprap in the locations as shown on the drawings.

In addition, 5 ton of Riprap will be place over the geotextile fabric at each tile outlet.

Rock shall be Class E Revetment Stone as defined by Iowa Department of Transportation (DOT).

All riprap shall be screened by running the stone over a grizzly or plate screen with a minimum opening of 8 inches. This operation shall be done at the quarry. The portion of the stone that is removed by the screening operation will not be acceptable for use as riprap.

Payment will be based on actual tonnage delivered to the site based on weight tickets to the nearest 0.1 ton, subject to the approval of the engineer.

Payment will constitute full compensation for the following related subsidiary items: Pollution Control, Removal of Water, Structure Excavation and Geotextile Fabric.

2. Subsidiary Item - Geotextile Fabric

Geotextile Fabric, IA-95

Construction Specification

000 IA-62 Concrete Grout for Riprap

1. SCOPE

The work shall consist of furnishing, transporting, and placing concrete grout in the construction of grouted rock riprap sections as shown on the drawings.

2. MATERIALS

Cement shall be Type I or Type II Portland cement conforming to ASTM C 150. Fly ash shall be in strict compliance with ASTM C 618, Class F or C. It may be used as a partial substitution for Portland cement for amounts not to exceed 20 percent of the total amount of cementitious material in the grout. The loss by ignition shall not exceed 4.0 percent. Fine aggregate shall conform to ASTM C 33 and shall be composed of clean, uncoated grains of material. Water shall be clean and free of harmful chemicals. Air entraining admixtures shall conform to ASTM C 260.

3. GROUT MIX

The grout mix shall be as follows:

- | | |
|-----------------------------|---|
| 1. Cement: | 10 sacks or 940 pounds per cubic yard |
| 2. Fine concrete aggregate: | 2,100 pounds per cubic yard |
| 3. Water: | 45 gallons per cubic yard or enough to provide a thick creamy consistency |
| 4. Air content: | 6 to 10 percent. |

When ready-mixed grout is furnished, the contractor shall furnish to the Engineer a delivery ticket showing the time of loading and the quantities of materials used for each load of grout mix.

No mixing water in excess of the amount called for in the grout mix shall be added during mixing, hauling or after arrival of the mix at the delivery point.

4. CONVEYING AND PLACING

Grout mix shall be delivered to the site and placed within 1 1/2 hours after the introduction of the cement to the aggregates. In hot weather or under conditions contributing to quick setup of the grout mix, discharge of the concrete shall be accomplished in 45 minutes unless a set-retarding admixture is used, in which case the manufacturer's recommended time limit will apply.

Grout mix shall not be dropped more than 5 feet vertically unless suitable equipment is used to prevent segregation.

The grout mix shall not be placed until the rock riprap has been inspected and approved.

Rock to be grouted shall be kept wet for at least 2 hours immediately prior to grouting. Grout shall not be placed in standing or flowing water.

The grout shall be consolidated by spading or mechanical vibration. The grout shall not be forced to flow laterally to its final location.

The average rate of grout application shall be 5.4 cubic feet per square yard of riprap (0.6 cubic feet per square foot).

5. CURING CONCRETE

Concrete shall be cured for 7 days by either:

1. Applying white pigmented curing compound at a rate of 1 gallon per 150 square feet or as recommended by the manufacturer.
2. Water soak exposed surface for the entire 7 days.
3. Cover with burlap, mats or other material and maintain in a moist condition.
4. Cover with four (4) mil plastic sheeting while concrete is still wet.

Grout mix shall not be placed when daily minimum temperatures are expected to be lower than 40 degrees F unless facilities are provided to maintain the temperature of the materials at 50 to 90 degrees F during the placement and curing period. Grout may not be placed on frozen surfaces. When freezing conditions are expected, rock shall be heated to 50 to 90 degrees F for at least 24 hours prior to placing grout.

6. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Bid Item No. 25 – Cement Grout

This item shall consist of furnishing and placing concrete grout on those portions of the riprap shown on the drawings.

The grout shall be consolidated into the voids with the use of a concrete vibrator. The average rate of grout application shall be adjusted to ensure that the voids are properly filled through the entire riprap depth. A smooth surface is not to be created by the grouting operation.

Grout shall be placed in contact with the downstream sheet pile over the full depth of riprap. There shall be no voids against the sheet pile. Grout against sheet pile upstream shall be smooth.

Grouting operation shall not be performed except in the presence of the Engineer or Engineer's Representative.

Grout unused or wasted, including any partial batch remaining at the completion of the operation, will be estimated and deducted by the Engineer from the volume for payment.

Payment will constitute full compensation for the following related subsidiary items: Pollution Control; and Removal of Water.

Construction Specification

000 IA-81 Metal Fabrication and Installation

1. SCOPE

The work shall consist of furnishing, fabricating, and installing metalwork including metal parts of composite structures.

2. MATERIALS

Steel shall be of structural quality. Finished surfaces shall be smooth and true to assure proper fit. Bolts, nuts, washers, rods, rivets, etc., shall be of a material equal to the steel being fastened.

3. PROTECTIVE COATINGS

Protective coatings will consist of either galvanizing or painting and shall be applied by the fabricator.

Galvanizing shall consist of a zinc coating by the hot dip process, except that bolts, nuts, and washers may have a electrodeposited zinc coating.

Paint System for this specification shall consist of the application of one coat of Epoxy Polyamide Primer (lead and chromate free) and one or more coats of Epoxy Polyamide (intermediate or finish), lead free. When finished, it will have a minimum dry film thickness of 8.0 mils.

4. FABRICATION

Materials shall be carefully fabricated as shown on the drawings. The fabrication shall be smooth and true to assure proper fit. Galvanized items shall not be cut, welded, or drilled after the zinc coating is applied.

5. ERECTION

The metal shall be erected true and plumb, closely conforming to the drawings.

6. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Subsidiary Item - Steel

This item will consist of furnishings and installing the steel channel pieces used to form the crest of the sheet pile weir (cap), reinforcing, and steel used for fabrication of the stoplog channel, and steel grating used in covering the water control structure.

Bolts, nuts and washers required for installation shall be included and considered incidental.

No separate payment will be made for steel. Payment for this item will be considered subsidiary to Steel Sheet Pile and the Water Control Structure.

Construction Specification

000 IA-95 Geotextile

1. SCOPE

This work shall consist of furnishing all materials, equipment, and labor necessary for the installation of geotextile.

2. MATERIAL QUALITY

Geotextile shall be manufactured from synthetic long chain or continuous polymeric filaments or yarns, having a composition of at least 95 percent, by weight, of polypropylene, polyester or polyvinylidene chloride. The geotextile shall be formed into a stable network of filaments or yarns that retain their relative position to each other, are inert to commonly encountered chemicals and are resistant to ultraviolet light, heat, hydrocarbons, mildew, rodents and insects. Unless otherwise specified, the class and type of geotextile shall be as shown on the drawings and shall meet the requirements for materials that follow:

1. Woven Geotextile shall conform to the physical properties listed in Table 1. The woven geotextile shall be manufactured from monofilament yarns that are woven into a uniform pattern with distinct and measurable openings. The geotextile shall be manufactured so that the yarns will retain their relative position with regard to each other. The yarns shall contain stabilizers and/or inhibitors to enhance their resistance to ultraviolet light or heat exposure. The edges of the material shall be salvaged or otherwise finished to prevent the outer yarn from unraveling.
2. Nonwoven Geotextile shall conform to the physical properties listed in Table 2. Nonwoven geotextile shall be manufactured from randomly oriented fibers that have been mechanically bonded together by the needle-punched process. In addition, one side may be slightly heat bonded. Thermally bonded, nonwoven geotextile, in addition to mechanically bonded, nonwoven geotextile, may be used for Road Stabilization. The filaments shall contain stabilizers and/or inhibitors to enhance their resistance to ultraviolet light or heat exposure.
3. The geotextile shall be shipped in rolls wrapped with a protective covering to keep out mud, dirt, dust, debris and direct sunlight. Each roll of geotextile shall be clearly marked to identify the brand, type and production run.

3. STORAGE

Prior to use, the geotextile shall be stored in a clean dry place, out of direct sunlight, not subject to extremes of either hot or cold, and with the manufacturer's protective cover in place. Receiving, storage, and handling at the job site shall be in accordance with the requirements in ASTM D 4873.

4. SURFACE PREPARATION

The surface on which the geotextile is to be placed shall be graded to the neat lines and grades as shown on the drawings. The surface shall be reasonably smooth and free of loose rock and clods, holes, depressions, projections, muddy conditions and standing or flowing water (unless otherwise shown on the drawings).

5. PLACEMENT

Prior to placement of the geotextile, the soil surface will be inspected for quality assurance of design and construction. The geotextile shall be placed on the approved prepared surface at the locations and in accordance with the details shown on the drawings. The geotextile shall be unrolled along the placement area and loosely laid (not stretched) in such a manner that it will conform to the surface irregularities

when material is placed on or against it. The geotextile may be folded and overlapped to permit proper placement in the designated area.

The geotextile shall be joined by overlapping a minimum of 18 inches (unless otherwise specified), and secured against the underlying foundation material. Securing pins, approved and provided by the geotextile manufacturer, shall be placed along the edge of the panel or roll material to adequately hold it in place during installation. Pins shall be steel or fiberglass formed as a "U", "L", or "T" shape or contain "ears" to prevent total penetration. Steel washers shall be provided on all but the "U" shaped pins. The upstream or up-slope geotextile shall overlap the abutting down-slope geotextile. At vertical laps, securing Natural Resources Conservation Service pins shall be inserted through both layers along a line through approximately the midpoint of the overlap. At horizontal laps and across slope laps, securing pins shall be inserted through the bottom layer only. Securing pins shall be placed along a line approximately 2 inches in from edge of the of the placed geotextile at intervals not to exceed 12 feet unless otherwise specified. Additional pins shall be installed as necessary and where appropriate, to prevent any undue slippage or movement of the geotextile. The use of securing pins will be held to the minimum necessary. Pins are to be left in place unless otherwise specified.

Should the geotextile be torn or punctured, or the overlaps disturbed, as evidenced by visible geotextile damage, subgrade pumping, intrusion, or grade distortion, the backfill around the damaged or displaced area shall be removed and restored to the original approved condition. The repair shall consist of a patch of the same type of geotextile being used, overlaying the existing geotextile. The patch shall extend a minimum of 2 feet from the edge of any damaged area.

The geotextile shall not be placed until it can be anchored and protected with the specified covering within 48 hours or protected from exposure to ultraviolet light. Geotextile shall be placed in accordance with the following applicable specification according to the use indicated in drawings:

Slope protection – Class I or II as indicated in Tables 1 and 2.

The geotextile shall not be placed until it can be anchored and protected with the specified covering within 48 hours or protected from exposure to ultraviolet light. Rock shall not be pushed or rolled over the geotextile.

Class I, unprotected – limit height for dropping stone onto bare geotextile to 3 feet.

Class II, protected – require the use of 6 inches a clean pit-run gravel over the geotextile to cushion the stone and limit the height of drop to 3 feet.

On slopes with strong seepage flow, the geotextile must be in intimate contact with the soil to prevent erosion of the soil surface. Use 6 inches of a clean pit-run gravel over the geotextile to hold it in place and minimize voids under the riprap. Embedment of the geotextile in a trench to form a cutoff at regular intervals down the slope will prevent erosion under the fabric. Place cutoffs more closely together in highly erodible soils and wider apart in more stable soils

Subsurface drains – Class III as indicated in Tables 1 and 2.

The geotextile shall not be placed until drainfill or other material can be used to provide cover within the same working day. Drainfill material shall be placed in a manner that prevents damage to the geotextile. In no case shall material be dropped on uncovered geotextile from a height of more than 5 feet.

Road stabilization – Class IV as indicated in Tables 1 and 2.

The geotextile shall be unrolled in a direction parallel to the roadway centerline in a loose manner permitting conformation to the surface irregularities when the roadway fill material is placed on its surface. In no case shall material be dropped on uncovered geotextile from a height of more than 5 feet. Unless otherwise specified, the minimum overlap of geotextile panels joined without sewing shall be 24 inches.

The geotextile may be temporarily secured with pins recommended or provided by the manufacturer, but they shall be removed before the permanent covering material is placed.

Table 1. Requirements for Woven Geotextiles^{1/}

Property	Test Method	Class I	Class II	Class III	Class IV
Grab tensile strength (pounds)	ASTM D4632	247 minimum	180 minimum	180 minimum	315 minimum
Elongation at failure (%)	ASTM D4632	< 50	< 50	< 50	< 50
Trapezoidal tear strength (pounds)	ASTM D4533	90 minimum	67 minimum	67 minimum	112 minimum
Puncture strength (pounds)	ASTM D6241	495 minimum	371 minimum	371 minimum	618 minimum
Ultraviolet light (% retained strength)	ASTM D4355	50 minimum	50 minimum	50 minimum	70 minimum
Permittivity (sec ⁻¹)	ASTM D4491	as specified			
Apparent opening size (AOS) ^{2/}	ASTM D4751	as specified			
Percent open area (POA)(%)	USACE ^{3/} CWO-02215-86	as specified			

^{1/} All values are minimum average roll values (MARV) in the weakest principal direction, unless otherwise noted.

^{2/} Maximum average roll value.

^{3/} Note: CWO is a USACE reference.

Table 2. Requirements for Nonwoven Geotextiles^{1/}

Property	Test Method	Class I ^{2/}	Class II ^{2/}	Class III ^{2/}	Class IV ^{2/}
Grab tensile strength (pounds)	ASTM D4632 grab test	202 minimum	157 minimum	112 minimum	202 minimum
Elongation at failure (%)	ASTM D4632	50 minimum	50 minimum	50 minimum	50 minimum
Trapezoidal tear strength (pounds)	ASTM D4533	79 minimum	56 minimum	40 minimum	79 minimum
Puncture strength (pounds)	ASTM D6241	433 minimum	309 minimum	223 minimum	433 minimum
Ultraviolet light (% retained strength)	ASTM D4355	50 minimum	50 minimum	50 minimum	50 minimum
Permittivity (sec ⁻¹)	ASTM D4491	0.7 minimum or as specified			
Apparent opening size (AOS) ^{3/}	ASTM D4751	0.22 minimum or as specified			

^{1/} All values are minimum average roll values (MARV) in the weakest principal direction, unless otherwise noted.

^{2/} Needle punched geotextiles may be used for all classes. Heat-bonded or resin-bonded geotextiles may be used for class IV only.

^{3/} Maximum average roll value.

6. SPECIFIC SITE REQUIREMENTS

A. Measurement and Payment

Compensation for any work item described in the contract documents but not listed in the bid schedule will be included in the payment for the item of work to which it is made subsidiary. Such items and bid items to which they are made subsidiary are identified in Items of Work and Construction Details section of this specification.

For items of work which lump sum prices are established in the contract, the quantity of work will not be measured for payment. Payment for each item will be made at the contract lump sum price and will constitute full compensation for completion of the work.

For items of work for which specific unit prices are established in the contract, the payment will be made based on the approved quantity measured by the engineer or weight tickets. Payment will constitute full compensation of the work completed as defined by each work item.

B. Items of Work and Construction Details

1. Subsidiary Item - Geotextile

This item shall consist of furnishing and placing geotextile on all surfaces that contact the rock riprap as shown on the drawings and at concrete aprons.

Geotextiles shall conform to the requirements of IDOT Engineering Fabric for embankment erosion control.

The geotextile shall be placed with the long dimension parallel to the channel.

No separate payment will be made for geotextile. Compensation of this item will be included in the payment for the related bid item, Riprap.

WRIGHT COUNTY WETLAND PROJECT
WRI922420D - BID NO. E26-05
PREBID MEETING, USDA Service Center 1133 Central Ave, Clarion IA
July 1, 2026 - 9:00 aM

Tracy Blocker, Division of Soil Conservation and Water Quality (Division) opened the meeting.

A) Introductions

- Sara Smith, Engineer with Division
- Andrew Schippers, P.E., Bolton & Menk Inc
- Others: See sign-in sheet

- There are 3 projects being bid at this time, including this one, one in Cerro Gordo County and one in Chickasaw County.

- This wetland project is part of the Water Quality Initiative that is being used to help implement the Iowa Nutrient Reduction Strategy.

B) Bidding

1. Time of Completion:

- The final date for completion of all work except for seeding is set for **06/15/2027**.
The final date for completion of seeding is **Buffer 06/30/2027 and the Structure 09/15/2027**

2. Liquidated Damages:

- There are liquidated damages provisions - absent a No-Fault Extension
- If *all work except for seeding* is not completed by June 15, 2027, **\$175 per day**.
- If the *seeding* is not subsequently completed by the respective dates **\$125 per day**.
Buffer 06/30/2027 and the Structure 09/15/2027

3. Taxes:

- There is no sales tax for materials purchased
- This should be considered when determining the unit prices submitted in the bid

4. Measurement and Payment:

- The specifications describe the method to be used in measuring and calculating the payment quantities
- Payments will be made based on monthly estimates at 97% of the work completed
- Mobilization is paid as percentage completed of the lump sum (less retainage)
- 97% of the cost of materials stored on site can be paid by submitted an invoice

5. Method of Bidding:

- This is a unit price contract
- Prices shall cover complete work and include all costs incidental thereto unless otherwise indicated
- The base bid includes all items **1 through 28 Engineer's list / 1.1 – 1.27 IMPACS list** (crop damage). A separate Document CC was provided with the bid package that may be used as a worksheet

- ALL bids must be submitted through our IMPACS site.
- Any questions must be submitted to us by **July 8, 2026**.
- Make sure acknowledged the addendum, if applicable
- If work is added to the contract after execution a Change Order or Contract Amendment will be issued as required
- Extension of the contract completion date(s), a Contract Amendment

6. Submission of Bids and Bid Security:

- Bids must be submitted on the 'Items' page within IMPACS and shall include a bid bond in the amount of ten percent (10%) within the 'Prerequisites' page on this IMPACS post.

<https://das.iowa.gov/vendors/bidding-opportunities#vendor-bid-opportunities> (IMPACS site)

- View Other Agency Hosted Solicitations
Sort by Agency: Agriculture & Land Stewardship

<https://solutions.scquest.com/apps/Router/SupplierLogin?CustOrg=DASIowa> (Log into IMPACS)

- Bidders must also be registered with the Iowa Department of Inspections, Appeals, & Licensing
https://laborportal.iwd.iowa.gov/iwd_portal/dashboards/contractor-home

IMPACS “101”

TAB 1 – Summary

TAB 2 – Prerequisites: Question 3

TAB 3 – Buyer(IDALS) Attachments including addendum, if applicable

TAB 4 – Supplier(You) Attachments, shouldn't need – Upload Bid Bond & Doc EE &
Doc CC Proposal-Acknowledgment-Affidavit

TAB 5 – Questions: answer 1 - 3

TAB 6 – Items: enter in each unit cost, note you need to hit “enter” for it to calculate

You do not need to complete the Estimated Delivery date. It is common to have multiple pages on this TAB. Page arrows are at the bottom left while next in bottom right will take you to TAB 7.

TAB 7 – Review & Submit: Green check marks, check the Certification at the bottom and submit

- Any time prior to close, you may withdraw or edit you bid.
- Doc CC must be signed by a legally authorized representative of the Bidder and notarized.
- All issued addendum shall be acknowledged on page 2 of Doc CC as received by the Bidder.
- Do not submit Plans or Specifications with the bid.
- If any form is not accurately completed, it could prevent the reading of that Bidder's bid.
- Bid Security or bid bond, ten percent (10%) of the base bid. If the Bidder elects to use a bid bond, the bidder shall complete Proposal Guarantee Bond (Document EE) and upload with the Bid Bond. If you use a cashier's check, it must be delivered 3 hours prior to bid opening. Your bid must still be in IMPACS

- All bids are due no later than 3:00 PM Thursday, July 16, 2026 via IMPACS
- Bids received after this time will be locked out.
- Bids may NOT be mailed or hand delivered.
- If you bid on multiple projects but don't want all, you must email Tracy.Blocker@iowaagriculture.gov prior to close and follow up with a call to be sure the email was received and seen.

7. Evaluation of bids and award of Construction Contract:

- Shall be awarded to the lowest responsible responsive bidder as determined by the Division.
- The Division may consider such factors as alternates, bid price, experience, contracts in default, responsibility of the Bidder, and similar factors
- IMPACS generate the Bid tab. Still email to bidders. Other plan holders or interested parties must request bid tabulations.

8. Bidder's Qualifications:

1. Required to be registered with the Iowa Department of Inspections, Appeals & Licensing
2. Upon request from the Division, submit a statement of Bidder's qualifications including experience, any contracts that are in default, available equipment, personnel, and financial ability

9. Execution of Contract:

1. Contracts will not be issued via IMPACS at this time.
2. required to:
 - ✓ execute the Contract;
 - ✓ obtain the appropriate insurance coverage and Performance/Payment Bond;
 - ✓ provide their Iowa Department of Inspections, Appeals & Licensing Registration Number;
 - ✓ Construction Progress Schedule (Document JJ)

within fourteen (14) calendar days from the date of receipt of the Notice-of-Award.

3. The Division, within fourteen (14) days of receipt shall sign the Contract
Should the Division fail to do so, the Contractor may withdraw in writing the signed Contract

10. The Notice-to-Proceed

- a. shall be issued within five (5) days of the execution of the Contract by the Division, provided that the Construction Progress Schedule has been accepted by the Division.
- b. additional time required, the time to issue the Notice-to-Proceed may be extended
- c. If the Notice-to-Proceed has not been issued within a thirty (30) day period, or within a greater period mutually agreed upon, the Contractor may terminate the Contract
- d. Must have an approved schedule before a Notice to Proceed will be issued. Pre-construction meeting will be held within 7 days of construction starting.

11. Questions and Addenda:

- Questions concerning the Plans and Construction Specifications
direct to 0: 0 with 0
and must copy Tracy Blocker: tracy.Blocker@iowaagriculture.gov with the Division.
- All other questions concerning the Contract Documents should be addressed to Tracy Blocker, Division: 515 344-6279 or tracy.blocker@iowaagriculture.gov.

- Any oral interpretations given shall be valid only if confirmed by written addendum.
- All interpretation requests should be addressed in writing and received no later than 3:00 PM July, 8, 2026.

The Division reserves the right to revise or amend the Contract Documents prior to close. Such revisions and amendments shall be announced by an addendum. Copies of such addenda shall be furnished to all plan holders.

- Q: How does a foreign entity (out-of-state) register with the Secretary of State?
A: A foreign business entity can be registered with the State by submitting a Certificate of Authority. You may submit this file through the Fast Track Filing website. The version submitted depends on the type of entity being registered (LLC, Profit, Nonprofit). . All foreign filing applications will look similar and will follow the same trend, though different chapters may have specific requirements as listed on the form. We have simplified the walkthrough by showing how to file for a foreign LLC, but the same general rules apply to all foreign filing forms. Click [here](#) to view the step-by-step Foreign LLC filing guide.
After submitting the file, you will receive an email from the Secretary of State notifying you that the form has been accepted. It is recommended that you consult with a private legal counsel for next steps
- Q: Does the Dave-Bacon Act apply?
A: No



GREAT LAKES/ATLANTIC REGION
7322 Newman Blvd., Bldg. 2
Dexter, MI 48130
(734) 623-2000
www.ducks.org

PRE-BID MEETING NOTES

Wri922420D
Bid No. E26-05
Wright County, Iowa
DU Project #IA-340-8

Prepared by:
Lucas Woodbury, Andrew Schippers
Ducks Unlimited, Inc.
Great Lakes/Atlantic Region

Date & Time: July 1, 2026; 9 a.m. to 11 a.m.
Location: USDA Service Center, Clarion, Iowa

General Comments

1. This project is one of three wetland projects currently being bid by IDALS. The project is part of the Iowa Water Quality Initiative and Nutrient Reduction Strategy.
2. Questions are due by July 8, 2026, and bids are due through IMPACS by 3:00 PM on July 16, 2026.
3. Completion date for all work except seeding is June 15, 2027. Buffer seeding must be completed by June 30, 2027 and structure seeding by September 15, 2027.
4. IDALS will not issue a Notice to Proceed until an approved construction schedule has been received.
5. Dewatering is considered part of the project requirements and shall be included in the Contractor bid.
6. The easement area is currently seeded to cover crops.
7. Crop damages associated with tile modifications outside easement areas will be handled through the crop damage item.
8. Two additional projects are currently out for bid at the same time as this project.
9. Permit requirements will apply to Bid Item No. 4.
10. GPS, CAD files, and staking information can be provided to the Contractor.

Engineer Discussion

1. The project includes approximately five acres of wetland treatment area.
2. Additional grading may be required due to limited elevation differences across portions of the site.
3. Two submerged berms are included in the design.
4. The west-side berm includes approximately 60 feet of sheet piling.
5. Engineers will review alternate sheet pile products submitted by contractors.
6. Spoil material may be returned to the borrow area or spread within approved easement boundaries.
7. Test pit information has been collected and groundwater conditions will be reviewed further.

Site Access and Construction Considerations

1. Construction access will need to be on 200th street with permission from county
2. The contractor will be responsible for obtaining the construction site access permit from the County engineer, including permit fees and work necessary to achieve access.
3. Landowner on NW side along R45 said that only vehicle access to site maybe along shared driveway, however he did not want his asphalt (up the driveway by about 40 yards) being driven on and broken by heavy equipment. Therefore, do not use the neighbor to the North driveway for construction access.
4. County officials requested evaluation of access from 200th Street.
5. Contractors should minimize damage to existing driveways, roadways and adjacent properties and must restore any impacts caused by construction activities.

6. No known seasonal nesting restrictions were identified during the meeting.

Septic System Modification

1. The septic system modification item requires additional clarification to ensure all bidders are pricing the same scope of work.
 - Post Meeting Change: Septic system modification included in bid item #28 has been revised to only include the removal of the 5" line that connected the house on the North side to the existing drainage tile. IDALS will procure a separate contract for the new septic tank through the County Sanitarian. Please see addendum no. 1 for more info.
2. The design is coordinated with the County Sanitarian office.
3. See Addendum No. 1.

Drainage, Outlets, and Structures

1. Questions were raised regarding the need for riprap at all pipe daylight locations.
 - Post meeting change: Riprap will be added at all proposed tile daylight locations.
2. The design includes tile outlets would have animal guards.
3. The water control structure outlet angle required for fabrication must be approved by the engineer before ordering materials.
4. Tile outlet sizes, lengths and quantities associated with Bid Items 21, 22, and 23 have been revised, see addendum No. 1.
5. Trash guard modifications are anticipated and may be addressed during construction through an engineer approved Change Order.
6. Testing may be required to verify filter/drain systems are functioning properly during construction.
7. See Addendum No. 1.

Dewatering and Erosion Control

1. Dewatering is incidental and must be included in the Contractor bid and performed according to specifications.
2. Road ditches or other approved areas may be used for temporary discharge but must be approved by the engineer.
3. Groundwater issues are not expected to be severe, although contractors should plan accordingly.
4. Cover crops are preferred for temporary erosion control and stabilization. Cover crops will be negotiated between the contractor and IDALS.
5. The Contractor will be responsible for SWPPP compliance and erosion-control implementation.

Seeding Discussion

1. Contractors shall follow all specified seeding periods included in the Technical specifications,
2. Dormant seeding may be performed when allowed by specifications and seasonal conditions.
3. Different requirements apply to structure seeding and buffer seeding.
4. Temporary stabilization measures shall be maintained until permanent vegetation is

Questions and Responses

1. Question: Do we have GPS and CAD files? Answer: Yes and staking information can also be provided.
2. Question: Is riprap required at all outlet daylight? Answer: Not currently shown; design team will review.
3. Question: How will the septic system modification be handled? Answer: Additional details will be coordinated with the County.
4. Question: Are there work-hour restrictions? Answer: None are currently known, but critical clay core work should be coordinated with engineering staff.
5. Question: Can waste material be returned to the borrow area? Answer: Yes.
6. Question: Is geotechnical information available? Answer: Test pit data has been recorded.
7. Question: Can alternate sheet piling be used? Answer: Yes, subject to review and approval.
8. Question: How should dewatering be addressed? Answer: Include all dewatering costs within the bid.

Follow-Up Items

1. Septic system clarification: The new septic tank noted in the plans is no longer included in the project, as IDALS will contract with the County/certified septic tank contractor directly.
2. Riprap quantities
3. Verify CMP outlet lengths and quantities.
4. Confirm fabrication angles for drainage structures.
5. Issue addendum regarding trash guard modifications.
6. Coordinate access requirements with County officials.
7. Provide geotechnical information upon request.
8. Consider moving crop damage item to the bottom of future schedules of prices.

Final Note

Many questions and changes have been addressed and can be seen in Addendum No. 1

Pre-Bid Meeting Sign-in Sheet

Bid No.: 26-05

Project ID: Wri922420D Nutrient Reduction Wetland

Wednesday, July 1, 2026 9:00 AM USDA Service Center - Clarion 1133 Central Ave W
 If I can't read your handwriting, I may not be able to send you the addendum or other pertinent information.

Clarion
 515-344-6279

	Name	Company/Affiliation	City State	Email	Phone
1	Tracy Blocker	Division	Des Moines IA 50309	tracy.blocker@iowaagriculture.gov	515-344-6279
2	Sara Smith	Division	Des Moines IA 50309	sara.smith@iowaagriculture.gov	515-422-7335
3	Lyle Reachin	MNL	Ostego MN		612 221 0475
4	Lena Ostransky	High Plains Shovelworks	Lincoln NE	LOstransky@highplains.biz	402 833 8842
5	Lucas Woodbury	Ducks Unlimited	Huxley, IA	lwoodbury@ducks.org	815-826-0920
6	ANDREW SCHIPPERS	DU	HUXLEY, IA	aschippers@ducks.org	832-704-3286
7	Grant Anndorfer	Dornbier Inc	Wesley, IA	Grant@DornbierInc.com	515-341-6881
8	Rick Peterson	Lanconer	Webster City Ia.		515-297-3785
9	MITCHEL PETERSON	Lanconer	AMES IA	mitchel.c.peterson@stapl.com	515-290-6757
10					
11					
12					
13					
14					
15					
16					
17					
18					
19					
20					

Division of Soil Conservation & Water Quality - Water Resources Bureau
as of

07/10/2026

Plan Holders List for Bid **26-04** **26-05** **26-06**
Project ID **Chi941410B** **Wri922420D** **Cer962218C**
Bid Opening **July 16, 2026 @ 3:00 PM**

	Name	Email	Company	Street Address	City	State	Zip code	Phone
26-04	Chi941410B							
Consultant	NATHAN BLANKMAN	NBLANKMAN@JEO.COM	JEO	724 Simon Ave	Carroll	IA	51401	712-830-4132
IDALS	ASHLEY WOS	ASHLEY.WOS@IOWAAGRICULTURE.GOV	IDALS		Des Moines			
IDALS	TRACY BLOCKER	TRACY.BLOCKER@IOWAAGRICULTURE.GOV	IDALS		Des Moines			515-344-6279
PB	TRAVIS LENTZ	LENTZEXC@GMAIL.COM	LENTZ EXCAVATING		ALTA VISTA	IA		641-330-6115
PB	LENA OSTRANSKY	LOSTRANSKY@HIGHPLAINS.BIZ	HIGH PLAINS STRUCTURAL GROUP		LINCOLN	NE		402-833-3842
PB	CHAD WILTZEN	CW@BRUENINGROCK.COM	SKYLINE CONSTRUCTION		DECORAH	IA		563-392-2933
PB	COLBIE SCHMIDT	DREWELOW360@GMAIL.COM	CEDAR RIDGE PRECISION (ADAM DREWELOW)	2721 AMHERST BLVD	NASHUA	IA		319-415-8494
PB	BRENT MEHMERT	BRENT@MEHMERTTILING.BIZ	MEHMERT TILING		LIME SPRINGS	IA		319-240-9930
	Cory Bacon	baconconcrete@neitel.net	Bacon Concrete	370 N Bancroft St, PO Box 188	Postville	IA	52162	563-864-7602
	Jared Mains	jncconstructionllc@gmail.com	JNC Construction LLC	609 3rd St PO Box 46	Clearfield	IA	50840	515.577.2066
	James Seehusen	james@pcius.com	PCI	PO Box A	Reinbeck	IA	50669	319-788-4764
	Braxton Rottinghaus	braxtonr@pcius.com	PCI	104 Blackhawk Street	Reinbeck	IA	50669	319-560-9845
	Chad McDonald	cmcdonald@gehrkeinc.com	Gehrke Inc	1405 21st Ave	Eldora	IA	50627	641.858.6953
PR	Cindy Adams	Cadams@mbi.build	Master Builders of Iowa	4100 Westown Pkwy	West Des Moines	IA	50266	515-402-9858
PR	Kira Rieck	kriec@mbi.build	Master Builders of Iowa	4100 Westown Pkwy	West Des Moines	IA	50266	515-288-8904
PR	Adam DoBraska	ADoBraska@mbi.build	Master Builders of Iowa	4100 Westown Pkwy	West Des Moines	IA	50266	515-777-5054
	Lacey	quotes@coleexcavating.com	Cole Excavating, LLC					641.823.4700
	Staci Snitker	sas@brueningrock.com	SKYLINE CONSTRUCTION	900 Montgomery St PO Box 127	Decorah	IA	52101	563-382-2933
	Christina	mattconstructioninc@gmail.com	MATT Construction Inc	203 Y Ave	Sumner	IA	50674	563-578-8418
PR		source1@mbi.build	Master Builders of Iowa					
	Eric Deters	edeters@melleninc.com	Mellen & Associates Inc		Council Bluffs			712-322-9333
	Chad McDonald	cmcdonald@gehrkeinc.com	Gehrke Inc	1405 21st Ave	Eldora	IA	50627	641.858.6953
	Jordan Krull	jordan@leymaster.com	Leymaster Tile		Cedar Falls			319-30-5057
	Archy Evans	archy.evans@construction.com	Dodge Construction					844-326-3826
	Chad Borsheim	ceb@brueningrock.com	Bruening Rock Products/Skyline Materials/Bullseye Trucking					515-460-5462

26-05 Wri922420D

Consultant	ANDRES SCHIPPERS	aschippers@ducks.org	Ducks Unlimited	209 Eugene St	Radcliffe	IA	832-704-3286
Consultant	LUCAS WOODBURY	LWOODBURY@DUCKS.ORG	Ducks Unlimited		HUXLEY	IA	815-826-0920
IDALS	SARA SMITH	SARA.SMITH@IOWAAGRICULTURE.GOV	IDALS		Des Moines		515-422-7335
IDALS	TRACY BLOCKER	TRACY.BLOCKER@IOWAAGRICULTURE.GOV	IDALS		Des Moines		515-344-6279
PB	LYLE REACDON		MNL	8740 77TH ST NE	OSTEGO	MN 55362	612-221-0475
PB	LENA OSTRANSKY	LOSTRANSKY@HIGHPLAINS.BIZ	HIGH PLAINS STRUCTURAL GROUP		LINCOLN	NE	402-833-3842
PB	GRANT ARNDORFER	GRANT@DORNBIERINC.COM	DORNBIER INC.		WESLEY	IA	515-341-6881
PB	CHASE DUESENBERG				VENTURA	IA	641-529-0562
	Darin Eastvold	bids@larsonscontracting.com	Larson Contracting Central LLC	508 W Main St PO Box 7	Lake Mills	IA 50450	406.890.4211
	Jared Mains	jncconstructionllc@gmail.com	JNC Construction LLC	609 3rd St PO Box 46	Clearfield	IA 50840	515.577.2066
	Marilyn Vonnahme	leorysoninc@gmail.com	Leroy and Sons, Inc.	405 Dunlap Street	Arcadia	IA 51430	712-790-9956
	James Seehusen	james@pcius.com	PCI	PO Box A	Reinbeck	IA 50669	319-788-4764
	Douglas Schmidgall	douglas.schmidgall@oldcastle.com	Oldcastle Infrastructure	1601 E 39th St N	Sioux Falls	SD 57104	320-391-6336
	Braxton Rottinghaus	braxtonr@pcius.com	PCI	104 Blackhawk Street	Reinbeck	IA 50669	319-560-9845
	Jodi Johnson	hjohnsonservices@gmail.com	H. Johnson Services, LLC	1943 180th ST	Creston	IA 50801	515.681.2224
	Corey Johnson	corey@molitorconstruction.com	Molitor Construction LLC	2528 Eastgate Dr	Boone	IA 50036	515-212-0724
	Evan Hurd	evan.hurd@hls-co.com	Heritage Land Solutions	302 Broad St	Story City	IA 50248	515-520-0711
	Chad McDonald	cmcdonald@gehrkeinc.com	Gehrke Inc	1405 21st Ave	Eldora	IA 50627	641.858.6953
PR	Cindy Adams	Cadams@mbi.build	Master Builders of Iowa	4100 Westown Pkwy	West Des Moines	IA 50266	515-402-9858
PR	Kira Rieck	krieck@mbi.build	Master Builders of Iowa	4100 Westown Pkwy	West Des Moines	IA 50266	515-288-8904
PR	Adam DoBraska	ADoBraska@mbi.build	Master Builders of Iowa	4100 Westown Pkwy	West Des Moines	IA 50266	515-777-5054
	Jeff Renier	jeff.renier@mnlcorp.com	MNL	8740 77th St NE	OSTEGO	MN 55362	763-295-0010
	Lacey	quotes@coleexcavating.com	Cole Excavating, LLC				641.823.4700
	Brook Tuttle	brook@mcdowellandsons.com	McDowell & Sons Contractors, Inc.	10214 HWY 65, P.O. Box 664	Iowa Falls	IA 50126	641-648-5071
	Brett Larson	jeff@buskellc.com	TLC / Buske				515-351-9616
PR		source1@mbi.build	Master Builders of Iowa				
	Eric Deters	edeters@melleninc.com	Mellen & Associates Inc		Council Bluffs		712-322-9333
	Chad McDonald	cmcdonald@gehrkeinc.com	Gehrke Inc	1405 21st Ave	Eldora	IA 50627	641.858.6953
	Jordan Krull	jordan@leymaster.com	Leymaster Tile		Cedar Falls		319-30-5057
	Archy Evans	archy.evans@construction.com	Dodge Construction				844-326-3826
	Chad Borsheim	ceb@brueningrock.com	Bruening Rock Products/Skyline Materials/Bullseye Trucking				515-460-5462

26-06 Cer962218C

Consultant	Brandon Short	brandon.short@bolton-menk.com	Bolton & Menk Inc Engineering						515.509.9296
IDALS	SARA SMITH	SARA.SMITH@IOWAAGRICULTURE.GOV	IDALS				Des Moines		515-422-7335
IDALS	TRACY BLOCKER	TRACY.BLOCKER@IOWAAGRICULTURE.GOV	IDALS				Des Moines		515-344-6279
PB	LYLE REACDON		MNL	8740 77TH ST NE			OSTEGO	MN	55362 612-221-0475
PB	LENA OSTRANSKY	L0STRANSKY@HIGHPLAINS.BIZ	HIGH PLAINS STRUCTURAL GROUP				LINCOLN	NE	402-833-3842
PB	GRANT ARNDORFER	GRANT@DORNBIERINC.COM	DORNBIER INC.				WESLEY	IA	515-341-6881
	Darin Eastvold	bids@larsonscontracting.com	Larson Contracting Central LLC	508 W Main St PO Box 7			Lake Mills	IA	50450 406.890.4211
	Jared Mains	jncconstructionllc@gmail.com	JNC Construction LLC	609 3rd St PO Box 46			Clearfield	IA	50840 515.577.2066
	James Seehusen	james@pcius.com	PCI	PO Box A			Reinbeck	IA	50669 319-788-4764
	Braxton Rottinghaus	braxtonr@pcius.com	PCI	104 Blackhawk Street			Reinbeck	IA	50669 319-560-9845
	Jodi Johnson	hjohnsonservices@gmail.com	H. Johnson Services, LLC	1943 180th ST			Creston	IA	50801 515.681.2224
	Chad McDonald	cmcdonald@gehrkeinc.com	Gehrke Inc	1405 21st Ave			Eldora	IA	50627 641.858.6953
PR	Cindy Adams	Cadams@mbi.build	Master Builders of Iowa	4100 Westown Pkwy			West Des Moines	IA	50266 515-402-9858
PR	Kira Rieck	kriec@mbi.build	Master Builders of Iowa	4100 Westown Pkwy			West Des Moines	IA	50266 515-288-8904
PR	Adam DoBraska	ADoBraska@mbi.build	Master Builders of Iowa	4100 Westown Pkwy			West Des Moines	IA	50266 515-777-5054
	Jeff Renier	jeff.renier@mnlcorp.com	MNL	8740 77th St NE			OSTEGO	MN	55362 763-295-0010
	Lacey	quotes@coleexcavating.com	Cole Excavating, LLC						641.823.4700
	Brook Tuttle	brook@mcdowellandsons.com	McDowell & Sons Contractors, Inc.	10214 HWY 65, P.O. Box 664			Iowa Falls	IA	50126 641-648-5071
	Douglas Schmidgall	douglas.schmidgall@oldcastle.com	Oldcastle Infrastructure	1601 E 39th St N			Sious Falls	SD	57104 320-391-6336
	Harley Johnson	hjohnsonservices@gmail.com	H. Johnson Services LLC						515-681-2224
PR		source1@mbi.build	Master Builders of Iowa						
	Chad McDonald	cmcdonald@gehrkeinc.com	Gehrke Inc	1405 21st Ave			Eldora	IA	50627 641.858.6953
	Jordan Krull	jordan@leymaster.com	Leymaster Tile				Cedar Falls		319-30-5057
	Archy Evans	archy.evans@construction.com	Dodge Construction						844-326-3826
	Chad Borsheim	ceb@brueningrock.com	Bruening Rock Products/Skyline Materials/Bullseye Trucking						515-460-5462

KEYX on plan holders list, did **NOT** submit bid

Y on plan holders list, submitted bid

NP not on plan holders list, submitted bid

PB attended pre-bid

IDALS staff

PR Plan Room

E Engineer of Record

tab Requested bid tab