

Addendum 1 for RFB927920-01

Project Name: WRC Decentralization Phase 2 & Fire Alarm & Myers Hall Sprinkler
DAS RFB #: 927920-01
DAS Project #: 9279.20-21 & 9294.00
Date: 2/16/2023

Questions Due: February 21, 2023, at 2:00pm

Bids Due: February 28, 2023, at 2:00pm

TO: PROSPECTIVE BIDDERS:

THIS ADDENDUM FORMS A PART OF THE BIDDING AND CONTRACT DOCUMENTS AND MODIFIES THE BIDDING DOCUMENTS DATED 01-10-2023, WITH AMENDMENTS AND ADDITIONS NOTED BELOW. THIS ADDENDUM SUPERSEDES AND SUPPLEMENTS ALL PORTIONS OF THE ORIGINAL BIDDING AND CONTRACT DOCUMENTS WITH WHICH IT CONFLICTS. ACKNOWLEDGE RECEIPT OF THIS ADDENDUM IN THE IMPACS ELECTRONIC PROCUREMENT SYSTEM. FAILURE TO DO SO MAY DISQUALIFY THE BIDDER.

GENERAL NOTES

The CM (Story Construction) will be in communication with Hazard Materials and asbestos contractors to remove any asbestos that may be present within the building.

Change all instances of RFB927900-01 to RFB927920-01.

QUESTIONS AND ANSWERS FROM PRE-BID MEETING

Q1. Is there an attic at Myers Hall that needs to be sprinklered?

A1. Yes, please see attached drawing sheet 04-FP103.

Q2. Will painting pipe and conduit fall under the owner performed work?

A2. All painting will be included with BP-09-1 as part of the updated allowance of \$40,000 for wall patching and painting. ADD #2 will further clarify this scope.

Q3. Which bid package should be responsible for the radiator cover removal?

A3. This will be done by BP #22-1 and ADD #2 will further clarify this scope.

CHANGES TO SPECIFICATIONS AND DRAWINGS

Specifications:

- **SECTION 00 0110 – TABLE OF CONTENTS**
 - **REPLACE** entire specification section.

- **SECTION 00 0115 – LIST OF DRAWING SHEETS**
 - **REPLACE** entire specification section.
- **SECTION 07 2100-THERMAL INSULATION**
 - **REMOVE** section in its entirety.
- **SECTION 08 7100-DOOR HARDWARE**
 - **REMOVE** section in its entirety.
- **SECTION 09 9123-INTERIOR PAINTING**
 - **ADD** §2.1B4 “Architect Pre-Approved Equivalent.”
 - **REMOVE** §2.1C regarding substitutions.
 - **REVISE** §2.3A3a to “Architect Pre-Approved Equivalent.”
- **SECTION 21 1316 – DRY PIPE FIRE SUPPRESSION SPRINKLER SYSTEMS**
 - **ADD** specification to project.
- **SECTION 23 0500 – COMMON WORK RESULTS FOR HVAC**
 - **REPLACE 3.4.B** with: “Concrete bases and pads for mechanical equipment shall be furnished by this Contractor. Size bases to extend minimum of 4" beyond equipment base in any direction, and 4" above finished floor elevation. Construct of reinforced concrete, roughen floor slab beneath base for bond, and provide steel rod anchors between floor and base. Locate anchor bolts using equipment manufacturer's templates. Chamfer top and edge corners.”
- **SECTION 23 0923 – DIRECT-DIGITAL CONTROL SYSTEM FOR HVAC**
 - **REVISE** 2.11.X.1. to read “All VFD's will be owner provided and BP #26-1 installed. Refer to 26 2923 – Variable-Frequency Motor Controllers for additional details.” This section will be included in Addendum #2.
 - **REVISE** 3.19.B. Delete reference to Appendix A in 23 09 93. If character limitations or space restrictions make it advisable to shorten a point name, provide a list of abbreviations in submittals.
 - **REVISE** 3.19.D.1. Delete reference to 23 09 93. Points are shown on schematics on control drawings and described in sequences.
- **SECTION 23 1123 – FACILITY NATURAL GAS PIPING**
 - **REMOVE** 3.1.Q.4. – the meter will be set, and meter concrete foundations will be provided by others.
- **SECTION 23 8239 – STEEL WATER TUBE BOILERS (HEATING WATER, MODULAR TYPE)**
 - **REVISE** 3.1.A. to 4" height on boiler pads.
- **SECTION 23 8239 – UNIT HEATERS**
 - **REMOVE** References to steam unit heaters. No steam unit heaters are in the project.

CHANGES TO THE DRAWINGS - WESTWOOD

- **00-MP00 – MECHANICAL & PLUMBING GENERAL INFORMATION**
 - **ADD** section outlining State Historical Preservation Office Requirements
- **00-E000 – ELECTRICAL GENERAL INFORMATION**
 - **REVISE** Description for wall mounted occupancy and ceiling devices description to include “ALL DEVICES TO BE PASSIVE INFRARED”
 - **ADD** section outlining State Historical Preservation Office Requirements
- **01-A101 - WESTWOOD FLOOR PLANS & RCPs**
 - **REVISE** CEILING PLAN NOTES to exclude note 6 regarding use of owner ceiling panel stock.
- **01-M500 – MECHANICAL DETAILS**
 - **REVISE** details F2 and F3 to read (heating water) instead of (chilled water). The intent is for the detail to apply to all heating water piping.
- **01-ED102 – SECOND AND THIRD FLOOR ELECTRICAL DEMOLITION PLAN**
 - **REVISE** Keynote 01-ED10 to state “KEYNOTE TYPICAL FOR ROOM 221, 220, 219, 216 215, 213 AND 200. SUPPORT ALL EXISTING CEILING MOUNTED ELECTRICAL DEVICES IN THE CEILING INCLUDED LIGHT FIXTURES, EXIT LIGHTS, SPEAKERS, AND FIRE ALARM DEVICES WHILE THE CEILING IS REMOVED TO INSTALL PIPING. REINSTALL THE EXISTING CEILING MOUNTED ELECTRICAL DEVICES IN THE CEILING AFTER MECHANICAL PIPING IS COMPLETE. REFER TO 01-AD01 FOR LOCATIONS OF CEILING REMOVED.”
- **01-E100 – BASEMENT LEVEL ELECTRICAL PLAN**
 - **REVISE** Keynote 01-E004 to state “CO DETECTOR (PROVIDED BY BP #22-1 MECHANICAL CONTRACTOR).”

CHANGES TO THE DRAWINGS - ADMIN BUILDING

- **02-E301 – ELECTRICAL ADMINISTRATION FIRE ALARM UPGRADES**
 - **ADD** To keynote 02-E002 “COORDINATE EXACT LOCATION WITH OWNER PRIOR TO ROUGH-IN.”

CHANGES TO THE DRAWINGS - MYERS HALL

- **04-AD01 – DEMOLITION PLANS**
 - Per detail A4 include demo note AD.03 for the two (2) door frames by the stairs in the vestibule near the general assembly rooms.
- **04-FP100 - BASEMENT FIRE PROTECTION PLAN**
 - **REVISE** notes 18 and 19 to read “NOT USED.”
- **04-FP101 - FIRST FLOOR FIRE PROTECTION PLAN**
 - **REVISE** notes 18 and 19 to read “NOT USED.”
 - **ADD** dry system riser to sheet.

- **04-FP102 - SECOND FLOOR FIRE PROTECTION PLAN**
 - **REVISE** notes 18 and 19 to read “NOT USED.”
 - **ADD** dry system riser to sheet.
 - **ADD** keynote 04-E025 to sheet.
 - **REMOVE** fire alarm devices that are not associated with the fire pump portion of the project. Due to source of funding, fire alarm devices associated with fire pump portion of project are required to be broken out as a separate price. Refer to bid package descriptions for more information. Refer to fire alarm sheets for remaining fire alarm devices.
- **04-FP103 - ATTIC FIRE PROTECTION PLAN**
 - **ADD** sheet to project.
- **04-FP300 - FIRE PUMP PLANS, DETAILS & SCHEDULES**
 - **REVISE** SPRINKLER RISER DIAGRAM to show dry sprinkler riser.
 - **ADD** dry sprinkler riser to FIRE PUMP PLAN.
- **04-MD100 – BASEMENT MECHANICAL PIPING DEMOLITION PLAN**
 - **ADD** keynote 04-MD5 regarding demolition of steam piping. See attached sheet for further information.
- **04-M100 – BASEMENT MECHANICAL PIPING PLAN**
 - **ADD** keynote 04-M05 regarding exhaust fan.
- **04-M500 – MECHANICAL DETAILS**
 - **REVISE** details F6 and D6 to read (heating water) instead of (chilled water). The intent is for the detail to apply to all heating water piping. Added detail 5 regarding pot feeder piping detail.
- **04-M600 – MECHANICAL SCHEDULES**
 - **CLARIFICATION** – Boiler efficiency listed in schedule is rated at 100% input, 20°F delta T and 120°F return water temperature.
- **04-E100 – BASEMENT LEVEL ELECTRICAL PLAN**
 - **ADD** Keynote to DETECTOR in Boiler B05 keynote state in “CO DETECTOR (PROVIDED BY MECHANICAL CONTRACTOR).”
 - **ADD** Electrical connection for dry pipe air compressor. Connection located in Boiler B05. Circuit to 20A/1P breaker in panel ‘SBLB’ with 2#12 and 1#12 GND in ¾” C. Non fused disconnect for air compressor to be furnished and installed by electrical contractor in Alternate #05.

SUBSTITUTION REQUESTS

SECTION	ITEM	SUBSTITUTION AND/OR APPROVED EQUAL
26 5100	L10	C-Lite LED Lighting
23 2113	Flow Balancing Kits	HCi
23 2113	Expansion Tank	Grundfos
23 8239	Unit Heaters	Daikin

ATTACHMENTS

1. **Specification sections:** 00 0110 – Table of Contents, 00 0115 – List of Drawing Sheets, 09 9123 – Interior Painting, and 21 1316 – Dry Pipe Fire Suppression Sprinkler Systems.
2. **Drawings:** 00-MP00, 04-FP101, 04-FP102, 04-FP103, 04-FP300, 04-MD100, 04-M100, and 04-M500
3. Hazardous Materials Report
4. Cottage 201 Asbestos Clarification
5. Pre-Bid Sign in Sheet held on 2/1/2023.

END OF ADDENDUM

SECTION 00 0110

TABLE OF CONTENTS

PROCUREMENT AND CONTRACTING REQUIREMENTS

1.01 DIVISION 00 – PROCUREMENT AND CONTRACTING REQUIREMENTS

A.	00 0101	Project Title Page
B.	00 0107	Seals Page
C.	00 0110	Table of Contents
D.	00 0115	List of Drawing Sheets
E.	00 0116	Bid Submittal Checklist
F.	00 1113	Notice to Bidders
G.	00 2113	Instructions to Bidders
H.	00 2113.01	IMPACS Electronic Procurement System Instructions
I.	00 3113	Preliminary Schedule
J.	00 3143	Permit Application
K.	00 4116	Bid Requirements
L.	00 4116.01	Non Discrimination Clause Information
M.	00 4116.02	Targeted Small Business Information
N.	00 4313	Bid Security Forms
O.	00 5200	Agreement Form
P.	00 6000	Payment Bond and Performance Bond Forms

SPECIFICATIONS

2.01 DIVISION 01 – GENERAL REQUIREMENTS

A.	01 1200	Contract Summary
B.	01 2500	Substitution Procedures <i>(Form Provided by Architect)</i>
C.	01 2600	Contract Modification Procedures
D.	01 2900	Payment Procedures
E.	01 3100	Project Management and Coordination
F.	01 3100.01	Web Based Construction Management
G.	01 3200	Construction Progress Documentation
H.	01 3300	Submittal Procedures
I.	01 4000	Quality Requirements
J.	01 5000	Temporary Facilities and Controls
K.	01 6000	Product Requirements
L.	01 7300	Execution
M.	01 7700	Closeout Procedures
N.	01 8100	Building Systems General Commissioning Requirements

2.02 Division 02 – EXISTING CONDITIONS

A.	02 41 00	Demolition
----	----------	------------

2.03 Division 6 – WOOD, PLASTIC, AND COMPOSITES

A.	06 10 00	Rough Carpentry
----	----------	-----------------

2.04 Division 7 – THERMAL AND MOISTURE PROTECTION

- A. 07 84 00 Fire Stopping
- B. 07 90 00 Joint Sealants

2.05 Division 8 – OPENINGS

- A. 08 06 71 Door Hardware Schedule
- B. 08 11 13 Hollow Metal Doors and Frames

2.06 Division 9 – FINISHES

- A. 09 21 16 Gypsum Board Assemblies
- B. 09 51 00 Acoustical Ceilings
- C. 09 91 23 Interior Painting

2.07 Division 21 – FIRE SUPPRESSION

- A. 21 05 23 General Duty Valves for Water Based Fire Suppression
- B. 21 05 53 Identification for Fire Suppression Piping and Equipment
- C. 21 11 00 Facility Fire Suppression Water Service Piping
- D. 21 13 00 Fire Suppression Sprinkler Systems
- E. 21 13 16 Dry Pipe Fire Suppression Sprinkler Systems
- F. 21 31 00 Fire Pumps

ADDM
#1

2.08 Division 22 – PLUMBING

- A. 22 05 00 Common Work Results for Plumbing
- B. 22 05 19 Meters and Gauges for Plumbing Piping
- C. 22 05 23 General Duty Valves for Plumbing Piping
- D. 22 05 29 Hangers and Supports for Plumbing Piping and Equipment
- E. 22 05 53 Identification for Plumbing Piping and Equipment
- F. 22 07 00 Plumbing Insulation
- G. 22 11 16 Domestic Water Piping
- H. 22 11 19 Domestic Water Piping Specialties
- I. 22 13 16 Sanitary Waste and Vent Piping
- J. 22 13 19 Sanitary Waste Piping Specialties

2.09 Division 23 – HVAC

- A. 23 05 00 Common Work Results for HVAC
- B. 23 05 13 Common Motor Requirements for HVAC Equipment
- C. 23 05 19 Meters and Gauges for HVAC Piping
- D. 23 05 23 General Duty Valves for HVAC Piping
- E. 23 05 29 Hangers and Supports for HVAC Piping and Equipment
- F. 23 05 48 Vibration and Seismic Controls for Plumbing, HVAC Piping and Equipment
- G. 23 05 53 Identification for HVAC Piping and Equipment
- H. 23 05 93 Testing, Adjusting, and Balancing for HVAC
- I. 23 07 00 HVAC Insulation
- J. 23 08 00 Mechanical Commissioning Requirements
- K. 23 09 23 Direct Digital Control System for HVAC
- L. 23 11 23 Facility Natural Gas Piping
- M. 23 21 13 Hydronic Piping
- N. 23 21 23 Hydronic Pumps
- O. 23 25 00 HVAC Water Treatment
- P. 23 52 16 Steel Water Tube Boilers (Heating Water, Modular Type)
- Q. 23 82 33 Convectors and Finned Tube Radiation
- R. 23 82 39 Unit Heaters

2.010 Division 26 – ELECTRICAL

- A. 26 05 00 Common Work Results for Electrical
- B. 26 05 05 Selective Demolition for Electrical
- C. 26 05 19 Low Voltage Electrical Power Conductors and Cables
- D. 26 05 26 Grounding and Bonding for Electrical Systems
- E. 26 05 29 Hangers and Supports for Electrical Systems
- F. 26 05 33.13 Conduit for Electrical Systems
- G. 26 05 33.16 Boxes for Electrical Systems
- H. 26 05 53 Identification for Electrical Systems
- I. 26 09 23 Lighting Control Devices
- J. 26 24 16 Panelboards
- K. 26 27 26 Wiring Devices
- L. 26 28 13 Fuses
- M. 26 28 16.16 Enclosed Switches
- N. 26 51 00 Interior Lighting

2.011 Division 27 – COMMUNICATIONS

- A. 27 13 00 Communications Backbone Cabling

2.012 Division 28 – ELECTRONIC SAFETY AND SECURITY

- A. 28 05 13 Conductors and Cables for Electronic Safety and Security
- B. 28 05 28 Pathways for Electronic Safety and Security
- C. 28 31 11 Digital, Addressable Fire Alarm System

END OF SECTION

SECTION 00 0115

LIST OF DRAWING SHEETS

DRAWINGS

1.01	SHEET	TITLE
	1. 00-G000	Cover Sheet
	2. 00-G001	Campus Map
	3. 00-MP00	Mechanical & Plumbing General Information
	4. 00-E000	Electrical General Information
	5. 01-AD01	Westwood Demo Floor Plans & Demo Reflected Ceiling Plans
	6. 01-A101	Westwood Floor Plans & RCPs
	7. 01-MD100	Basement Mechanical Piping Demolition Plan
	8. 01-MD101	First Floor Mechanical Piping Demolition Plan
	9. 01-MD102	Second and Third Floor Mechanical Piping Demolition Plan
	10. 01-M100	Basement Mechanical Piping Plan
	11. 01-M101	First Floor Mechanical Piping Plan
	12. 01-M102	Second and Third Floor Mechanical Piping Plan
	13. 01-M103	Thermostat Zoning Plans
	14. 01-M500	Mechanical Details
	15. 01-M501	Controls
	16. 01-M600	Mechanical Schedules
	17. 01-ED100	Basement Level Electrical Demolition Plan
	18. 01-ED101	First Floor Electrical Demolition Plan
	19. 01-ED102	Second and Third floor Electrical Demolition Plan
	20. 01-E100	Basement Level Electrical Plan
	21. 01-E101	First Floor Electrical Plan
	22. 01-E102	Second and Third Floor Electrical Plan
	23. 01-ED300	Basement Level Fire Alarm Demolition Plan
	24. 01-ED301	First Floor Fire Alarm Demolition Plan
	25. 01-ED302	Second and Third Floor Fire Alarm Demolition Plan
	26. 01-E300	Basement Level Fire Alarm Plan
	27. 01-E301	First Floor Fire Alarm Plan
	28. 01-E302	Second and Third Floor Fire Alarm Plan
	29. 02-E301	Electrical Administration Fire Alarm Upgrades
	30. 04-AD01	Demolition Plans
	31. 04-A110	Basement and First Floor Plans & Doors
	32. 04-A111	Second Floor Reflected Ceiling Plan
	33. 04-P100	Plumbing Plans
	34. 04-FP000	Fire Protection General Information
	35. 04-FP100	Basement Fire Protection Plan
	36. 04-FP101	First Floor Fire Protection Plan
	37. 04-FP102	Second Floor Fire Protection Plan
	38. 04-FP103	Attic Fire Protection Plan
	39. 04-FP300	Fire Pump Plans, Details, & Schedules
	40. 04-MD100	Basement Mechanical Piping Demolition Plan
	41. 04-MD101	First Floor Mechanical Piping Demolition Plan
	42. 04-MD102	Second Floor Mechanical Piping Demolition Plan
	43. 04-M100	Basement Mechanical Piping Plan
	44. 04-M101	First Floor Mechanical Piping Plan
	45. 04-M102	Second Floor Mechanical Piping Plan
	46. 04-M103	Thermostat Zoning Plans

ADDM
#1

47. 04-M500	Mechanical Details
48. 04-M501	Controls
49. 04-M502	Controls
50. 04-M600	Mechanical Schedules
51. 04-ED100	Basement Level Electrical Demolition Plan
52. 04-ED101	First Floor Electrical Demolition Plan
53. 04-ED102	Second Floor Electrical Demolition Plan
54. 04-E100	Basement Level Electrical Plan
55. 04-E101	First Floor Electrical Plan
56. 04-E102	Second Floor Electrical Plan
57. 04-ED300	Basement Level Fire Alarm Demolition Plan
58. 04-ED301	First Floor Fire Alarm Demolition Plan
59. 04-ED302	Second Floor Fire Alarm Demolition Plan
60. 04-E300	Basement Level Fire Alarm Plan
61. 04-E301	First Floor Fire Alarm Plan
62. 04-E302	Second Floor Fire Alarm Plan
63. 04-E600	Electrical Schedules
64. C1-ED301	Cottage Style A Fire Alarm Demolition Plan
65. C1-E301	Cottage Style A Fire Alarm Plans
66. C2-ED301	Cottage Style B Fire Alarm Demolition Plan
67. C2-E301	Cottage Style B Fire Alarm Plans
68. C3-ED301	Cottage Style C Fire Alarm Demolition Plan
69. C3-E301	Cottage Style C Fire Alarm Plans

END OF SECTION

**SECTION 09 9123
INTERIOR PAINTING**

PART 1 GENERAL

1.1 SECTION INCLUDES

- A. Surface preparation.
- B. Field application of paints.
- C. Scope: Finish new wall, new door and frame, and other surfaces as indicated.
- D. Do Not Paint or Finish the Following Items:
 - 1. Items factory-finished unless otherwise indicated; materials and products having factory-applied primers are not considered factory finished.
 - 2. Items indicated to receive other finishes.
 - 3. Items indicated to remain unfinished.
 - 4. Fire rating labels, equipment serial number and capacity labels, bar code labels, and operating parts of equipment.
 - 5. Floors, unless specifically indicated.
 - 6. Concealed pipes, ducts, and conduits.

1.2 DEFINITIONS

- A. Comply with ASTM D16 for interpretation of terms used in this section.

1.3 REFERENCE STANDARDS

- A. 40 CFR 59, Subpart D - National Volatile Organic Compound Emission Standards for Architectural Coatings; U.S. Environmental Protection Agency current edition.
- B. ASTM D16 - Standard Terminology for Paint, Related Coatings, Materials, and Applications 2019.
- C. MPI (APL) - Master Painters Institute Approved Products List; Master Painters and Decorators Association Current Edition.
- D. MPI (APSM) - Master Painters Institute Architectural Painting Specification Manual Current Edition.
- E. SSPC-SP 1 - Solvent Cleaning 2015, with Editorial Revision (2016).
- F. SSPC-SP 6 - Commercial Blast Cleaning 2007.

1.4 SUBMITTALS

- A. Product Data: Provide complete list of products to be used, with the following information for each:
 - 1. Manufacturer's name, product name and/or catalog number, and general product category (e.g., "alkyd enamel").
 - 2. MPI product number (e.g., MPI #47).

3. Cross-reference to specified paint system(s) product is to be used in; include description of each system.
 - B. Samples: Submit three paper "draw down" samples, 8-1/2 by 11 inches (216 by 279 mm) in size, illustrating range of colors available for each finishing product specified.
 1. Where sheen is specified, submit samples in only that sheen.
 - C. Certification: By manufacturer that paints and finishes comply with VOC limits specified.
- 1.5 DELIVERY, STORAGE, AND HANDLING
- A. Deliver products to site in sealed and labeled containers; inspect to verify acceptability.
 - B. Container Label: Include manufacturer's name, type of paint, brand name, lot number, brand code, coverage, surface preparation, drying time, cleanup requirements, color designation, and instructions for mixing and reducing.
 - C. Paint Materials: Store at minimum ambient temperature of 45 degrees F (7 degrees C) and a maximum of 90 degrees F (32 degrees C), in ventilated area, and as required by manufacturer's instructions.
- 1.6 FIELD CONDITIONS
- A. Do not apply materials when surface and ambient temperatures are outside the temperature ranges required by the paint product manufacturer.
 - B. Follow manufacturer's recommended procedures for producing best results, including testing of substrates, moisture in substrates, and humidity and temperature limitations.
 - C. Do not apply materials when relative humidity exceeds 85 percent, at temperatures less than 5 degrees F (3 degrees C) above the dew point, or to damp or wet surfaces.
 - D. Minimum Application Temperatures for Paints: 50 degrees F (10 degrees C) for interiors unless required otherwise by manufacturer's instructions.
 - E. Provide lighting level of 80 ft candles (860 lx) measured mid-height at substrate surface.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Provide paints and finishes from the same manufacturer to the greatest extent possible.
- B. Paints:
 1. Diamond Vogel Paints: www.diamondvogel.com/#sle.
 2. PPG Paints: www.ppgpaints.com/#sle.
 3. Sherwin-Williams Company: www.sherwin-williams.com/#sle.
 4. Architect Pre-Approved Equivalent.

ADDM
#1

2.2 PAINTS AND FINISHES - GENERAL

- A. Paints and Finishes: Ready-mixed, unless intended to be a field-catalyzed paint.
 1. Where MPI paint numbers are specified, provide products listed in Master Painters Institute Approved Product List, current edition available at www.paintinfo.com, for specified MPI categories, except as otherwise indicated.

2. Provide paints and finishes of a soft paste consistency, capable of being readily and uniformly dispersed to a homogeneous coating, with good flow and brushing properties, and capable of drying or curing free of streaks or sags.
 3. Provide materials that are compatible with one another and the substrates indicated under conditions of service and application, as demonstrated by manufacturer based on testing and field experience.
 4. Supply each paint material in quantity required to complete entire project's work from a single production run.
 5. Do not reduce, thin, or dilute paint or finishes or add materials unless such procedure is specifically described in manufacturer's product instructions.
- B. Volatile Organic Compound (VOC) Content:
1. Provide paints and finishes that comply with the most stringent requirements specified in the following:
 - a. 40 CFR 59, Subpart D--National Volatile Organic Compound Emission Standards for Architectural Coatings.
 - b. Architectural coatings VOC limits of State in which the project is located.
 2. Determination of VOC Content: Testing and calculation in accordance with 40 CFR 59, Subpart D (EPA Method 24), exclusive of colorants added to a tint base and water added at project site; or other method acceptable to authorities having jurisdiction.
- C. Sheens: Provide the sheens specified; where sheen is not specified, sheen will be selected later by Architect/Engineer from the manufacturer's full line.
- D. Colors:
1. Selection to be made by Architect/Engineer after award of contract.

2.3 PAINT SYSTEMS - INTERIOR

- A. Paint I-OP - Interior Surfaces to be Painted, Unless Otherwise Indicated: Including gypsum board, uncoated steel, shop primed steel, and galvanized steel.
1. Paint hollow metal doors and door frames in all spaces indicated to receive new finishes.
 2. Two top coats and one coat primer.
 3. Top Coat(s): High Performance Architectural Interior Latex; MPI #138, 139, 140, or 141.
 - a. Products:
 - 1) Sherwin-Williams Pre-Catalyzed Waterbased Epoxy, Eg-Shel. (MPI #139)
 - 2) Sherwin-Williams Pre-Catalyzed Waterbased Epoxy, Semi-Gloss. (MPI #141)
 - 3) Substitutions: Architect Pre-Approved Equivalent.
 4. Top Coat Sheen:
 - a. Eggshell: MPI gloss level 3; use this sheen at gypsum wallboard locations.
 - b. Semi-Gloss: MPI gloss level 5; use this sheen for hollow metal doors and frames.
 5. Primer: As recommended by top coat manufacturer for specific substrate.

2.4 ACCESSORY MATERIALS

- A. Accessory Materials: Provide primers, sealers, cleaning agents, cleaning cloths, sanding materials, and clean-up materials as required for final completion of painted surfaces.

- B. Patching Material: Latex filler.
- C. Fastener Head Cover Material: Latex filler.

PART 3 EXECUTION

3.1 EXAMINATION

- A. Do not begin application of paints and finishes until substrates have been adequately prepared.
- B. Verify that surfaces are ready to receive work as instructed by the product manufacturer.
- C. Examine surfaces scheduled to be finished prior to commencement of work. Report any condition that may potentially affect proper application.
- D. If substrate preparation is the responsibility of another installer, notify Architect/Engineer of unsatisfactory preparation before proceeding.
- E. Test shop-applied primer for compatibility with subsequent cover materials.
- F. Measure moisture content of surfaces using an electronic moisture meter. Do not apply finishes unless moisture content of surfaces is below the following maximums:
 - 1. Gypsum Wallboard: 12 percent.

3.2 PREPARATION

- A. Clean surfaces thoroughly and correct defects prior to application.
- B. Prepare surfaces using the methods recommended by the manufacturer for achieving the best result for the substrate under the project conditions.
- C. Remove or repair existing paints or finishes that exhibit surface defects.
- D. Remove or mask surface appurtenances, including electrical plates, hardware, light fixture trim, escutcheons, and fittings, prior to preparing surfaces or finishing.
- E. Seal surfaces that might cause bleed through or staining of topcoat.
- F. Remove mildew from impervious surfaces by scrubbing with solution of tetra-sodium phosphate and bleach. Rinse with clean water and allow surface to dry.
- G. Gypsum Board: Fill minor defects with filler compound. Spot prime defects after repair.
- H. Galvanized Surfaces:
 - 1. Remove surface contamination and oils and wash with solvent according to SSPC-SP 1.
- I. Ferrous Metal:
 - 1. Solvent clean according to SSPC-SP 1.
 - 2. Shop-Primed Surfaces: Sand and scrape to remove loose primer and rust. Feather edges to make touch-up patches inconspicuous. Clean surfaces with solvent. Prime bare steel surfaces. Re-prime entire shop-primed item.
 - 3. Remove rust, loose mill scale, and other foreign substances using methods recommended in writing by paint manufacturer and blast cleaning according to SSPC-SP 6 "Commercial Blast Cleaning". Protect from corrosion until coated.

3.3 APPLICATION

- A. Apply products in accordance with manufacturer's written instructions and recommendations in "MPI Architectural Painting Specification Manual".
- B. Do not apply finishes to surfaces that are not dry. Allow applied coats to dry before next coat is applied.
- C. Apply each coat to uniform appearance in thicknesses specified by manufacturer.
- D. Vacuum clean surfaces of loose particles. Use tack cloth to remove dust and particles just prior to applying next coat.
- E. Reinstall electrical cover plates, hardware, light fixture trim, escutcheons, and fittings removed prior to finishing.

3.4 CLEANING

- A. Collect waste material that could constitute a fire hazard, place in closed metal containers, and remove daily from site.

3.5 PROTECTION

- A. Touch-up damaged finishes after Substantial Completion.

END OF SECTION

PART 1 GENERAL

1.1 SUMMARY

- A. Provide equipment, material, devices, labor, and supervision necessary to fabricate and erect hydraulically designed Dry Pipe Suppression Sprinkler System as required by the Drawings and this Section.

1.2 CODES AND REGULATIONS

- A. Sprinkler system design, equipment, materials, devices, and installation shall conform to NFPA Codes and Requirements of Governmental Bodies and Bureaus as listed below:
 - 1. NFPA 13, 14, 24, 75 and other standards as applicable.
 - 2. Local Fire Department
 - 3. State Fire Marshal
 - 4. International Building Code
 - 5. Factory Mutual (FM)
 - 6. Underwriters Laboratory (UL)

1.3 QUALIFICATIONS

- A. All installation work shall be performed by licensed fire protection sprinkler contractors, licensed for such work where the work is to be performed.

1.4 WIRING

- A. The Division 26 Contractor shall furnish wiring for signal and alarm devices furnished by sprinkler contractor.

1.5 SPRINKLER DESIGN

- A. Flow tests taken by Iowa Fire Equipment Company at the hydrant near "Employee Home or E-Home" indicates a static pressure of 40 psi and residual pressure of 26 psi with a flow of 342 GPM.
 - 1. There is an existing sprinkler system in the building that may have additional data available.

1.6 SUBMITTALS

- A. Product Data: Submit manufacturer's technical product data and installation instructions for all fire protection materials and products.
- B. Shop Drawings: Submit scaled, dimensioned installation drawings and supporting hydraulic calculations. Provide drawings and calculations that have been approved by the Authority Having Jurisdiction and that are prepared and stamped by a Registered Engineer or by a technician with NICET level III certification.
- C. Contractor's Material & Test Certificate: Submit completed Contractor's Material & Test Certificate for each system.

- D. At project closeout, submit record drawings of installed fire protection piping and products.
- E. Submit operating and maintenance data and parts lists for fire protection materials and products. Include this data, product data, shop drawings, approved drawings, approved calculations, certificate of installation, and record drawings in maintenance manual.

PART 2 PRODUCTS

2.1 MANUFACTURERS

- A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
 - 1. Water Flow Indicators and Supervisory Switches
 - a. Potter Electric Signal Co.
 - b. System Sensor Div., Pittway Corp.
 - c. Engineer Pre-Approved Equivalent
 - 2. Sprinklers
 - a. ASCOA Fire Systems, Figgie International Co.
 - b. Central Sprinkler Corp.
 - c. Gem Sprinkler Co. Div., Grinnell Corp.
 - d. Globe Fire Sprinkler Corp.
 - e. Reliable Automatic Sprinkler Co., Inc.
 - f. Star Sprinkler Corp.
 - g. Viking Corp.
 - h. Engineer Pre-Approved Equivalent
 - 3. Fire Protection Service Gate and Check Valves
 - a. Gem Sprinkler Co. Div., Grinnell Corp.
 - b. Kennedy Valve Div., McWane, Inc.
 - c. Nibco, Inc.
 - d. Stockham Valves and Fittings, Inc.
 - e. Victaulic Company of America
 - f. Central Sprinklers Corp.
 - g. Engineer Pre-Approved Equivalent
 - 4. Grooved Couplings for Steel Piping
 - a. Grinnell Supply Sales Co., Grinnell Corp.
 - b. Gustin-Bacon Div., Tyler Pipe Subsid., Tyler Corp.
 - c. Stockham Valves and Fittings, Inc.

- d. Victaulic Company of America
 - e. Central Sprinklers Corp.
 - f. Engineer Pre-Approved Equivalent
5. Dry Pipe Valves
- a. Victaulic
 - b. Grinnell Supply Sales Co., Grinnell Corp.
 - c. Reliable Automatic Sprinkler Co., Inc.
 - d. Viking Corp.
 - e. ASCOA Fire Systems, Figgie International Co.
 - f. Central Sprinklers Corp.
 - g. Engineer Pre-Approved Equivalent
6. Air Compressors
- a. Victaulic
 - b. Gast
 - c. Speedaire
 - d. Thomas Compressors and Vacuum Pumps
 - e. Ingersoll-Rand Air Compressors
 - f. Engineer Pre-Approved Equivalent

2.2 PIPES

- A. Refer to Part 3 Article "Sprinkler System Piping Applications" for identification of systems where pipe and fitting materials specified below are used.
- B. Steel Pipe: ASTM A53, Schedule 40, galvanized, plain and threaded ends, for threaded, cut-groove, and rolled-groove joints.
- C. Steel Pipe: ASTM A 135, Schedule 10, galvanized, with plain ends for rolled-groove joints.

2.3 PIPE FITTINGS

- A. Grooved-End Fittings for Ductile-Iron Pipe: ASTM A 536 ductile-iron or ASTM A 47 malleable-iron, AWWA pipe-size, designed to accept AWWA C606 grooved couplings. Include cement lining or Food and Drug Administration (FDA)-approved interior coating.
- B. Steel Fittings: ASTM A234, seamless or welded; ASME B16.9, butt welding; or ASME B16.11, socket-welding type for welded joints.
- C. Steel Flanges and Flanged Fittings: ASME B16.5.
- D. Grooved-End Fittings for Steel Pipe: UL-listed and FM-approved, ASTM A536, Grade 65-45-12 ductile iron or ASTM A 47 Grade 32510 malleable iron, with grooves or shoulders designed to accept grooved couplings.

2.4 JOINING MATERIALS

- A. Refer to Division 22 for joining materials not included in this Section.

2.5 GENERAL-DUTY VALVES

- A. Refer to Division 21 for general-duty gate and ball valves.

2.6 FIRE PROTECTION SERVICE VALVES

- A. General: UL-listed and FM-approved, with 175-psig non-shock minimum working pressure rating.
1. Option: Valves for use with grooved piping may be grooved type.

2.7 SPECIALTY VALVES

- A. Ball Drip Valves: UL 1726 automatic drain valve, 3/4-inch size, spring-loaded, ball check device with threaded ends.
- B. Dry Pipe Valves shall be UL-listed and FM-approved, with 175-psig working pressure. Include trim sets for bypass, drain, electric sprinkler alarm switch, air pressure monitoring switch, pressure gauges, precision retarding chamber, air line, and fill line attachment with strainer.
1. Drip Cup Assembly: Pipe drain with check valve to main drain piping.
 2. Option: Grooved-end connections for use with grooved-end piping.
 3. Provide all required pipe nipples and fittings for operation with standard galvanized finish.
 4. Provide all trim accessories required for operation.
 5. Provide all required gauges for operation.
 6. Provide alarm pressure switch.
 7. Dry Accelerator.
 8. Provide air supervisory pressure switch.
 9. Provide air supply system for establishing and maintaining air in the system.
 - a. Compressor.
 - b. Low-pressure alarms.
 - c. Ball valves.
 - d. Required trim.

2.8 SPRINKLERS

- A. Automatic Sprinklers with quick-response element conforming to:
1. UL 199 and FM-approved, for applications except residential.
- B. Sprinkler types and categories are as indicated and as required by application. Furnish automatic sprinklers with nominal 1/2-inch orifice and 1/2-inch NPT.
- C. Sprinkler heads shall be of the following types:
1. Dry pendant, quick response, recessed type chrome-plated, two piece escutcheon ring, Reliable model F3QR series or approved equivalent.

- 2. Areas without finished ceilings, in concealed spaces and under ducts; quick response, upright-type head for exposed piping, brass finish, Reliable F1FR series or approved equivalent.
- D. Sprinkler heads shall be of the ordinary temperature range 160oF except where subject to high temperatures caused by unit heaters, hot pipes, radiant ceilings, or other heat source, heads shall be of high temperature type, 250oF.
- E. Sprinkler Guards: Wire-cage type, including fastening device for attaching to sprinkler.
- F. Sprinkler Cabinets: Finished steel cabinet and hinged cover, with space for minimum of 6 spare sprinklers plus sprinkler wrench, suitable for wall mounting. Include number of sprinklers required by NFPA 13 and 1 wrench for sprinklers. Include separate cabinet with sprinklers and wrench for each style sprinkler on project.

2.9 SPECIALTY SPRINKLER FITTINGS

- A. Mechanical "T" Fittings: UL 213, ductile-iron housing with pressure-responsive gasket, bolts, and threaded or locking-lug outlet.
- B. Mechanical Cross Fittings: UL 213, ductile-iron housing with pressure-responsive gaskets, bolts, and threaded or locking-lug outlets.
- C. Drop-Nipple Fittings: UL 1474, with threaded inlet, threaded outlet, and seals; adjustable.
- D. Sprinkler Alarm Test Fittings: Ductile-iron housing with 1-1/2-inch (DN 40) inlet and outlet, integral test valves, combination orifice and sight glass, and threaded or locking lug ends.

2.10 ALARM DEVICES

- A. Alarm Devices: Types and sizes that will match piping and equipment connections.
- B. Waterflow Indicators: UL 346, electrical-supervision type, vane-type Waterflow detector, rated to 250 psig, and designed for horizontal or vertical installation. Include 2 SPDT (single-pole, double-throw) circuit switches to provide isolated alarm and auxiliary contacts, 7 ampere, 125 volts AC and 0.25 ampere, 24 volts DC; complete with factory-set, field-adjustable retard element to prevent false signals, and tamper-proof cover that sends a signal when cover is removed.
- C. Supervisory Switches: UL 753 for valves, electrical-supervision type, SPDT (single-pole, double-throw), normally closed contacts, designed to signal controlled valve in other than full open position.
- D. Supervisory Switches: UL 753 for indicator posts, electrical-supervision type, SPDT (single-pole, double-throw), normally closed contacts, designed to signal controlled valve in other than full open position.
- E. Supervisory Pressure Switches: UL 753, for low air alarm, air pressure switch with retard, electrical-supervision type, SPDT (single-pole, double-throw), normally closed contacts, designed to operate on rise or drop in air pressure.

2.11 PRESSURE GAUGES

- A. Pressure Gauges: UL 393, 3½" to 4½" diameter dial, with dial range of 0-250 psig.

PART 3 EXECUTION

3.1 SPRINKLER SYSTEM PIPING APPLICATIONS

- A. Refer to Part 2 of this Section for detailed specifications on pipe and fittings products listed below. Use pipe, fittings, and joining methods according to the following applications. Piping may be joined with flanges instead of indicated joints. Use grooved-end fittings with grooved couplings that are made by the same manufacturer and that comply with listing when used together for grooved-coupling joints.
 - 1. Option: Mechanical "T" bolted-branch-outlet fittings, instead of fitting types specified may be used for branch connections.
- B. Sizes 10" and Smaller for Dry Pipe Systems: ASTM A53 or A135 Schedule 40 galvanized steel pipe with rolled-groove or cut-groove ends, grooved-end steel pipe fittings, and grooved-coupling joints.
- C. Sizes 2-1/2" to 6" for Dry Pipe Systems: ASTM A135 or A795, Schedule 10 galvanized steel pipe with rolled groove ends, grooved-end steel pipe fittings, and grooved-coupling joints.

3.2 VALVE APPLICATIONS

- A. Drawings indicate valve types to be used. Where specific valve types are not indicated, the following requirements apply:
 - 1. Shut-off Duty: Use gate, ball, or butterfly valves.
 - 2. Throttling Duty: Use globe, ball, or butterfly valves.

3.3 JOINT CONSTRUCTION

- A. Grooved-End Pipe and Grooved-End Fitting Joints: Use groove-end fittings and grooved couplings that are made by the same manufacturer and that are listed for use together. Groove pipe and assemble joints with grooved coupling, gasket, lubricant, and bolts according to coupling and fitting manufacturer's written instructions.
- B. Mechanically Formed Outlet Joints: Use UL-listed procedure and follow forming equipment manufacturer's written instructions. Drill pilot hole in tube, form branch for collar, dimple tube to form seating stop, and braze branch tube into formed-collar outlet.
- C. Locking-Lug Joints: Follow manufacturer's written instructions.

3.4 PIPING INSTALLATIONS

- A. Locations and Arrangements: Drawings (plans, schematics, and diagrams) indicate general location and arrangement of piping. Install piping as indicated, as far as practical.
 - 1. Deviations from approved shop drawings for sprinkler piping require written approval from authority having jurisdiction. File written approval with the Architect prior to deviating from approved shop drawings.
- B. Use approved fittings to make changes in direction, branch takeoffs from mains, and reductions in pipe sizes.
- C. Install flanges or flange adapters on valves, apparatus, and equipment have 2½-inch and larger connections.
- D. Install combination Inspector's Test Connection and Drain in sprinkler piping, sized on the system riser, if acceptable to the authority having jurisdiction.

- E. Install sprinkler piping with drains for complete system drainage.
- F. Install ball drip valves to drain piping between fire department connections and check valves, and where indicated. Drain outside building.
- G. Install alarm devices in piping systems.
- H. Hangers and Supports: Comply with NFPA 13.
 - 1. Install hanger and support spacing and locations for steel piping joined with grooved mechanical couplings according to manufacturer's written instructions for rigid systems.
 - 2. Do not hang from joist bridging. Joist bridging is not considered structural.
- I. Install pressure gauges on riser. Include pressure gauges with connection not less than ¼" and with soft metal seated globe valve, arranged for draining pipe between gauge and valve. Install gauges to permit removal, and install where they will not be subject to freezing.
- J. Hold riser piping and components as close to wall as allowable. Install riser components vertically, when possible, rather than horizontally to minimize space requirements. Risers to second floor shall not pass through sales areas or electrical rooms.
- K. For dry pipe systems, no portion of the sprinkler system shall be gridded, looped, or arranged in such a manner as to allow water to flow to any sprinkler from more than one direction.

3.5 HYDRAULIC CALCULATIONS

- A. Size system piping such that total required system pressure at demand flow (including hose streams) is at least 5 psi less than the available pressure at demand flow. Include in calculations, the greater of the following:
 - 1. 8-psi allowance for future reduced pressure principle backflow preventer installed at service entrance.
 - 2. Actual backflow preventer installed.

3.6 VALVE INSTALLATIONS

- A. Refer to Division 21 for installation of general-duty valves. Install fire-protection specialty valves, trim, fittings, controls, and specialties according to NFPA 13, manufacturer's written instructions, and the authority having jurisdiction.
- B. Gate Valves: Install fire-protection service valves supervised-open, located to control sources of water supply excerpt from fire department connections. Where there is more than 1 control valve, provide permanently marked identification signs indicating portion of system controlled by each valve.
- C. Install tamper switches on valves controlling water supply to the sprinkler system.
- D. Install check valve in each water supply connection. Install backflow preventers instead of check valves in potable water supply sources.
- E. Install valve on each sprinkler line to sprinkler head in elevator hoistway or elevator equipment room. Valve shall be located outside of these areas. Valves shall be locked in the open position.
- F. Dry Pipe Valves: Install valves in vertical position for proper direction of flow, including bypass check valve and retard chamber drain line connection.
- G. Install permanent signs supported by chains identifying all drains, test connections, air supplies (for dry pipe systems), and water supply valves. Install placards indicating all hydraulic design criteria for each area and permanently attach placards to riser.

3.7 SPRINKLER APPLICATIONS

- A. Rooms without Ceilings: Upright sprinklers.
- B. Rooms with Ceilings: Recessed sprinklers.
- C. Sprinkler Temperature Ratings: Use sprinklers with the following temperature ratings in the applications listed unless noted otherwise on drawings:
 - 1. Ordinary Temperature Classification (165° F): Public areas, classrooms, offices, janitor's closets, mechanical equipment rooms.
 - 2. Intermediate Temperature Classification (212° F): Top of elevator hoistways where ambient temperatures can exceed 100° F, stock rooms.

3.8 SPRINKLER INSTALLATIONS

- A. Install sprinklers in locations indicated. When sprinkler locations are not indicated in an area, locate sprinklers to meet this specification.
- B. Install sprinklers in suspended ceiling in center of acoustical panels and in center of half of acoustical panels, as shown on plans. The location of sprinklers may deviate up to 3 inches from the center, provided the deviation is continued for all sprinklers in the rows of both directions.
- C. Install sprinkler guards on sprinklers in janitor closets, gymnasiums, and on non-recessed heads within 84 inches of the floor.

3.9 CONNECTIONS

- A. Connect water supplies to sprinkler systems. Include backflow preventers.
- B. Electrical Connections: Power wiring as specified in Division 26.
- C. For Dry Pipe Systems: Connect air lines to air compressor controlled by an automatic air maintenance device. Flexible connections and hose are not allowed.
- D. Follow NFPA 24 testing requirements of below ground piping prior to connecting to the above ground pipes.

3.10 FIELD QUALITY CONTROL

- A. Perform field acceptance tests of each fire protection system with Architect/Engineer and authority having jurisdiction present.
 - 1. Flush, test, and inspect sprinkler piping systems according to NFPA 13 Chapter "System Acceptance."
- B. Replace piping system components that do not pass test procedures specified then retest to demonstrate compliance. Repeat procedure until satisfactory results are obtained.
 - 1. Complete the Contractor's Material & Test Certificate and submit form promptly to Owner's representative and authority having jurisdiction.

3.11 CLEANING

- A. Clean dirt and debris from sprinklers. Replace sprinklers having paint other than factory finish with new sprinklers. Cleaning and reuse of painted sprinklers is prohibited.

3.12 COMMISSIONING

- A. Starting Procedures: Follow manufacturer's written procedures. If manufacturer prescribes no procedures, proceed as follows:
 - 1. Verify that valves, trim, fittings, controls, and accessories have been installed correctly and operate correctly.
 - 2. Verify that specified tests of piping are complete.
 - 3. Check that damaged sprinklers and sprinklers with paint or coating not specified have been replaced with new, correct type of sprinklers.
 - 4. Check that sprinklers are correct type, have correct finish and temperature ratings, and have guards where required for applications.
 - 5. Check that potable water supplies have correct type of backflow preventer.
 - 6. Check that fire department connections have threads compatible with local fire department equipment and have correct pressure rating.
 - 7. Fill wet pipe sprinkler systems with water.
 - 8. Fill dry pipe sprinkler systems with air.
 - 9. Energize circuits to electrical equipment and devices.
 - 10. Adjust operating controls and pressure settings.
- B. Coordinate with fire alarm system tests. Operate systems as required.

3.13 DEMONSTRATION

- A. Demonstrate equipment, specialties, and accessories. Review operating and maintenance information.
- B. Schedule demonstration with at least 7 days advance notice.

END OF SECTION

GENERAL MECHANICAL NOTES

- LIGHT LINES INDICATE EXISTING PIPING, DUCTWORK, EQUIPMENT, ETC. TO REMAIN. BOLD LINES INDICATE NEW PIPING, DUCTWORK, EQUIPMENT, ETC. TO BE INSTALLED BY THIS CONTRACT UNLESS NOT OTHERWISE NOTED.
- COORDINATE ROUGH-IN AND FINAL LOCATION OF DUCTWORK AND PIPING WITH LIGHTING, STRUCTURE, SPRINKLERS, ETC. PROVIDE OFFSETS AND/OR EASEMENTS, OR RELOCATE AS REQUIRED AVOIDING CONFLICTS WITH WORK OF OTHER TRADES.
- PROVIDE TEMPORARY FILTRATION ON RETURNS DURING CONSTRUCTION TO PREVENT DUST FROM SPREADING TO DUCTWORK, HVAC EQUIPMENT, AND NON-CONSTRUCTION AREAS.
- PIPING IS SHOWN IN SCHEMATIC FORM. ROUTE AS REQUIRED FOR CLEARANCE. VERIFY ROUTING AND CLEARANCES AND COORDINATE WITH OTHER TRADES PRIOR TO REMEDIATION.
- BREAK CONNECTIONS ARE REQUIRED FOR MAINTENANCE AND PIPING ITEMS THAT REQUIRE REMOVAL FOR MAINTENANCE.
- PIPE REDUCTIONS ON HORIZONTAL PIPING GOING FROM LARGER TO SMALLER SHALL BE MADE WITH CONCENTRIC REDUCERS. TOP FLAT FOR LIQUID SYSTEMS. CONCENTRIC REDUCERS MAY BE USED FOR FLOW GOING FROM SMALL TO LARGER SIZE PIPE.
- FIRE SAFE ALL PIPE PENETRATIONS PER UL AT RATED WALLS AND FLOORS.
- THERMOSTATS SHALL BE MOUNTED 4'-0" ABOVE FINISHED FLOOR.
- NEW FLOOR/WALL/CEILING PENETRATIONS REQUIRED FOR MECHANICAL PIPING INSTALLATION SHALL BE CLEANLY BORED AT RIGHT ANGLES. AS NEW PIPING IS INSTALLED, NEW PIPING PENETRATIONS SHALL BE NEATLY CAULKED TO FILL VOID. EXPOSED WALL PENETRATIONS SHALL BE FINISHED WITH ESCUTCHEONS.
- ALL NEW PIPING EXPOSED IN OCCUPIED SPACES SHALL HAVE PVC JACKETS INSTALLED OVER THE PIPING INSULATION. ANY PIPING REQUIRED TO BE EXPOSED SHALL BE INSTALLED VERTICALLY OR HORIZONTALLY IN LEAST VISIBLE LOCATIONS.
- ALL NEW EQUIPMENT AND ACCESSORIES (CIRCUIT SETTERS, CIRCULATION PUMPS, EXPANSION TANKS, ETC.) SHALL BE INSTALLED TO BE EASILY ACCESSIBLE.
- ALL CONDENSATE PIPING SHALL BE SLOPED 1/8" PER FOOT MINIMUM.
- CONTRACTOR SHALL PATCH/REPAIR ALL UNUSED OPENINGS AND MODIFIED FINISH SURFACES. PATCHING SHALL MATCH MATERIALS, FINISH, AND TEXTURE OF ADJACENT SURFACES.
- PATCH ANY REMAINING OPENINGS AND FILL EXCESSIVE GAPS. REWORK AND REFINISH TO MATCH ADJACENT STRUCTURES. FLASH AND SEAL ALL MECHANICAL AND ELECTRICAL PENETRATIONS THRU WALLS, CEILING, AND FLOORS WITH METAL FRAMEWORK OR ESCUTCHEONS. ALL OPENINGS SHALL BE PROPERLY SEALED TO MEET FIRE RATING NEEDS.
- HEATING AND WATER BRANCH PIPING TO TERMINAL HEATING DEVICES SHALL BE 3/4" PIPE SIZE UNLESS OTHERWISE NOTED.
- NEW WORK HAS BEEN SHOWN DIAGRAMMATICALLY AND DUE TO THE LIMITED SCALE OF THESE DRAWINGS, THE PLACEMENT AND ROUTING OF ALL DUCTWORK, PIPING, ETC. IS CONSIDERED SCHEMATIC IN NATURE. THEREFORE, THE DRAWINGS MAY NOT SHOW ALL OFFSETS AND TRANSITIONS, WHICH MAY BE REQUIRED. THE CONTRACTOR SHALL PROVIDE COMPLETE FULLY FUNCTIONAL SYSTEMS.
- ALL WORK WITHIN THE CONTRACT DOCUMENTS SHALL BE COMPLETED IN A SAFE MANNER AND IN ACCORDANCE WITH ALL APPLICABLE STATE AND NATIONAL CODES, REGULATIONS, AND ORDINANCES. IF ANY CONFLICTS ARISE BETWEEN THE CONTRACT DOCUMENTS AND THE APPLICABLE CODES, REGULATIONS, OR ORDINANCES, THE CONTRACTOR SHALL BE RESPONSIBLE TO HAVE ALL WORK CONFORM TO THE STRICTER OF SAID REQUIREMENTS.
- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS AS REQUIRED FOR ELECTRICAL, FIRE PROTECTION, PLUMBING, MECHANICAL, AND BACKFLOW PREVENTION INSTALLATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE BOTH A COMPLETE AND COMPLIANT INSTALLATION AS MAY BE DETERMINED BY THE AUTHORITY/AUTHORITIES HAVING JURISDICTION.
- CONTRACTOR SHALL NOT PROCURE OR FABRICATE ANY PIPING, DUCTWORK, OR OTHER EQUIPMENT WITHOUT FIRST VERIFYING ALL DIMENSIONS AND CONDITIONS WHETHER CURRENTLY EXISTING OR NOT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, INCLUDING ANY REQUIRED REWORK.
- MAINTAIN ALL MANUFACTURER RECOMMENDED EQUIPMENT SERVICE AND SAFETY CLEARANCES. DO NOT LOCATE ANY EQUIPMENT OR RUN MATERIALS ABOVE ANY ELECTRICAL PANELS OR SWITCHGEAR. MAINTAIN ALL NFPA/NEC CODE REQUIRED CLEARANCES.
- EACH CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING, SCHEDULING, AND SEQUENCING OF THEIR WORK WITH ALL OTHER TRADES. PROVIDE OFFSETS, EASEMENTS, OR RELOCATE AS REQUIRED AVOIDING CONFLICTS WITH WORK OF OTHER TRADES. FURNISH SUFFICIENT RESOURCES TO MEET ALL PROJECT MILESTONES AND DEADLINES.
- PROTECT WORK FROM DAMAGE OR CONTAMINATION. PROVIDE TEMPORARY PROTECTIVE CAPPING OR TAPED POLYETHYLENE ENCLOSURES OVER OPEN DUCTWORK AND PIPING ENDS AND EQUIPMENT. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING MECHANICAL SYSTEMS PRIOR TO PLACING THEM IN SERVICE.
- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE WATERTIGHT AND WEATHER-PROOF INTEGRITY OF ROOFS, WALLS, AND FLOORS DURING CONSTRUCTION. EACH TRADE SHALL LOCATE/DIMENSION/COORDINATE THEIR ROOF, FLOOR, AND WALL OPENINGS AS NEEDED WITH THE GENERAL CONTRACTOR OR CONSTRUCTION MANGER.

GENERAL PLUMBING NOTES

- UNLESS NOTED OTHERWISE: LIGHT LINES DENOTE EXISTING PIPING, OR EQUIPMENT WHICH IS TO REMAIN. BOLD LINES INDICATE NEW WORK TO BE INSTALLED UNDER THIS CONTRACT.
- PLUMBING SHOWN IN SCHEMATIC FORM. NOT ALL RISERS AND DROPS ARE SHOWN. PROVIDE OFFSETS AS REQUIRED TO MEET SPACE REQUIREMENTS AND TO AVOID INTERFERENCE WITH OTHER TRADES. THE CONTRACTOR SHALL PROVIDE COMPLETE FULLY FUNCTIONAL SYSTEMS.
- ALL EQUIPMENT AND ACCESSORIES SHALL BE INSTALLED TO BE EASILY ACCESSIBLE.
- PLUMBING WORK SHALL BE COORDINATED WITH OTHER TRADES, INCLUDING BUT NOT LIMITED TO DUCTWORK, ELECTRICAL EQUIPMENT, PIPING AND FIRE PROTECTION SPACE ABOVE CEILING IS LIMITED AND SHALL BE COORDINATED WITH OTHER TRADES.
- ALL WORK WITHIN THE CONTRACT DOCUMENTS, WHICH INCLUDE THIS DRAWING, SHALL BE COMPLETED IN A SAFE WORKMANLIKE MANNER AND IN ACCORDANCE WITH ALL APPLICABLE STATE, LOCAL AND NATIONAL CODES, REGULATIONS AND ORDINANCES. IF ANY CONFLICTS ARISE BETWEEN THE CONTRACT DOCUMENTS AND THE APPLICABLE CODES, REGULATIONS OR ORDINANCE, THE CONTRACTOR SHALL BE RESPONSIBLE TO HAVE ALL WORK CONFORM TO THE STRICTER OF SAID REQUIREMENTS.
- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS AS REQUIRED FOR ELECTRICAL, FIRE PROTECTION, PLUMBING, MECHANICAL AND BACKFLOW PREVENTION INSTALLATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE BOTH A COMPLETE AND COMPLIANT INSTALLATION AS MAY BE DETERMINED BY THE AUTHORITY(S) HAVING JURISDICTION.
- CONTRACTOR SHALL NOT PROCURE OR FABRICATE ANY PIPING, DUCTWORK OR OTHER EQUIPMENT WITHOUT FIRST VERIFYING ALL DIMENSIONS AND CONDITIONS WHETHER CURRENTLY EXISTING OR NOT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, INCLUDING ANY REQUIRED REWORK.
- MAINTAIN ALL MANUFACTURER RECOMMENDED EQUIPMENT SERVICE AND SAFETY CLEARANCES. DO NOT LOCATE ANY EQUIPMENT OR RUN MATERIALS ABOVE ANY ELECTRICAL PANELS OR SWITCHGEAR. MAINTAIN ALL NFPA/NEC CODE REQUIRED CLEARANCES.
- EACH CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING, SCHEDULING AND SEQUENCING OF THEIR WORK WITH ALL OTHER TRADES. PROVIDE OFFSETS, EASEMENTS, OR RELOCATE TO AVOID CONFLICTS WITH WORK OF OTHER TRADES. FURNISH SUFFICIENT RESOURCES TO MEET ALL PROJECT MILESTONES AND DEADLINES.
- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE WATERTIGHT AND WEATHER-PROOF INTEGRITY OF ROOFS, WALLS, AND FLOORS DURING CONSTRUCTION. EACH TRADE SHALL LOCATE/DIMENSION/COORDINATE THEIR ROOF, FLOOR AND WALL OPENINGS WITH THE GENERAL CONTRACTOR (GC) OR CONSTRUCTION MANGER.
- PROTECT NEW WORK FROM DAMAGE OR DECONTAMINATION. PROVIDE TEMPORARY PROTECTIVE CAPPING OR TAPED POLYETHYLENE ENCLOSURES OVER OPEN DUCTWORK AND PIPING ENDS AND EQUIPMENT. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING MECHANICAL SYSTEMS PRIOR TO PLACING THEM IN SERVICE.
- IN A NEAT AND WORKMANLIKE MANNER. PATCH ANY REMAINING OPENINGS AND FILL EXCESSIVE GAPS. REWORK AND REFINISH TO MATCH ADJACENT STRUCTURES. FLASH AND SEAL ALL MECHANICAL AND ELECTRICAL PENETRATIONS THRU WALLS, CEILING AND FLOORS WITH METAL FRAMEWORK OR ESCUTCHEONS. ALL OPENINGS SHALL BE PROPERLY SEALED SO AS TO MEET FIRE RATING NEEDS.

GENERAL MECHANICAL DEMOLITION NOTES

- THESE DRAWINGS REPRESENT THE LAYOUT OF EXISTING CONDITIONS OF MAJOR COMPONENTS. THEY ARE NOT INTENDED TO SHOW ACCESSORIES OR INCIDENTALS COMMON TO THE COMPONENTS INDICATED. THOUGH THESE ITEMS ARE TO BE REMOVED, ACCESSIBILITY TO DEMOLITION ITEMS SHALL NOT BE INFERRED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF BUILDING AND EXISTING CONDITIONS PRIOR TO BID SUBMISSION.
- DEMOLITION WORK SHOWN IS BASED ON LIMITED SITE OBSERVATIONS AND CONSTRUCTION RECORD DOCUMENTS. CONTRACTOR SHALL NOT DEMOLISH ANY MECHANICAL PIPING, DUCTWORK, EQUIPMENT, OR OTHER ITEMS WITHOUT FIRST VERIFYING EXISTING CONDITIONS. CONSULT OWNER'S REPRESENTATIVE OR CONSTRUCTION MANAGER BEFORE START OF WORK.
- DEMOLITION OF MECHANICAL PIPING, DUCTWORK, AND EQUIPMENT SHALL INCLUDE ALL HANGERS, FITTINGS, DAMPERS, VALVES, ETC.
- REPAIR ANY INSULATION DAMAGED DURING REMOVAL. REPAIR WORK TO MATCH EXISTING.
- COORDINATE WALL AND FLOOR PATCHING REQUIREMENTS. PATCHWORK SHALL MATCH MATERIALS, FINISH, AND TEXTURE OF ADJACENT SURFACES.
- CONTRACTOR SHALL PATCH/REPAIR ALL UNUSED OPENINGS AND MODIFIED FINISH SURFACES. PATCHING SHALL MATCH MATERIALS, FINISH, AND TEXTURE OF ADJACENT SURFACES.
- CONTRACTOR SHALL BE RESPONSIBLE FOR PROPER AND TIMELY DISPOSAL OF ALL CONSTRUCTION DEBRIS INCLUDING BUT NOT LIMITED TO EQUIPMENT AND MATERIALS NOT CLAIMED BY OWNER.
- IT IS ESSENTIAL TO MINIMIZE DISRUPTIONS. COORDINATE ALL DEMOLITION WITH THE OWNER OR CONSTRUCTION MANAGER BEFORE SHUTTING DOWN ANY UTILITY OR SIMILAR SYSTEM. SHUTDOWN OF UTILITIES OR SIMILAR SYSTEMS SHALL BE REQUESTED WELL IN ADVANCE AND PRE-APPROVED BY THE PROPER AUTHORITY AND/OR AUTHORITIES HAVING JURISDICTION BEFORE WORK BEGINS.
- ALL WORK WITHIN THE CONTRACT DOCUMENTS SHALL BE COMPLETED IN A SAFE MANNER AND IN ACCORDANCE WITH ALL APPLICABLE STATE AND NATIONAL CODES, REGULATIONS, AND ORDINANCES. IF ANY CONFLICTS ARISE BETWEEN THE CONTRACT DOCUMENTS AND THE APPLICABLE CODES, REGULATIONS, OR ORDINANCES, THE CONTRACTOR SHALL BE RESPONSIBLE TO HAVE ALL WORK CONFORM TO THE STRICTER OF SAID REQUIREMENTS.
- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE WATERTIGHT AND WEATHER-PROOF INTEGRITY OF ROOFS, WALLS, AND FLOORS DURING CONSTRUCTION. EACH TRADE SHALL LOCATE/DIMENSION/COORDINATE THEIR ROOF, FLOOR, AND WALL OPENINGS AS NEEDED WITH THE CONSTRUCTION MANGER.
- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS AS REQUIRED FOR ELECTRICAL, FIRE PROTECTION, PLUMBING, MECHANICAL, AND BACKFLOW PREVENTION INSTALLATIONS. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE BOTH A COMPLETE AND COMPLIANT INSTALLATION AS MAY BE DETERMINED BY THE AUTHORITY AND/OR AUTHORITIES HAVING JURISDICTION.
- PROVIDE TEMPORARY SPACE TEMPERING (HEATING/COOLING/DEHUMIDIFICATION) AS NEEDED TO PROTECT SPACES AND INSTALLATIONS FROM EXPOSURE TO DAMAGING CONDITIONS.

GENERAL MECHANICAL PIPING NOTES

- PIPING IS SHOWN IN SCHEMATIC FORM. ROUTE AS REQUIRED FOR CLEARANCE WITH EXISTING CONDITIONS AND OTHER TRADES.
- UNIONS AND VALVES TO BREAK CONNECTIONS ARE REQUIRED AT ALL MAJOR EQUIPMENT AND ALL PIPING ITEMS THAT REQUIRE REMOVAL FOR MAINTENANCE.
- PIPE REDUCTIONS ON HORIZONTAL PIPING GOING FROM LARGER TO SMALLER SHALL BE MADE WITH CONCENTRIC REDUCERS. TOP FLAT FOR LIQUID SYSTEMS. CONCENTRIC REDUCERS MAY BE USED FOR FLOW GOING FROM SMALL TO LARGER SIZE PIPE.
- FIRE SAFE ALL PIPE PENETRATIONS PER UL AT RATED WALLS AND FLOORS. REFER TO DETAILS FOR ADDITIONAL INFORMATION.
- FLOOR/WALL/CEILING PENETRATIONS REQUIRED FOR MECHANICAL PIPING INSTALLATION SHALL BE CLEANLY BORED AT RIGHT ANGLES. AS NEW PIPING IS INSTALLED, NEW PIPING PENETRATIONS SHALL BE NEATLY CAULKED TO FILL VOID. EXPOSED WALL PENETRATIONS SHALL BE FINISHED WITH ESCUTCHEONS.
- ALL NEW EQUIPMENT AND ACCESSORIES (CIRCUIT SETTERS, CIRCULATION PUMPS, EXPANSION TANKS, ETC.) SHALL BE INSTALLED TO BE EASILY ACCESSIBLE. ALL ALLEANCES FOR EQUIPMENT PER MANUFACTURERS' INSTRUCTIONS SHALL BE REQUIRED.
- CONNECTIONS BETWEEN DISSIMILAR PIPING MATERIALS SHALL BE MADE USING DIELECTRIC FITTINGS.
- THERMOSTATS SHALL BE MOUNTED AT 4'-0" ABOVE FINISHED FLOOR.
- REFER TO SPECIFICATIONS FOR ADDITIONAL INFORMATION.

GENERAL PLUMBING DEMOLITION NOTES

- THIS DRAWING DIAGRAMMATICALLY REPRESENTS THE LAYOUT OF EXISTING CONDITIONS WITH MAJOR PLUMBING COMPONENTS. THEY ARE NOT INTENDED TO SHOW ACCESSORIES OR INCIDENTALS COMMON TO EQUIPMENT INDICATED. THOUGH THESE ITEMS ARE TO BE REMOVED, ACCESSIBILITY TO DEMOLITION ITEMS SHALL NOT BE INFERRED. THE CONTRACTOR SHALL BE RESPONSIBLE FOR FIELD VERIFICATION OF BUILDING AND EXISTING CONDITIONS, PRIOR TO BID SUBMISSION.
- EXISTING PIPING PENETRATIONS VACATED/REVEALED DURING DEMOLITION AND REMODEL SHALL BE INFILLED AND FINISHED TO MATCH EXISTING. IF MATERIALS FOR REPAIR TO MATCH EXISTING ARE NOT AVAILABLE (IE GLAZED WALL TILE), GROUT ABANDONED PENETRATION FULL AND FINISH FLUSH. PRIOR APPROVAL OF THE OWNER MUST BE OBTAINED BEFORE ANY PROPOSED NON-SIMILAR FINISH WORK BEGINS.
- DISCONNECT AND REMOVE ALL PREVIOUSLY ABANDONED PIPING WITHIN THE PROJECT AREA. REMOVE EXISTING/ABANDONED HANGERS AND SUPPORTS IF DEEMED NOT REUSABLE.
- ALL PIPING SHOWN IS BASED ON ORIGINAL DRAWINGS AND LIMITED SITE OBSERVATIONS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR VERIFYING ALL EXISTING CONDITIONS PRIOR TO COMMENCING WORK.
- ALL PIPING ASSOCIATED WITH EXISTING SYSTEMS SHALL BE DEMOLISHED. NO PIPING SHALL BE ABANDONED.
- CONTRACTOR SHALL BE RESPONSIBLE FOR DRAINING PIPING SYSTEMS TO BE CUT, CAPPED OR REMOVED. DISCHARGE FROM SUCH SYSTEMS SHALL BE APPROPRIATELY DISPOSED OF PER FEDERAL, STATE AND LOCAL REQUIREMENTS.
- COORDINATE WITH GENERAL CONTRACTOR FOR FLOOR, WALL AND ROOF PATCHING REQUIRED DUE TO PENETRATIONS RESULTING FROM DEMOLITION OF EXISTING AND INSTALLATION OF NEW EQUIPMENT AND COMPONENTS.
- CONTRACTOR IS RESPONSIBLE TO VERIFY ACTUAL NUMBER AND LOCATION OF SYSTEMS AND COMPONENTS TO BE DEMOLISHED AND REMOVED.
- TO MINIMIZE DISRUPTIONS, COORDINATE ALL DEMOLITION WITH OWNER, GENERAL CONTRACTOR, OR CONSTRUCTION MANAGER BEFORE SHUTTING DOWN ANY UTILITY OR SIMILAR SYSTEM. SHUTDOWNS FOR UTILITIES OR SIMILAR SYSTEMS SHALL BE REQUESTED WELL IN ADVANCE PER THE SPECIFICATION.
- ALL WORK WITHIN THE CONTRACT DOCUMENTS, WHICH INCLUDE THIS DRAWING, SHALL BE COMPLETED IN A SAFE WORKMANLIKE MANNER AND IN ACCORDANCE WITH ALL APPLICABLE STATE, LOCAL AND NATIONAL CODES, REGULATIONS AND ORDINANCES. IF ANY CONFLICTS ARISE BETWEEN THE CONTRACT DOCUMENTS AND THE APPLICABLE CODES, REGULATIONS OR ORDINANCE, THE CONTRACTOR SHALL BE RESPONSIBLE TO HAVE ALL WORK CONFORM TO THE STRICTER OF SAID REQUIREMENTS.
- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS AS REQUIRED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE BOTH A COMPLETE AND COMPLIANT INSTALLATION AS MAY BE DETERMINED BY THE AUTHORITY(S) HAVING JURISDICTION.
- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE WATERTIGHT AND WEATHER-PROOF INTEGRITY OF ROOFS, WALLS AND FLOORS DURING CONSTRUCTION. EACH TRADE SHALL LOCATE/DIMENSION/COORDINATE THEIR ROOF, FLOOR AND WALL OPENINGS WITH THE GENERAL CONTRACTOR (GC) OR CONSTRUCTION MANGER.


GENERAL MECHANICAL ABBREVIATIONS

SYMBOLS	F	R
& @ # NUMBER OR POUND	FS FT FTHD	RH RHC RPM
A	G	S
A/E AD ADJ AFF AHU ALT AP APPROX AS AVG	GA GAL GC GPH GPM GPM H HP HPR HPS HTG HVAC HX HZ	SCH SCHM SHT SHT SQ IN SV SYS SRV
B	H	I
BAS BFF BFBP BHP BTU BTUH	H&CW HORIZ HVAC HZ	T TCC TEMP THRU TYP
C	I	U
CAP CFM CFH CH CHP CHSP CIRC CLG CONT CONTR CONV COORD CTRL CU CUH	GA GAL GC GPH GPM H HP HPR HPS HTG HVAC HX HZ	UNO UTL
D	K	V
'/DEG 'F 'C DB DDC DEMO DIA DIAG DWG	GA GAL GC GPH GPM H HP HPR HPS HTG HVAC HX HZ	VEL VERT VFD
E	L	W
EAT ELEC EQ EQUIP EQUIV ET EWB EWT EX	LAT LB(S) LDB LWB LWT	W/ WB WPD WT WTR
	M	
	N	
	O	
	P	
	Q	
	R	
	S	
	T	
	U	
	V	
	W	
	X	
	Y	
	Z	


GENERAL PLUMBING ABBREVIATIONS

SYMBOLS	F	R
& @ # NUMBER OR POUND	FCO FD FPT FS	RD RECIRC REQD RHC RPM
A	G	S
ADJ AFF ALT AMB AP APPROX AS ASSY AUX AVG	GA GAL GC GPH GPM GPH GPM H HP HPR HPS HTG HVAC HZ	SCH SCHM SHT SHT SQ IN SV SYS SRV
B	H	I
BAS BFF BFBP BHP BTU BTUH	H&CW HORIZ HVAC HZ	T TCC TEMP THRU TYP
C	I	U
CAP CFM CFH CH CHP CHSP CIRC CL CLG CLR CLW CO COND CONSTR CONT CONTR COORD CTRL CU CU FT CU IN	GA GAL GC GPH GPM H HP HPR HPS HTG HVAC HZ	UNO UTL
D	K	V
'/DEG 'F 'C DB DDC DEMO DIA DIAG DWG	GA GAL GC GPH GPM H HP HPR HPS HTG HVAC HX HZ	VEL VERT VFD
E	L	W
EAT ELEC EQ EQUIP EQUIV ET EWB EWT EX	LAT LB(S) LDB LWB LWT	W/ WB WPD WT WTR
	M	
	N	
	O	
	P	
	Q	
	R	
	S	
	T	
	U	
	V	
	W	
	X	
	Y	
	Z	

MECHANICAL SYMBOLS LIST



PLUMBING SYMBOLS LIST





STATE HISTORICAL PRESERVATION OFFICE REQUIREMENTS:

- FOR FINISHED SPACES (OFFICES, RECEPTION, ETC.), PAINT EXPOSED PIPING WHITE.
- FOR UNFINISHED SPACES (BASEMENTS, ATTICS, WORKSHOPS, ETC.) PIPING CAN REMAIN UNPAINTED.
- FOR SPACES WITH WOOD CEILINGS (NATURAL COLOR) IN MYERS HALL PAINT EXPOSED PIPING NEXT TO WOOD CEILINGS BROWN. FOR EXPOSED PIPING IN THE REST OF THE ROOM, PAINT AS DESCRIBED IN FINISHED SPACES.

KEYNOTES	
KEY	NOTE
04-E003	DIRECTIONAL BORE NEW FEEDER FOR FIRE PUMP. REFER TO 04-FP101 FOR CONTINUATION.
04-E004	EXISTING TRANSFORMER. CONNECT FIRE PUMP TO SECONDARY SIDE OF THE TRANSFORMER. CIRCUIT FIRE PUMP WITH (S) # 10 AND 186 GND IN 1-1/2" CONDUIT
04-FP01	AREA SHALL BE CONSIDERED LIGHT HAZARD, WITH SPRINKLER PROTECTION DENSITY OF 0.10 GPM/SQ FT OVER THE HYDRAULICALLY MOST REMOTE 1500 SF. PROVIDE ALLOWANCE FOR 100 GPM COMBINED INSIDE AND OUTSIDE HOSE STREAM.
04-FP02	AREA SHALL BE CONSIDERED ORDINARY HAZARD GROUP 1 WITH A DENSITY OF 0.15 GPM OVER THE MOST HYDRAULICALLY REMOTE 1500 SF WITH A 250 GPM COMBINED INSIDE AND OUTSIDE HOSE STREAM ALLOWANCE.
04-FP07	ELEVATORS AND ELEVATOR MACHINE ROOMS. PROVIDE HORIZONTAL SIDEWALL HEADS IN ELEVATOR PIT AT ELEVATOR DOOR SIDE. ELEVATOR MACHINE ROOM AND AT TOP OF ELEVATOR SHAFT PER NFPA 13. MEET ANS AND LOCAL ELEVATOR INSPECTORS REQUIREMENTS FOR SPRINKLERS IN ELEVATOR SHAFTS AND ELEVATOR MACHINE ROOMS.
04-FP19	NEW 4" X 2 1/2" X 2 1/2" FIRE PUMP TEST CONNECTION WITH HYDRANT OUTLET SNOOTS, GATE VALVES, CAPS AND CHAINS, AND IDENTIFICATION PLATE LETTERED "FIRE PUMP TEST".


FIRE PROTECTION

- PROVIDE ALL MATERIALS AND EQUIPMENT AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERATE FIRE PROTECTION SYSTEMS AS INDICATED ON DRAWINGS, AS SPECIFIED, AND IN COMPLIANCE WITH THE STANDARDS OF THE NATIONAL FIRE PROTECTION ASSOCIATION, AND ALL STATE REGULATIONS.
- THE ENTIRE BUILDING SPRINKLER SYSTEM SHALL BE HYDRAULICALLY DESIGNED UNLESS OTHERWISE NOTED ON THE DRAWINGS.
- FIRE PROTECTION WORK SHALL BE COORDINATED WITH OTHER TRADES INCLUDING BUT NOT LIMITED TO DUCTWORK, PLUMBING, ELECTRICAL EQUIPMENT, AND PIPING. SPACE ABOVE THE CEILING IS LIMITED AND SHALL BE COORDINATED WITH OTHER TRADES.
- ALL FIRE PROTECTION PIPING MAY NOT BE INSTALLED AT A SINGLE ELEVATION. OFFSETS MAY BE REQUIRED TO ALLOW FOR INSTALLATION OF OTHER WORK. NOT ALL MAIN OR BRANCH LINES SHOWN. INSTALL PIPING TO BE SELF DRAINING BY GRAVITY WHERE POSSIBLE OR PROVIDE DRAIN LEGS AS NEEDED.
- VERIFY CEILING HEIGHTS AND TYPES WITH ARCHITECTURAL PLANS AND ELEVATIONS.
- TEST DRAIN LOCATIONS SHALL BE DRAINED INTO FLOOR DRAINS, MOP SINKS, OR THROUGH EXTERIOR WALLS TO SPILL ON CONCRETE PAD SPLASH BLOCKS, MOUNTED ON GRADE. VERIFY ALL LOCATIONS WITH ARCHITECT.
- ALL EQUIPMENT AND ACCESSORIES SHALL BE INSTALLED TO BE EASILY ACCESSIBLE.
- ALL WORK WITHIN THE CONTRACT DOCUMENTS, WHICH INCLUDE THIS DRAWING, SHALL BE COMPLETED IN A SAFE WORKMANLIKE MANNER AND IN ACCORDANCE WITH ALL APPLICABLE STATE, AND NATIONAL, CODES, REGULATIONS AND ORDINANCES. IF ANY CONFLICTS ARISE BETWEEN THE CONTRACT DOCUMENTS AND THE APPLICABLE CODES, REGULATIONS OR ORDINANCE, THE CONTRACTOR SHALL BE RESPONSIBLE TO HAVE ALL WORK CONFORM TO THE STRICTER OF SAID REQUIREMENTS.
- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS AS REQUIRED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE BOTH A COMPLETE AND COMPLIANT INSTALLATION AS MAY BE DETERMINED BY THE AUTHORITY(S) HAVING JURISDICTION.
- CONTRACTOR SHALL NOT PROCURE OR FABRICATE ANY PIPING, DUCTWORK OR OTHER EQUIPMENT WITHOUT FIRST VERIFYING ALL DIMENSIONS AND CONDITIONS WHETHER CURRENTLY EXISTING OR NOT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, INCLUDING ANY REQUIRED REWORK.
- MAINTAIN ALL MANUFACTURER RECOMMENDED EQUIPMENT SERVICE AND SAFETY CLEARANCES. DO NOT LOCATE ANY EQUIPMENT OR RUN MATERIALS ABOVE ANY ELECTRICAL PANELS OR SWITCHGEAR. MAINTAIN ALL NFPA/NEC CODE REQUIRED CLEARANCES.
- EACH CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING, SCHEDULING AND SEQUENCING OF THEIR WORK WITH ALL OTHER TRADES. PROVIDE OFFSETS, EASEMENTS OR RELOCATE TO AVOID CONFLICTS WITH WORK OF OTHER TRADES. FURNISH SUFFICIENT RESOURCES TO MEET ALL PROJECT MILESTONES AND DEADLINES.
- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE WATERTIGHT AND WEATHER-PROOF INTEGRITY OF ROOFS, WALLS AND FLOORS DURING CONSTRUCTION. EACH TRADE SHALL LOCATE DIMENSION COORDINATE THEIR ROOF, FLOOR AND WALL OPENINGS WITH THE GENERAL CONTRACTOR (GC) OR CONSTRUCTION MANAGER.
- PROTECT EXISTING BUILDING FROM DAMAGE OR CONTAMINATION. PROVIDE TEMPORARY PROTECTIVE CAPPING OR TAPED POLYETHYLENE ENCLOSURES OVER PIPING ENDS AND EQUIPMENT. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING MECHANICAL SYSTEMS PRIOR TO PLACING THEM IN SERVICE.
- IN A NEAT AND WORKMANLIKE MANNER: FLASH AND SEAL ALL MECHANICAL AND ELECTRICAL PENETRATIONS THRU WALLS, CEILINGS AND FLOORS WITH METAL FRAMEWORK OR ESCUTCHEONS. ALL OPENINGS SHALL BE PROPERLY SEALED SO AS TO MEET FIRE RATING NEEDS.
- CENTER SPRINKLERS IN CEILING TILES IN BOTH DIRECTIONS IN ALL AREAS. IN AREAS WITH 2'X4' CEILING TILES, CENTER USING A 2'X2' CEILING PATTERN IS ACCEPTABLE.
- FOR EXPOSED SPRINKLER PIPING IN FINISHED AREAS:
 - INSTALL AS TIGHT TO CEILING AS POSSIBLE.
 - KEEP PIPING AND HEADS A MINIMUM OF 4FT AWAY FROM WINDOWS, WHERE SPACE DOES NOT ALLOW, SUCH AS CORRIDORS. EXPOSED PIPING WITHIN 4 FT IS ACCEPTABLE.
 - TO PRESERVE HISTORIC BUILDING STATUS, MINIMIZE DISTURBANCE OF ANY DECORATIVE MATERIALS OR DETAILS SUCH AS DECORATIVE PLASTER.
- NOT USED.
- NOT USED.
- CONTRACTOR TO CAREFULLY REMOVE AND RE-INSTALL LAY-IN CEILING AS REQUIRED TO INSTALL NEW PIPING AND SPRINKLERS. REPLACE ANY TILE DAMAGED. SEE ARCHITECTURAL PLANS FOR CEILING TYPES.
- WHERE GYPSUM BOARD IS DEMOLISHED AT CEILINGS AND NON-FIRE-RATED WALLS, CUT OPENINGS CLEAN, STRAIGHT, AND AS SMALL AS PRACTICAL TO PERFORM THE WORK REQUIRED. LEAVE READY FOR DRYWALL PATCHING. PATCHING OF CEILINGS AND NON-FIRE-RATED WALLS WILL BE BY OTHERS. PROVIDE TESTED FIRESTOPPING ASSEMBLIES AT PENETRATIONS OF FIRE-RATED WALLS.
- FOR FINISHED SPACES (OFFICES, RECEPTION, ETC.), PAINT PIPING, CONDUIT, AND PROVIDE SPRINKLER HEADS WITH WHITE FACTORY FINISH.
- FOR UNFINISHED SPACES (BASEMENTS, ATTICS, WORKSHOPS, ETC.) PIPING, CONDUIT, SPRINKLER HEADS CAN REMAIN UNPAINTED.
- FOR SPACES WITH WOOD CEILINGS (NATURAL COLOR) IN MYERS HALL PAINT PIPING BROWN AND USE STAINLESS SPRINKLER HEADS.
- IN MYERS HALL, TO THE BEST EXTENT POSSIBLE, ROUTE PIPING ON THE SIDE OF BEAMS, RATHER THAN THE BOTTOM OF THE BEAMS.



B6 FIRST FLOOR FIRE PROTECTION PLAN
1/8" = 1'-0" 0' 12"

[Symbol]	LIGHT HAZARD
[Symbol]	ORDINARY HAZARD
[Symbol]	ELEVATOR AND ELEVATOR MACHINE ROOM



KEY PLAN

Fire Sprinkler #9279.21
Iowa Department of Administrative Services
1251 354th St, Woodward, IA 50276


DATE	BY	DESCRIPTION
02/07/2023	JET	ADD 1
	TLS	
	100% CD	
2023-01-10		
2142203390		
		FIELD BOOK

FIRST FLOOR FIRE PROTECTION PLAN


04-FP101

KEYNOTES	
KEY	NOTE
04-E025	FURNISH AND INSTALL HEAT DETECTOR AND SMOKE DETECTOR WITHIN 24" OF SPRINKLER HEADS IN TOP OF ELEVATOR SHAFT.
04-FP01	AREA SHALL BE CONSIDERED LIGHT HAZARD, WITH SPRINKLER PROTECTION DENSITY OF 0.10 GPM/SQFT OVER THE HYDRAULICALLY MOST REMOTE 1500 SF. PROVIDE ALLOWANCE FOR 100 GPM COMBINED INSIDE AND OUTSIDE HOSE STREAM.
04-FP02	AREA SHALL BE CONSIDERED ORDINARY HAZARD GROUP 1 WITH A DENSITY OF 0.15 GPM OVER THE MOST HYDRAULICALLY REMOTE 1500 SF WITH A 250 GPM COMBINED INSIDE AND OUTSIDE HOSE STREAM ALLOWANCE.
04-FP07	ELEVATORS AND ELEVATOR MACHINE ROOMS: PROVIDE HORIZONTAL SIDEWALL HEADS IN ELEVATOR PIT AT ELEVATOR DOOR SIDE, ELEVATOR MACHINE ROOM AND AT TOP OF ELEVATOR SHAFT PER NFPA 13. MEET ANSI AND LOCAL ELEVATOR INSPECTOR'S REQUIREMENTS FOR SPRINKLERS IN ELEVATOR SHAFTS AND ELEVATOR MACHINE ROOMS.

- ### FIRE PROTECTION
- PROVIDE ALL MATERIALS AND EQUIPMENT AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERATE FIRE PROTECTION SYSTEMS AS INDICATED ON DRAWINGS, AS SPECIFIED, AND IN COMPLIANCE WITH THE STANDARDS OF THE NATIONAL FIRE PROTECTION ASSOCIATION, AND ALL STATE REGULATIONS.
 - THE ENTIRE BUILDING SPRINKLER SYSTEM SHALL BE HYDRAULICALLY DESIGNED UNLESS OTHERWISE NOTED ON THE DRAWINGS.
 - FIRE PROTECTION WORK SHALL BE COORDINATED WITH OTHER TRADES INCLUDING BUT NOT LIMITED TO DUCTWORK, PLUMBING, ELECTRICAL EQUIPMENT, AND PIPING SPACE ABOVE THE CEILING IS LIMITED AND SHALL BE COORDINATED WITH OTHER TRADES.
 - ALL FIRE PROTECTION PIPING MAY NOT BE INSTALLED AT A SINGLE ELEVATION; OFFSETS MAY BE REQUIRED TO ALLOW FOR INSTALLATION OF OTHER WORK; NOT ALL MAIN OR BRANCH LINES SHOWN. INSTALL PIPING TO BE SELF-DRAINING BY GRAVITY WHERE POSSIBLE OR PROVIDE DRAIN LEGS AS NEEDED.
 - VERIFY CEILING HEIGHTS AND TYPES WITH ARCHITECTURAL PLANS AND ELEVATIONS.
 - TEST DRAIN LOCATIONS SHALL BE DRAINED INTO FLOOR DRAINS, MOP SINKS, OR THROUGH EXTERIOR WALLS TO SPILL ON CONCRETE PAD SPLASH BLOCKS, MOUNTED ON GRADE. VERIFY ALL LOCATIONS WITH ARCHITECT.
 - ALL EQUIPMENT AND ACCESSORIES SHALL BE INSTALLED TO BE EASILY ACCESSIBLE.
 - ALL WORK WITHIN THE CONTRACT DOCUMENTS, WHICH INCLUDE THIS DRAWING, SHALL BE COMPLETED IN A SAFE WORKMANLIKE MANNER AND IN ACCORDANCE WITH ALL APPLICABLE STATE AND NATIONAL CODES, REGULATIONS AND ORDINANCES. IF ANY CONFLICTS ARISE BETWEEN THE CONTRACT DOCUMENTS AND THE APPLICABLE CODES, REGULATIONS OR ORDINANCE, THE CONTRACTOR SHALL BE RESPONSIBLE TO HAVE ALL WORK CONFORM TO THE STRICTER OF SAID REQUIREMENTS.
 - THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS AS REQUIRED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE BOTH A COMPLETE AND COMPLIANT INSTALLATION AS MAY BE DETERMINED BY THE AUTHORITY(S) HAVING JURISDICTION.
 - CONTRACTOR SHALL NOT PROCURE OR FABRICATE ANY PIPING, DUCTWORK OR OTHER EQUIPMENT WITHOUT FIRST VERIFYING ALL DIMENSIONS AND CONDITIONS WHETHER CURRENTLY EXISTING OR NOT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, INCLUDING ANY REQUIRED REWORK.
 - MAINTAIN ALL MANUFACTURER RECOMMENDED EQUIPMENT SERVICE AND SAFETY CLEARANCES. DO NOT LOCATE ANY EQUIPMENT OR RUN MATERIALS ABOVE ANY ELECTRICAL PANELS OR SWITCHGEAR. MAINTAIN ALL NFPA/NEC CODE REQUIRED CLEARANCES.
 - EACH CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING, SCHEDULING AND SEQUENCING OF THEIR WORK WITH ALL OTHER TRADES. PROVIDE OFFSETS, EASEMENTS OR RELOCATE TO AVOID CONFLICTS WITH WORK OF OTHER TRADES. FURNISH SUFFICIENT RESOURCES TO MEET ALL PROJECT MILESTONES AND DEADLINES.
 - CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE WATERTIGHT AND WEATHER-PROOF INTEGRITY OF ROOFS, WALLS AND FLOORS DURING CONSTRUCTION. EACH TRADE SHALL LOCATE/DIMENSION/COORDINATE THEIR ROOF, FLOOR AND WALL OPENINGS WITH THE GENERAL CONTRACTOR (GC) OR CONSTRUCTION MANAGER.
 - PROTECT EXISTING BUILDING FROM DAMAGE OR CONTAMINATION. PROVIDE TEMPORARY PROTECTIVE CAPPING OR TAPED POLYETHYLENE ENCLOSURES OVER PIPING ENDS AND EQUIPMENT. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING MECHANICAL SYSTEMS PRIOR TO PLACING THEM IN SERVICE.
 - IN A NEAT AND WORKMANLIKE MANNER: FLASH AND SEAL ALL MECHANICAL AND ELECTRICAL PENETRATIONS THRU WALLS, CEILING AND FLOORS WITH METAL FRAMEWORK OR ESCUTCHEONS. ALL OPENINGS SHALL BE PROPERLY SEALED SO AS TO MEET FIRE RATING NEEDS.
 - CENTER SPRINKLERS IN CEILING TILES IN BOTH DIRECTIONS IN ALL AREAS. IN AREAS WITH 2'x4' CEILING TILES, CENTER USING A 2'x2' CEILING PATTERN IS ACCEPTABLE.
 - FOR EXPOSED SPRINKLER PIPING IN FINISHED AREAS:
 - INSTALL AS TIGHT TO CEILING AS POSSIBLE
 - KEEP PIPING AND HEADS A MINIMUM OF 4FT AWAY FROM WINDOWS, WHERE SPACE DOES NOT ALLOW, SUCH AS CORRIDORS, EXPOSED PIPING WITHIN 4 FT IS ACCEPTABLE
 - TO PRESERVE HISTORIC BUILDING STATUS, MINIMIZE DISTURBANCE OF ANY DECORATIVE MATERIALS OR DETAILS SUCH AS DECORATIVE PLASTER
 - NOT USED.
 - NOT USED.
 - CONTRACTOR TO CAREFULLY REMOVE AND RE-INSTALL LAY-IN CEILING AS REQUIRED TO INSTALL NEW PIPING AND SPRINKLERS. REPLACE ANY TILE DAMAGED. SEE ARCHITECTURAL PLANS FOR CEILING TYPES.
 - WHERE GYPSUM BOARD IS DEMOLISHED AT CEILINGS AND NON-FIRE-RATED WALLS, CUT OPENINGS CLEAN, STRAIGHT, AND AS SMALL AS PRACTICAL TO PERFORM THE WORK REQUIRED. LEAVE READY FOR DRYWALL PATCHING. PATCHING OF CEILINGS AND NON-FIRE-RATED WALLS WILL BE BY OTHERS. PROVIDE TESTED FIRESTOPPING ASSEMBLIES AT PENETRATIONS OF FIRE-RATED WALLS.
 - FOR FINISHED SPACES (OFFICES, RECEPTION, ETC.), PAINT PIPING, CONDUIT, AND PROVIDE SPRINKLER HEADS WITH WHITE FACTORY FINISH.
 - FOR UNFINISHED SPACES (BASEMENTS, ATTICS, WORKSHOPS, ETC.) PIPING, CONDUIT, SPRINKLER HEADS CAN REMAIN UNPAINTED.
 - FOR SPACES WITH WOOD CEILINGS (NATURAL COLOR) IN MYERS HALL PAINT PIPING BROWN AND USE STAINLESS SPRINKLER HEADS.
 - IN MYERS HALL, TO THE BEST EXTENT POSSIBLE, ROUTE PIPING ON THE SIDE OF BEAMS, RATHER THAN THE BOTTOM OF THE BEAMS.




ONLY FIRE ALARM DEVICES REQUIRED FOR FIRE PUMP PORTION OF PROJECT ARE SHOWN ON THIS SHEET. REFER TO BID PACKAGES FOR BREAKOUTS REQUIRED FOR SPRINKLER AND FIRE ALARM PROJECTS. ALL OTHER FIRE ALARM DEVICES ARE NO LONGER SHOWN ON THIS SHEET. REFER TO FIRE ALARM SHEETS FOR OTHER FIRE ALARM DEVICES.



B6 SECOND FLOOR FIRE PROTECTION PLAN
1/8" = 1'-0" 0 12

[Diagonal Lines]	LIGHT HAZARD
[Cross-hatch]	ORDINARY HAZARD
[Solid Black]	ELEVATOR AND ELEVATOR MACHINE ROOM




DRAWN BY	JET	ADD	1	02/07/2023	ADDENDUM #1
APPROVED BY	TLS				
ISSUED FOR	100%	CD			
ISSUE DATE	2023-01-10				
PROJECT NUMBER	2142203390				
FIELD BOOK					


KEYNOTES	
KEY	NOTE
04-FP08	AREA TO BE CONSIDERED LIGHT HAZARD WITH A DENSITY OF 0.10 GPM/SF OVER THE MOST HYDRAULICALLY REMOTE 1500 SF WITH A 100 GPM TOTAL COMBINED INSIDE AND OUTSIDE HOSE STREAM ALLOWANCE. AREA TO BE SERVED BY A DRY TYPE SYSTEM.

FIRE PROTECTION


- PROVIDE ALL MATERIALS AND EQUIPMENT AND PERFORM ALL LABOR REQUIRED TO INSTALL COMPLETE AND OPERATE FIRE PROTECTION SYSTEMS AS INDICATED ON DRAWINGS, AS SPECIFIED, AND IN COMPLIANCE WITH THE STANDARDS OF THE NATIONAL FIRE PROTECTION ASSOCIATION, AND ALL STATE REGULATIONS.
- THE ENTIRE BUILDING SPRINKLER SYSTEM SHALL BE HYDRAULICALLY DESIGNED UNLESS OTHERWISE NOTED ON THE DRAWINGS.
- FIRE PROTECTION WORK SHALL BE COORDINATED WITH OTHER TRADES INCLUDING BUT NOT LIMITED TO DUCTWORK, PLUMBING, ELECTRICAL EQUIPMENT, AND PIPING. SPACE ABOVE THE CEILING IS LIMITED AND SHALL BE COORDINATED WITH OTHER TRADES.
- ALL FIRE PROTECTION PIPING MAY NOT BE INSTALLED AT A SINGLE ELEVATION. OFFSETS MAY BE REQUIRED TO ALLOW FOR INSTALLATION OF OTHER WORK. NOT ALL MAIN OR BRANCH LINES SHOWN. INSTALL PIPING TO BE SELF-DRAINING BY GRAVITY WHERE POSSIBLE OR PROVIDE DRAIN LEGS AS NEEDED.
- VERIFY CEILING HEIGHTS AND TYPES WITH ARCHITECTURAL PLANS AND ELEVATIONS.
- TEST DRAIN LOCATIONS SHALL BE DRAINED INTO FLOOR DRAINS, MOP SINKS, OR THROUGH EXTERIOR WALLS TO SPILL ON CONCRETE PAD SPLASH BLOCKS, MOUNTED ON GRADE. VERIFY ALL LOCATIONS WITH ARCHITECT.
- ALL EQUIPMENT AND ACCESSORIES SHALL BE INSTALLED TO BE EASILY ACCESSIBLE.
- ALL WORK WITHIN THE CONTRACT DOCUMENTS, WHICH INCLUDE THIS DRAWING, SHALL BE COMPLETED IN A SAFE WORKMANLIKE MANNER AND IN ACCORDANCE WITH ALL APPLICABLE STATE AND NATIONAL CODES, REGULATIONS AND ORDINANCES. IF ANY CONFLICTS ARISE BETWEEN THE CONTRACT DOCUMENTS AND THE APPLICABLE CODES, REGULATIONS OR ORDINANCE, THE CONTRACTOR SHALL BE RESPONSIBLE TO HAVE ALL WORK CONFORM TO THE STRICTER OF SAID REQUIREMENTS.
- THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS AND INSPECTIONS AS REQUIRED. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE BOTH A COMPLETE AND COMPLIANT INSTALLATION AS MAY BE DETERMINED BY THE AUTHORITY(S) HAVING JURISDICTION.
- CONTRACTOR SHALL NOT PROCURE OR FABRICATE ANY PIPING, DUCTWORK OR OTHER EQUIPMENT WITHOUT FIRST VERIFYING ALL DIMENSIONS AND CONDITIONS WHETHER CURRENTLY EXISTING OR NOT. THE CONTRACTOR SHALL BE RESPONSIBLE FOR ALL WORK, INCLUDING ANY REQUIRED REWORK.
- MAINTAIN ALL MANUFACTURER RECOMMENDED EQUIPMENT SERVICE AND SAFETY CLEARANCES. DO NOT LOCATE ANY EQUIPMENT OR RUN MATERIALS ABOVE ANY ELECTRICAL PANELS OR SWITCHGEAR. MAINTAIN ALL NFPA/NEC CODE REQUIRED CLEARANCES.
- EACH CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING, SCHEDULING AND SEQUENCING OF THEIR WORK WITH ALL OTHER TRADES. PROVIDE OFFSETS, EASEMENTS OR RELOCATE TO AVOID CONFLICTS WITH WORK OF OTHER TRADES. FURNISH SUFFICIENT RESOURCES TO MEET ALL PROJECT MILESTONES AND DEADLINES.
- CONTRACTOR SHALL BE RESPONSIBLE FOR MAINTAINING THE WATERTIGHT AND WEATHER-PROOF INTEGRITY OF ROOFS, WALLS AND FLOORS DURING CONSTRUCTION. EACH TRADE SHALL LOCATE, DIMENSION AND COORDINATE THEIR ROOF, FLOOR AND WALL OPENINGS WITH THE GENERAL CONTRACTOR (GC) OR CONSTRUCTION MANAGER.
- PROTECT EXISTING BUILDING FROM DAMAGE OR CONTAMINATION. PROVIDE TEMPORARY PROTECTIVE CAPPING OR TAPED POLYETHYLENE ENCLOSURES OVER PIPING ENDS AND EQUIPMENT. CONTRACTOR SHALL BE RESPONSIBLE FOR CLEANING MECHANICAL SYSTEMS PRIOR TO PLACING THEM IN SERVICE.
- IN A NEAT AND WORKMANLIKE MANNER: FLASH AND SEAL ALL MECHANICAL AND ELECTRICAL PENETRATIONS THRU WALLS, CEILINGS AND FLOORS WITH METAL FRAMEWORK OR ESCUTCHEONS. ALL OPENINGS SHALL BE PROPERLY SEALED SO AS TO MEET FIRE RATING NEEDS.
- CENTER SPRINKLERS IN CEILING TILES IN BOTH DIRECTIONS IN ALL AREAS. IN AREAS WITH 2'x4' CEILING TILES, CENTER USING A 2'x2' CEILING PATTERN IS ACCEPTABLE.
- FOR EXPOSED SPRINKLER PIPING IN FINISHED AREAS:
 - INSTALL AS TIGHT TO CEILING AS POSSIBLE
 - KEEP PIPING AND HEADS A MINIMUM OF 4FT AWAY FROM WINDOWS. WHERE SPACE DOES NOT ALLOW, SUCH AS CORRIDORS, EXPOSED PIPING WITHIN 4 FT IS ACCEPTABLE
 - TO PRESERVE HISTORIC BUILDING STATUS, MINIMIZE DISTURBANCE OF ANY DECORATIVE MATERIALS OR DETAILS SUCH AS DECORATIVE PLASTER
- NOT USED.
- CONTRACTOR TO CAREFULLY REMOVE AND RE-INSTALL LAY-IN CEILING AS REQUIRED TO INSTALL NEW PIPING AND SPRINKLERS. REPLACE ANY TILE DAMAGED. SEE ARCHITECTURAL PLANS FOR CEILING TYPES.
- WHERE GYPSUM BOARD IS DEMOLISHED AT CEILINGS AND NON-FIRE-RATED WALLS, CUT OPENINGS CLEAN, STRAIGHT, AND AS SMALL AS PRACTICAL TO PERFORM THE WORK REQUIRED. LEAVE READY FOR DRYWALL PATCHING. PATCHING OF CEILINGS AND NON-FIRE-RATED WALLS WILL BE BY OTHERS. PROVIDE TESTED FIRESTOPPING ASSEMBLIES AT PENETRATIONS OF FIRE-RATED WALLS.
- FOR FINISHED SPACES (OFFICES, RECEPTION, ETC.), PAINT PIPING, CONDUIT, AND PROVIDE SPRINKLER HEADS WITH WHITE FACTORY FINISH.
- FOR UNFINISHED SPACES (BASEMENTS, ATTICS, WORKSHOPS, ETC.) PIPING, CONDUIT, SPRINKLER HEADS CAN REMAIN UNPAINTED.
- FOR SPACES WITH WOOD CEILINGS (NATURAL COLOR) IN MYERS HALL PAINT PIPING BROWN AND USE STAINLESS SPRINKLER HEADS.
- IN MYERS HALL, TO THE BEST EXTENT POSSIBLE, ROUTE PIPING ON THE SIDE OF BEAMS, RATHER THAN THE BOTTOM OF THE BEAMS.



[Diagonal Hatching]	LIGHT HAZARD
[Cross-hatching]	ORDINARY HAZARD
[Diagonal Hatching]	ELEVATOR AND ELEVATOR MACHINE ROOM




1 ATTIC FIRE PROTECTION PLAN
1/8" = 1'-0" 0 12'




KEY PLAN

ADD	1	02/07/2023	ADDENDUM #1
JET	TLS	100% CD	2023-01-10
ISSUED FOR	ISSUE DATE	PROJECT NUMBER	FIELD BOOK
		2142203390	

KEYNOTES	
KEY	NOTE
04-E002	FIRE ALARM RELAYS FOR INTERFACE WITH FIRE PUMP AND JOCKEY PUMP.
04-E005	NEW FEEDER FOR FIRE PUMP. REFER TO 04-FP300 FOR CONTINUATION.
04-E011	WIRING BETWEEN FIRE PUMP CONTROLLER AND FIRE PUMP TO BE IN RIGID METAL CONDUIT.
04-E023	WIRING BETWEEN JOCKEY PUMP CONTROLLER AND JOCKEY PUMP TO BE IN RIGID METAL CONDUIT.
04-FP13	4" BRANCH LINES FOR FUTURE EXTENSION OF FIRE PROTECTION. PROVIDE WITH INDICATING BUTTERFLY VALVE AND CAP.
04-FP14	JOCKEY PUMP CONTROLLER.
04-FP15	FIRE PUMP CONTROLLER.
04-FP16	INDICATING BUTTERFLY VALVE WITH TAMPERSWITCH.
04-FP17	INDICATING GATE VALVE WITH TAMPERSWITCH.
04-FP18	CHECK VALVE.
04-FP20	ISOLATION VALVE.
04-FP21	FIRE PROTECTION SYSTEM RISER. SEE DETAIL.





A4 FIRE PUMP PLAN
1/2" = 1'-0" 0' 3"





C4 FIRE PUMP ISOMETRIC

FIRE PUMP SCHEDULE											
MARK	DESCRIPTION	TYPE	GPM	HEAD (PSI)	SHUTOFF HEAD (PSI)	HEAD @ 150% FLOW (PSI)	MOTOR DATA			DESIGN BASIS	
							HP	RPM	VOLTS/PHASE		
FP-1	FIRE PUMP	VERTICAL IN-LINE	300	40	48	38	20	3500	208	3	AURORA 4-383-7B


JOCKEY PUMP SCHEDULE											
MARK	DESCRIPTION	TYPE	PUMP DATA			MOTOR DATA			DESIGN BASIS		
			STAGES	GPM	HEAD (PSI)	HP	RPM	VOLTS/PHASE			
JP-1	JOCKEY PUMP	VERTICAL MULTISTAGE	5	5	50	1/2	3500	208	3	AURORA PVM1-S	




A6 BASEMENT FIRE PROTECTION PIPING PLAN
1/8" = 1'-0" 0' 12"



E6 SPRINKLER RISER DIAGRAM
NOT TO SCALE



G6 FIRE PUMP SCHEMATIC
NOT TO SCALE



KEY PLAN

FIRE PUMP PLANS, DETAILS & SCHEDULES

04-FP300



Fire Sprinkler #9279.21
Iowa Department of Administrative Services
1251 354th St, Woodward, IA 50276

BSG	TLS	100% CD	2023-01-10	214200390	FIELD BOOK
ADD					
1					


02072023 ADDENDUM #1

DRAWN BY: _____
APPROVED BY: _____
ISSUED FOR: _____
ISSUE DATE: _____
PROJECT NUMBER: _____
FIELD BOOK: _____

KEYNOTES	
KEY	NOTE
04-MD1	REMOVE STEAM RADIATOR AND ASSOCIATED PIPING AND CONTROLS
04-MD3	REMOVE STEAM HEAT EXCHANGER. REMOVE ALL CONTROLS AND PIPING ACCESSORIES.
04-MD4	TEMPORARILY CAP PIPING TO COILS; RECONNECT TO NEW BOILER SYSTEM. SEE NEW WORK PLANS FOR ADDITIONAL DETAILS.
04-MD5	VALVE SEAL AND CAP STEAM PIPE MAINS AT THE NEAREST SHUTOFF VALVE IN THE TUNNEL OUTSIDE OF BUILDING FOOTPRINT.



C6 BASEMENT MECHANICAL PIPING DEMOLITION PLAN
1/8" = 1'-0" 0 12'



WRC Decentralization Phase 2 (#9279.20)
Iowa Department of Administrative Services
1251 354th St, Woodward, IA 50276

CAS	ADD	1	02/07/2023	ADDENDUM #1
TLS				
100% CD				
2023-01-10				
2142203390				
FIELD BOOK				

BASEMENT MECHANICAL PIPING DEMOLITION PLAN

04-MD100

KEYNOTES	
KEY	NOTE
04-M01	REBALANCE HEATING COIL TO GPM LISTED BELOW.
04-M02	38 INCHES AROUND EACH BOILERS MINIMUM
04-M05	ADD LINE VOLTAGE COOLING-ONLY THERMOSTAT TO CONTROL EXHAUST FAN. SET TO 80° F.



SEAL

WRC Decentralization Phase 2 (#9279.20)
Iowa Department of Administrative Services
1251 354th St, Woodward, IA 50276


CAS	ADD	ADDENDUM #1
TLS	1	02072023
100% CD		
ISSUE DATE		2023-01-10
PROJECT NUMBER		2142203390
FIELD BOOK		

BASEMENT MECHANICAL PIPING PLAN


04-M100




A6 BASEMENT ENLARGED MECHANICAL PLAN
1/4" = 1'-0"




D6 BASEMENT MECHANICAL PIPING PLAN
1/8" = 1'-0"




3 3-Tier Fin Tube Piping Diagram - Piping in Floor Below
NOT TO SCALE




4 3-Tier Fin Tube Piping Diagram - Piping in Ceiling Above
NOT TO SCALE




F2 END SUCTION PUMP WITH VIBRATION ISOLATION DETAIL
NOT TO SCALE




1 1-Tier Fin Tube Piping Diagram - Piping in Floor Below
NOT TO SCALE




2 1-Tier Fin Tube Piping Diagram - Piping in Ceiling Above
NOT TO SCALE




F4 AIR SEPARATOR/BLADDER TYPE EXP. TANK DETAIL
NOT TO SCALE




5 Pot Feeder Piping Detail
NOT TO SCALE




D6 Interior Wall Pipe Penetration Detail (Through Conditioned Space)
NOT TO SCALE




E5 CIRCULATING PUMP DETAIL
NOT TO SCALE




F5 GAS-FIRED BOILER PIPING DETAIL
NOT TO SCALE



B6 HEATING WATER SCHEMATIC
NOT TO SCALE



D3 INSULATED PIPE HANGER DETAIL
NOT TO SCALE



F6 Interior Fire Rated Wall Pipe Penetration Detail
NOT TO SCALE

CAS	ADD	1	02/07/2023	ADDENDUM #1
TLS	100%	CD	2023-01-10	
ISSUED FOR	2023-01-10			
PROJECT NUMBER	2142203390			
FIELD BOOK				

November 10, 2022

Woodward Resource Center
ATTN: Mr. Rodney Carr
Facility Manager
1251 334th Street
Woodward, IA 50276

RE: Woodward Resource Center – Cottages – Asbestos Survey

Dear Mr. Carr:

Per your request and authorization, Shive-Hattery, Inc. performed asbestos surveys for the above referenced project on October 28 and 29, 2022. It is our understanding that the buildings will undergo renovations that may disturb suspect asbestos-containing building materials. It was the intent of the survey to determine what materials within the project area contain asbestos.

Methods and Procedures

The review for this project was performed by personnel trained and certified under the National Emission Standards for Hazardous Air Pollutants (NESHAP) regulations. Partial or destructive testing was not performed to reveal concealed conditions.

A sample from each suspect homogeneous area was collected from the project areas at the Woodward Resource Center Cottages. Pertinent information such as location, color, etc. was recorded for each suspect material. The samples were then sent to an NAVLAP accredited laboratory for analysis.

The samples were analyzed for asbestos fibers utilizing the Polarized Light Microscopy method of analysis by EMLab P&K of Phoenix, AZ. Each sample was analyzed for the six different types of fibrous asbestos forms of which a percentage, by volume, is estimated and summarized. As defined by the U.S. Environmental Protection Agency mandated AHERA regulations, the suspect material is considered an asbestos-containing material (ACM) if the material contains more than 1.0 percent of any one or a combination of asbestos fibers.

Pertinent information for each bulk sample has been summarized on the sample analytical results which can be found at the end of this report.

Summary of Findings

Cottage 101 Franklin:

Three (3) samples were collected from 5 homogeneous areas located at Cottage 101 Franklin. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Joint Compound w/ Multilayered Paint (Wall)	0%
2. White Drywall w/ Brown Paper (Wall)	0%
3. White Texture w/ Gray Paint (Wall)	0%
4. White Joint Compound w/ Multilayered Paint (Ceiling)	0%
5. White Drywall w/ Brown Paper (Ceiling)	0%



Cottage 103 Franklin:

Three (3) samples were collected from 5 homogeneous areas located at Cottage 103 Franklin. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Joint Compound w/ Multilayered Paint (Ceiling)	0%
2. White Drywall w/ Brown Paper (Ceiling)	0%
3. White Texture w/ Gray Paint (Wall)	0%
4. White Joint Compound w/ Multilayered Paint (Wall)	0%
5. White Drywall w/ Brown Paper (Wall)	0%

Cottage 104 Franklin:

Three (3) samples were collected from 4 homogeneous areas located at Cottage 104 Franklin. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Joint Compound w/ Multilayered Paint (Ceiling)	0%
2. White Drywall w/ Brown Paper (Ceiling)	0%
3. White Joint Compound w/ Multilayered Paint (Wall)	0%
4. White Drywall w/ Brown Paper (Wall)	0%

Cottage 105 Franklin:

Three (3) samples were collected from 6 homogeneous areas located at Cottage 105 Franklin. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Compound (Wall)	0%
2. White Joint Compound w/ Tan Paint (Wall)	0%
3. White Drywall w/ Brown Paper (Wall)	0%
4. White Compound (Ceiling)	0%
5. White Joint Compound w/ Tan Paint (Ceiling)	0%
6. White Drywall w/ Brown Paper (Ceiling)	0%

Cottage 107 Franklin:

Three (3) samples were collected from 6 homogeneous areas located at Cottage 107 Franklin. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Joint Compound (Ceiling)	0%
2. White Joint Compound w/ White Paint (Ceiling)	0%
3. Beige Drywall w/ Brown Paper and White Paint (Ceiling)	0%

4.	White Joint Compound w/ White Paint #1 (Wall)	0%
5.	White Joint Compound w/ White Paint #2 (Wall)	0%
6.	Beige Drywall w/ Brown/Green Paper (Wall)	0%

Cottage 108 Franklin:

Three (3) samples were collected from 8 homogeneous areas located at Cottage 108 Franklin. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Compound w/ Multilayered Paint (Ceiling)	0%
2. Cream Tape (Ceiling)	0%
3. White Joint Compound (Ceiling)	0%
4. White Drywall w/ Brown Paper (Ceiling)	0%
5. White Compound w/ Multilayered Paint (Wall)	0%
6. Cream Tape (Wall)	0%
7. White Joint Compound (Wall)	0%
8. White Drywall w/ Brown Paper (Wall)	0%

Cottage 109 Franklin:

Three (3) samples were collected from 5 homogeneous areas located at Cottage 109 Franklin. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Compound w/ Multilayered Paint (Ceiling)	0%
2. Brown Drywall w/ Brown/Green Paper (Ceiling)	0%
3. White Joint Compound (Wall)	0%
4. White Compound w/ Multilayered Paint (Wall)	0%
5. Brown Drywall w/ Brown/Green Paper (Wall)	0%

Cottage 200 Franklin:

Three (3) samples were collected from 6 homogeneous areas located at Cottage 200 Franklin. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Compound w/ White Paint (Ceiling)	0%
2. Off-White Compound w/ Multilayered Paint (Ceiling)	0%
3. White Drywall w/ Brown Paper (Ceiling)	0%
4. White Compound w/ White Paint (Wall)	0%
5. Off-White Compound w/ Tan Paint (Wall)	0%
6. Brown Drywall w/ Brown/Green Paper (Wall)	0%

Cottage 201 Franklin:

Eight (8) samples were collected from 16 homogeneous areas located at Cottage 201 Franklin. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. Off-White Joint Compound w/ White Paint (Ceiling)	0%
2. Off-White Compound w/ Multilayered Paint (Ceiling)	0%
3. White Drywall w/ Brown Paper (Ceiling)	0%
4. Off-White Joint Compound w/ White Paint (Wall)	0%
5. Off-White Compound w/ Multilayered Paint (Wall)	0%
6. White Drywall w/ Brown Paper (Wall)	0%
7. White Compound (Wall) – NE Restroom North Wall	2% Chrysotile*
8. Tan Mastic	0%
9. Yellow Linoleum	0%
10. Tan Linoleum	0%
11. Beige Caulk	0%
12. Brown/Gray Linoleum w/ Fibrous Backing	0%
13. Tan Mastic a/w Brown/Gray Linoleum	0%
14. Tan Stucco	0%
15. Gray Cementitious Material	0%
16. Dark Brown Mastic	0%

*Material was point counted for more accurate results.

Cottage 202 Franklin:

Four (4) samples were collected from 5 homogeneous areas located at Cottage 202 Franklin. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Joint Compound w/ White Paint (Ceiling)	0%
2. White Drywall w/ Brown Paper (Ceiling)	0%
3. White Joint Compound w/ White Paint (Wall)	0%
4. White Drywall w/ Brown Paper (Wall)	0%
5. Brown Mastic	0%

Cottage 203 Franklin:

Five (5) samples were collected from 9 homogeneous areas located at Cottage 203 Franklin. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Compound w/ Multilayered Paint (Ceiling)	0%
2. White Drywall w/ Brown Paper (Ceiling)	0%
3. White Compound w/ Multilayered Paint #1 (Wall)	0%

4.	White Compound w/ Multilayered Paint #2 (Wall)	0%
5.	White Drywall w/ Brown Paper (Wall)	0%
6.	Cream Non-Fibrous Material	0%
7.	Tan Mastic	0%
8.	Tan Linoleum w/ Fibrous Backing	0%
9.	Yellow Mastic	0%

Cottage 202 Pine:

Four (4) samples were collected from 9 homogeneous areas located at Cottage 202 Pine. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Compound w/ White Paint (Ceiling)	0%
2. Cream Tape (Ceiling)	0%
3. White Joint Compound (Ceiling)	0%
4. White Drywall w/ Brown Paper & Cream Paint (Ceiling)	0%
5. White Compound w/ White Paint (Wall)	0%
6. Cream Tape (Wall)	0%
7. White Joint Compound (Wall)	0%
8. White Drywall w/ Brown Paper & Cream Paint (Wall)	0%
9. Yellow Mastic	0%

Cottage 204 Pine:

Three (3) samples were collected from 5 homogeneous areas located at Cottage 204 Pine. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. Yellow Mastic	0%
2. White Joint Compound (Wall)	0%
3. White Drywall w/ Brown Paper (Wall)	0%
4. White Joint Compound (Ceiling)	0%
5. White Drywall w/ Brown Paper (Ceiling)	0%

Cottage 301 Pine:

Three (3) samples were collected from 6 homogeneous areas located at Cottage 301 Pine. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Joint Compound (Ceiling)	0%
2. White Compound w/ Multilayered Paint (Ceiling)	0%
3. White Drywall w/ Brown Paper (Ceiling)	0%
4. White Joint Compound (Wall)	0%
5. White Compound w/ Multilayered Paint (Wall)	0%
6. White Drywall w/ Brown Paper (Wall)	0%

Cottage 302 Pine:

Three (3) samples were collected from 4 homogeneous areas located at Cottage 302 Pine. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Joint Compound (Ceiling)	0%
2. White Drywall w/ Brown Paper & White Paint (Ceiling)	0%
3. White Joint Compound (Wall)	0%
4. White Drywall w/ Brown Paper & White Paint (Wall)	0%

Cottage 303 Pine:

Three (3) samples were collected from 4 homogeneous areas located at Cottage 303 Pine. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Joint Compound (Ceiling)	0%
2. White Drywall w/ Brown Paper & White Paint (Ceiling)	0%
3. White Joint Compound (Wall)	0%
4. White Drywall w/ Brown Paper & White Paint (Wall)	0%

Cottage 304 Pine:

Three (3) samples were collected from 6 homogeneous areas located at Cottage 304 Pine. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Joint Compound w/ White Paint (Ceiling)	0%
2. White Joint Compound w/ Multilayered Paint (Ceiling)	0%
3. White Drywall w/ Brown Paper (Ceiling)	0%
4. White Joint Compound w/ White Paint (Wall)	0%
5. White Compound w/ Multilayered Paint (Wall)	0%
6. White Drywall w/ Brown Paper (Wall)	0%

Cottage 103 Cedar Street:

Three (3) samples were collected from 4 homogeneous areas located at Cottage 103 Cedar Street. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Joint Compound (Ceiling)	0%
2. White Drywall w/ Brown Paper (Ceiling)	0%
3. White Joint Compound (Wall)	0%
4. White Drywall w/ Brown Paper (Wall)	0%

Cottage 201 Cedar Street:

Three (3) samples were collected from 5 homogeneous areas located at Cottage 201 Cedar Street. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. Semi-Transparent Caulk w/ White Paint (Wall)	0%
2. White Joint Compound & White Paint (Wall)	0%
3. Brown Drywall w/ Brown/Green Paper (Wall)	0%
4. White Joint Compound (Ceiling)	0%
5. Brown Drywall w/ Brown/Green Paper (Ceiling)	0%

Cottage 101 Cherry Lane:

Three (3) samples were collected from 8 homogeneous areas located at Cottage 101 Cherry Lane. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. Off-White Compound (Ceiling)	0%
2. White Compound w/ White Paint (Ceiling)	0%
3. Brown Adhesive (Ceiling)	0%
4. White Drywall w/ Brown Paper (Ceiling)	0%
5. Off-White Compound (Wall)	0%
6. White Compound w/ White Paint (Wall)	0%
7. Brown Adhesive (Wall)	0%
8. White Drywall w/ Brown Paper (Wall)	0%

Cottage 103 Cherry Lane:

Four (4) samples were collected from 7 homogeneous areas located at Cottage 103 Cherry Lane. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. Red Insulation	0%
2. Yellow Mastic	0%
3. White Joint Compound w/ White Paint (Ceiling)	0%
4. White Drywall w/ Brown Paper (Ceiling)	0%
5. White Joint Compound w/ White Paint (Wall)	0%
6. White Drywall w/ Brown Paper (Wall)	0%
7. White Joint Compound w/ White Paint (Wall) - NE Entryway	<1% Chrysotile

Cottage 104 Cherry Lane:

Three (3) samples were collected from 4 homogeneous areas located at Cottage 104 Cherry Lane. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Joint Compound (Ceiling)	0%
2. White Drywall w/ Brown Paper & White Paint (Ceiling)	0%
3. White Joint Compound (Wall)	0%
4. White Drywall w/ Brown Paper & White Paint (Wall)	0%

Cottage 105 Cherry Lane:

Three (3) samples were collected from 4 homogeneous areas located at Cottage 105 Cherry Lane. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Joint Compound w/ White Paint (Ceiling)	0%
2. White Drywall w/ Brown/Green Paper (Ceiling)	0%
3. White Joint Compound w/ White Paint (Wall)	0%
4. White Drywall w/ Brown/Green Paper (Wall)	0%

Cottage 107 Cherry Lane:

Three (3) samples were collected from 4 homogeneous areas located at Cottage 107 Cherry Lane. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Joint Compound w/ Multilayered Paint (Ceiling)	0%
2. White Drywall w/ Brown/Green Paper & Multilayered Paint (Ceiling)	0%
3. White Joint Compound w/ Multilayered Paint (Wall)	0%
4. White Drywall w/ Brown/Green Paper & Multilayered Paint (Wall)	0%

Recommendations

Thus, it appears that the proposed project will not disturb any asbestos-containing materials and asbestos abatement is not required.

During the inspection, cottage at 201 Franklin was undergoing bathroom wall tile renovations. This work is outside the scope of this project. Wall mastic was observed, and a sample collected due to easy access. The sample came back positive for asbestos. It is our recommendation to halt that project until the asbestos-containing material is abated prior to commencing with further work.

Trace amounts of asbestos were found in the joint compound in cottage 103 Cherry Lane. This homogeneous area is not asbestos-containing material as defined by the EPA and asbestos abatement is not required. However, it is important that OSHA guidelines be followed. If this material is to be disturbed, OSHA requires that the material be handled using safe work practices by personnel trained in the proper procedure for building materials containing minimal amounts of asbestos.

Please call our office if you should have any questions or comments.

Sincerely,

SHIVE-HATTERY, INC.



Grant W. Bridgford
License Number IA 22-7928 INSP
Expiration Date: February 10, 2023

GWB/mas

Encs.

Copy: Chad Siems, S-H

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 101 Franklin; 2142203390
EML ID: 3071775

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 101 Franklin; 2142203390

Date of Sampling: 10-27-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	3
Total Samples Analyzed:	3
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA.001A, Sheetrock and Joint Compound

Lab ID-Version‡: 14821628-1

Sample Layers	Asbestos Content
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001B, Sheetrock and Joint Compound

Lab ID-Version‡: 14821629-1

Sample Layers	Asbestos Content
White Texture with Gray Paint	ND
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001C, Sheetrock and Joint Compound

Lab ID-Version‡: 14821630-1

Sample Layers	Asbestos Content
White Texture with Gray Paint	ND
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 103 Franklin; 2142203390
EML ID: 3071781

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 103 Franklin; 2142203390

Date of Sampling: 10-27-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	3
Total Samples Analyzed:	3
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA-001A, Sheetrock and Joint Compound

Lab ID-Version‡: 14821242-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper and Multilayered Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA-001B, Sheetrock and Joint Compound

Lab ID-Version‡: 14821243-1

Sample Layers	Asbestos Content
Yellow Mastic	ND
White Joint Compound	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Poor

Location: HA-001C, Sheetrock and Joint Compound

Lab ID-Version‡: 14821244-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper and Multilayered Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 104 Franklin; 2142203390
EML ID: 3071838

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 104 Franklin; 2142203390

Date of Sampling: 10-27-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	3
Total Samples Analyzed:	3
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14822127-1

Sample Layers	Asbestos Content
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14822128-1

Sample Layers	Asbestos Content
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14822129-1

Sample Layers	Asbestos Content
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 105 Franklin; 2142203390
EML ID: 3071771

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 105 Franklin; 2142203390

Date of Sampling: 10-27-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	3
Total Samples Analyzed:	3
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA-001A, Sheetrock and Joint Compound

Lab ID-Version‡: 14821584-1

Sample Layers	Asbestos Content
White Compound	ND
White Joint Compound with Tan Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA-001B, Sheetrock and Joint Compound

Lab ID-Version‡: 14821585-1

Sample Layers	Asbestos Content
White Compound	ND
White Joint Compound with Tan Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA-001C, Sheetrock and Joint Compound

Lab ID-Version‡: 14821586-1

Sample Layers	Asbestos Content
White Compound	ND
White Joint Compound with Tan Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".



ASBESTOS ANALYSIS

Phoenix, AZ: NVLAP Lab Code 500031-0; CO-ELAP # AL-17343
 Orange County, CA: NVLAP Lab Code 200577-0
 San Bruno, CA: NVLAP Lab Code 200728-0; AHA IHLAP #102856
 San Diego, CA: NVLAP Lab Code 500034-0

FL: Lauderdale, FL: NVLAP Lab C
 Cherry Hill, NJ: NVLAP Lab Code
 Ft. Worth, TX: NVLAP Lab Code



003071771

CONTACT INFORMATION

Company: Shive-Hattery
 Address: 4125 Westown Pkwy #100, West Des Moines, IA 50266

Contact: Grant Bridgford

Special Instructions:
 *Point Count All Results Between 1-3%
 *Stop at 1st Positive Greater Than 10%
 *Email results to gbrdgford@shive-hattery.com

PROJECT INFORMATION

Project ID: Cottage 105 Franking

Project Desc: 242203390

ZIO Code: 10-27-02

PO Number:

TURN AROUND TIME CODES - (TAT)

STD - Standard (DEFAULT)

ND - Next Business Day

SD - Same Business Day Rush*

*RUSHES AVAILABLE FROM LOCATIONS LISTED ABOVE

Rushes received after 2pm or on weekends, will be considered received the next business day. Please alert us in advance of weekend analysis needs.

SAMPLE ID	DESCRIPTION	Sample Type (Below)	TAT (Above)	Total Volume (Air Samples Only)	NOTES
HH001A	Sheetrock & Joint Compound	B	STD		
B					
C					

REQUESTED SERVICES (✓ Boxes)	PCM	PLM	Rock & Soil	Other Requests
	Air			
Fiber Count (NIOSH 7400)				
OSHA with TWA				
EPA Method 600/R-93/116				
EPA Point Count (200 Point Count)				
EPA Point Count (400 Point Count)				
EPA Point Count (1000 Point Count)				
Gravimetric Point Count				
CARB 435 Method - Pre-crushed Sample				
CARB 435 Method - Regular Sample (7 Bus. Days)				
Non-Asbestos Fiber Ct. (NIOSH 7400) - "B" Counting Rules				
Lead Analysis				

SAMPLE TYPE CODES

A - Air	W - Wipe
B - Bulk	T - Tape
D - Dust	R - Rock
SO - Soil	O - Other

REINQUISHED BY

[Signature]

DATE & TIME

10-28-02 0800

RECEIVED BY

[Signature]

DATE & TIME

10-31-02 9:30 AM

By submitting this Chain of Custody, you agree to be bound by the terms and conditions set forth at <http://www.emlab.com/s/main/service/terms.html>

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 107 Franklin; 2142203390
EML ID: 3071790

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 107 Franklin; 2142203390

Date of Sampling: 10-27-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted: 3
Total Samples Analyzed: 3
Total Samples with Layer Asbestos Content > 1%: 0

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14822223-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Joint Compound with White Paint	ND
Beige Drywall with Brown Paper and White Paint	ND
Composite Non-Asbestos Content:	10% Cellulose < 1% Glass Fibers
Sample Composite Homogeneity:	Poor

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14822224-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
Beige Drywall with Brown/Green Paper and White Paint	ND
Composite Non-Asbestos Content:	10% Cellulose < 1% Glass Fibers
Sample Composite Homogeneity:	Poor

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14822225-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint #1	ND
White Joint Compound with White Paint #2	ND
Beige Drywall with Brown/Green Paper	ND
Composite Non-Asbestos Content:	10% Cellulose < 1% Glass Fibers
Sample Composite Homogeneity:	Poor

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 108 Franklin; 2142203390
EML ID: 3071839

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 108 Franklin; 2142203390

Date of Sampling: 10-27-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted: 3
Total Samples Analyzed: 3
Total Samples with Layer Asbestos Content > 1%: 0

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14822107-1

Sample Layers	Asbestos Content
White Compound with Multilayered Paint	ND
Cream Tape	ND
White Joint Compound	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	15% Cellulose
Sample Composite Homogeneity:	Poor

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14822108-1

Sample Layers	Asbestos Content
White Compound with Multilayered Paint	ND
Cream Tape	ND
White Joint Compound	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	15% Cellulose
Sample Composite Homogeneity:	Poor

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14822109-1

Sample Layers	Asbestos Content
White Compound with Multilayered Paint	ND
Cream Tape	ND
White Joint Compound	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	15% Cellulose
Sample Composite Homogeneity:	Poor

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

866.888.6653 www.EMLabPK.com
 Phoenix, AZ: NVLAP Lab Code 500031-0; CO-ELAP # AL-17343
 Orange County, CA: NVLAP Lab Code 200577-0
 San Bruno, CA: NVLAP Lab Code 200728-0; AHA IHLAP #102856
 San Diego, CA: NVLAP Lab Code 500034-0

003071839 

CONTACT INFORMATION

Company: Shive-Hattery
 Contact: Grant Bridgford
 Phone: 515.971.8844
 Address: 4125 Westown Pkwy #100, West Des Moines, IA 50266
 Special Instructions:
 • Point Count: All Results Between 1-3%
 • Stop at 1st Positive Greater Than 10%
 • Email results to gbridgford@shive-hattery.com

TURN AROUND TIME CODES - (TAT)

Project ID: *Village 108 Franklin*
 Project Desc: *2142203390*
 Project: Sampling
 Zip Code: *10.27.22* Date & Time: *10.27.22*
 PO Number:
 STD - Standard (DEFAULT)
 ND - Next Business Day
 SD - Same Business Day Rush*
* RUSHES AVAILABLE FROM LOCATIONS LISTED ABOVE
 Rushes received after 2pm or on weekends, will be considered received the next business day. Please alert us in advance of weekend analysis needs.

SAMPLE ID	DESCRIPTION	Sample Type (Below)	TAT (Above)	Total Volume (Air Samples Only)	NOTES
<i>HA-001A</i>	<i>Sheetrock Joint Compound</i>	<i>B</i>	<i>STD</i>		
<i>B</i>					
<i>C</i>					

REINQUISHED BY

DATE & TIME

Grant Bridgford

10.28.22 0800

RECEIVED BY

DATE & TIME

Grant Bridgford

10.31.22 4:30pm

ASBESTOS ANALYSIS

REQUESTED SERVICES (✓ Boxes)	PLM				Rock & Soil		Other Requests	
	PCM Air	Bulk	Rock & Soil	Other Requests	PCM Air	OSHA with TWA	Other Requests	
Fiber Count (NIOSH 7400)								
EPA Method 600/R-93/1116								
EPA Point Count (200 Point Count)								
EPA Point Count (400 Point Count)								
EPA Point Count (1000 Point Count)								
Gravimetric Point Count								
CARB 435 Method - Pre-crushed Sample								
CARB 435 Method - Regular Sample (7 Bus. Days)								
Non-Asbestos Fiber Ct. (NIOSH 7400) - "B" Counting Rules								
Lead Analysis								

By submitting this Chain of Custody, you agree to be bound by the terms and conditions set forth at <http://www.emlab.com/s/main/service/terms.html>

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 109 Franklin
EML ID: 3071767

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 109 Franklin

Date of Sampling: 10-27-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted: 3
Total Samples Analyzed: 3
Total Samples with Layer Asbestos Content > 1%: 0

Location: HA-001A, Sheetrock and Joint Compound

Lab ID-Version‡: 14821526-1

Sample Layers	Asbestos Content
White Compound with Multilayered Paint	ND
Brown Drywall with Brown/Green Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA-001B, Sheetrock and Joint Compound

Lab ID-Version‡: 14821527-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Compound with Multilayered Paint	ND
Brown Drywall with Brown/Green Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Poor

Location: HA-001C, Sheetrock and Joint Compound

Lab ID-Version‡: 14821528-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Compound with Multilayered Paint	ND
Brown Drywall with Brown/Green Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Poor

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 200 Franklin; 21422003390
EML ID: 3071796

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 200 Franklin; 21422003390

Date of Sampling: 10-26-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	3
Total Samples Analyzed:	3
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14821960-1

Sample Layers	Asbestos Content
White Compound with White Paint	ND
Off-White Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose < 1% Glass Fibers
Sample Composite Homogeneity:	Poor

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14821961-1

Sample Layers	Asbestos Content
White Compound with White Paint	ND
Off-White Compound with Tan Paint	ND
Brown Drywall with Brown/Green Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Poor

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14821962-1

Sample Layers	Asbestos Content
White Compound with White Paint	ND
Off-White Compound with Tan Paint	ND
Brown Drywall with Brown/Green Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Poor

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

CHAIN OF CUSTODY



866.888.6653 www.EMLabPK.com
 Phoenix, AZ: NVLAP Lab Code 500031-0; CO-ELAP # AL-17343
 Orange County, CA: NVLAP Lab Code 200577-0
 San Bruno, CA: NVLAP Lab Code 200728-0; AHA IHLAP #102856
 San Diego, CA: NVLAP Lab Code 500034-0

Ft. Lauderdale, FL: NVLAP Lab Code
 Cherry Hill, NJ: NVLAP Lab Code
 Ft. Worth, TX: NVLAP Lab Code



CONTACT INFORMATION

Company: Shive-Hattery
 Contact: Grant Bridgford
 Phone: 515.971.8844
 Address: 4125 Westown Pkwy #100, West Des Moines, IA 50266
 Special Instructions:
 *Point Count All Results Between 1-3%
 *Stop at 1st Positive Greater Than 10%
 *Email results to gbridgford@shive-hattery.com

PROJECT INFORMATION

Project ID: Cottage 200 Franklin
 Project Desc.: 2142203390
 Project: Sampling
 ZIP Code: Date & Time: 10.26.22
 PO Number:

TURN AROUND TIME CODES - (TAT)

STD - Standard (DEFAULT)
 ND - Next Business Day
 SD - Same Business Day Rush*
* RUSHES AVAILABLE FROM LOCATIONS LISTED ABOVE
 Rushes received after 2pm or on weekends, will be considered received the next business day. Please alert us in advance of weekend analysis needs.

ASBESTOS ANALYSIS

REQUESTED SERVICES (✓ Boxes)

PCM Air	PLM				Rock & Soil	Other Requests
	Bulk	Bulk	Bulk	Bulk		
Fiber Count (NIOSH 7400)					CARB 435 Method - Pre-crushed Sample	Non-Asbestos Fiber Ct. (NIOSH 7400) - "B" Counting Rules
OSHA with TWA					CARB 435 Method - Regular Sample (7 Bus. Days)	Lead Analysis

SAMPLE TYPE CODES

A - Air	W - Wipe
B - Bulk	T - Tape
D - Dust	R - Rock
SO - Soil	O - Other

SAMPLE ID	DESCRIPTION	Sample Type (Below)	TAT (Above)	Total Volume (Air Samples Only)	NOTES
HA-001A	Sneetrock & joint compound	B	STD		
B		I			
C		I			

RELINQUISHED BY

Grant Bridgford
 DATE & TIME: 10.28.22 0800

RECEIVED BY

Sammy
 DATE & TIME: 10-31-22 9:30am

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 201 Franklin; 2142203390
EML ID: 3071801

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 201 Franklin; 2142203390

Date of Sampling: 10-26-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	8
Total Samples Analyzed:	8
Total Samples with Layer Asbestos Content > 1%:	1

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14821905-1

Sample Layers	Asbestos Content
White Drywall with Brown Paper and White Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14821906-1

Sample Layers	Asbestos Content
Off-White Joint Compound with White Paint	ND
Off-White Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Poor

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14821907-1

Sample Layers	Asbestos Content
Off-White Joint Compound with White Paint	ND
Off-White Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Poor

Location: HA.002, Yellow Mastic A/W Ceramic Wall Tile

Lab ID-Version‡: 14821908-1

Sample Layers	Asbestos Content
White Compound	2% Chrysotile
Tan Mastic	ND
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 201 Franklin; 2142203390

Date of Sampling: 10-26-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Location: HA.003, Yellow & Tan Linoleum

Lab ID-Version‡: 14821909-1

Sample Layers	Asbestos Content
Yellow Linoleum	ND
Tan Linoleum	ND
Sample Composite Homogeneity:	Moderate

Location: HA.004, Tan & Gray Linoleum

Lab ID-Version‡: 14821910-1

Sample Layers	Asbestos Content
Beige Caulk	ND
Brown/Gray Linoleum with Fibrous Backing	ND
Tan Mastic	ND
Composite Non-Asbestos Content:	5% Cellulose < 1% Glass Fibers < 1% Synthetic Fibers
Sample Composite Homogeneity:	Poor

Location: HA.005, Tan Stucco

Lab ID-Version‡: 14821911-1

Sample Layers	Asbestos Content
Tan Stucco	ND
Gray Cementitious Material	ND
Sample Composite Homogeneity:	Moderate

Location: HA.006, Brown Cove Base Mastic

Lab ID-Version‡: 14821912-1

Sample Layers	Asbestos Content
Dark Brown Mastic	ND
Sample Composite Homogeneity:	Good

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 201 Franklin; 2142203390
EML ID: 3071801

Approved by:

Dates of Analysis:

Asbestos-EPA 400 point count: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos-EPA 400 point count (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1262)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. Due to the nature of the analyses performed, field blank correction of results is not applied. The results relate only to the samples as received and tested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 201 Franklin; 2142203390

Date of Sampling: 10-26-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS POINT COUNT REPORT

Location:	HA.002 Yellow Mastic A/W Ceramic Wall Tile		
Total Points Counted:	400		
Lab ID-Version‡:	14838972-1		
Sample Layers	Asbestos Type	Asbestos Points Counted	Asbestos Concentration (%)
White Compound	Chrysotile	8	2
Layer Totals:		8	2

The analytical sensitivity is 1 asbestos point. The limit of detection is 1 asbestos point divided by the total number of points counted and multiplied by 100.

The results relate only to the items tested. Interpretation is left to the company and/or persons who conducted the field work. The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government.

All samples were received in acceptable condition unless otherwise noted. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

CHAIN OF CUSTODY



ASBESTOS ANALYSIS

866.888.6653 www.EMLabPK.com
 Phoenix, AZ: NVLAP Lab Code 500031-0; CO-EIAP # AL-17343
 Orange County, CA: NVLAP Lab Code 200577-0
 San Bruno, CA: NVLAP Lab Code 200728-0; AHA IHLAP #102856
 San Diego, CA: NVLAP Lab Code 500034-0

FL: Lauderdale, FL: NVLAP Lab Code
 Cherry Hill, NJ: NVLAP Lab Code
 Ft. Worth, TX: NVLAP Lab Code



CONTACT INFORMATION

Company: Shive-Hattery

Address: 4125 Westown Pkwy #100, West Des Moines, IA 50266

Contact: Grant Bridgford

Special Instructions:
 *Point Count All Results Between 1-3%
 *Stop at 1st Positive Greater Than 10%
 *Email results to gbridgford@shive-hattery.com

Phone: 515.971.8844

PROJECT INFORMATION

Project ID: Cottage 201 Franklin

Project Desc: 242203350

Project Zip Code: Sampling Date & Time: 10-26-22

PO Number:

TURN AROUND TIME CODES - (TAT)

STD - Standard (DEFAULT)

ND - Next Business Day

SD - Same Business Day Rush*

*RUSHES AVAILABLE FROM LOCATIONS LISTED ABOVE

Rushes received after 2pm or on weekends, will be considered received the next business day. Please alert us in advance of weekend analysis needs.

SAMPLE ID	DESCRIPTION	Sample Type (Below)	TAT (Above)	Total Volume (Air Samples Only)	NOTES
HA-001A	Sheetrock & Joint Compound	B	STD		
B					
C					
HA002	Yellow Mastic w/ Ceramic Wall				
HA-003	Yellow & Tan Linoleum Tile				
HA-004	Tan & Gray Linoleum				
HA-005	Tan Stucco				
HA-006	Brown Cove Base Mastic				

SAMPLE TYPE CODES

A - Air	W - Wipe
B - Bulk	T - Tape
D - Dust	R - Rock
SO - Soil	O - Other

RELINQUISHED BY

[Signature]

DATE & TIME

10-28-22 0800

RECEIVED BY

[Signature]

DATE & TIME

10-31-22 11:30am

REQUESTED SERVICES (✓ Boxes)	PCM	Bulk	Rock & Soil	Other Requests
	Air			
Fiber Count (NIOSH 7400)				
OSHA with TWA				
EPA Method 600/R-93/116				
EPA Point Count (200 Point Count)				
EPA Point Count (400 Point Count)				
EPA Point Count (1000 Point Count)				
Gravimetric Point Count				
CARB 435 Method - Pre-crushed Sample				
CARB 435 Method - Regular Sample (7 Bus. Days)				
Non-Asbestos Fiber Ct. (NIOSH 7400) - "B" Counting Rules				
Lead Analysis				

By submitting this Chain of Custody, you agree to be bound by the terms and conditions set forth at <http://www.emlab.com/s/main/serviceterms.html>

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 202 Franklin; 2142203390
EML ID: 3071840

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 202 Franklin; 2142203390

Date of Sampling: 10-26-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	4
Total Samples Analyzed:	4
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14822076-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14822077-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14822078-1

Sample Layers	Asbestos Content
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.002, Brown Cove Base Mastic

Lab ID-Version‡: 14822079-1

Sample Layers	Asbestos Content
Brown Mastic	ND
Sample Composite Homogeneity:	Good

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 203 Franklin; 2142203390
EML ID: 3071844

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 203 Franklin; 2142203390

Date of Sampling: 10-26-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted: 5
Total Samples Analyzed: 5
Total Samples with Layer Asbestos Content > 1%: 0

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14822043-1

Sample Layers	Asbestos Content
White Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14822044-1

Sample Layers	Asbestos Content
White Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14822045-1

Sample Layers	Asbestos Content
White Compound with Multilayered Paint #1	ND
White Compound with Multilayered Paint #2	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.002, Cream Wall Matting

Lab ID-Version‡: 14822046-1

Sample Layers	Asbestos Content
Cream Non-Fibrous Material	ND
Tan Mastic	ND
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Client: Shive-Hattery
C/O: Grant Bridgford
Re: Cottage 203 Franklin; 2142203390

Date of Sampling: 10-26-2022
Date of Receipt: 10-31-2022
Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Location: HA.003, Tan & Gray Speckled Linoleum

Lab ID-Version‡: 14822047-1

Sample Layers	Asbestos Content
Tan Linoleum with Fibrous Backing	ND
Yellow Mastic	ND
Composite Non-Asbestos Content:	15% Cellulose < 1% Glass Fibers
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 202 Pine; 2142203390
EML ID: 3071786

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 202 Pine; 2142203390

Date of Sampling: 10-27-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	4
Total Samples Analyzed:	4
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA-001A, Sheetrock and Joint Compound

Lab ID-Version‡: 14822087-1

Sample Layers	Asbestos Content
White Compound with White Paint	ND
Cream Tape	ND
White Joint Compound	ND
White Drywall with Brown Paper and Cream Paint	ND
Composite Non-Asbestos Content:	15% Cellulose
Sample Composite Homogeneity:	Poor

Location: HA-001B, Sheetrock and Joint Compound

Lab ID-Version‡: 14822088-1

Sample Layers	Asbestos Content
White Compound with White Paint	ND
Cream Tape	ND
White Joint Compound	ND
White Drywall with Brown Paper and Cream Paint	ND
Composite Non-Asbestos Content:	15% Cellulose
Sample Composite Homogeneity:	Poor

Location: HA-001C, Sheetrock and Joint Compound

Lab ID-Version‡: 14822089-1

Sample Layers	Asbestos Content
White Compound with White Paint	ND
Cream Tape	ND
White Joint Compound	ND
White Drywall with Brown Paper and Cream Paint	ND
Composite Non-Asbestos Content:	15% Cellulose
Sample Composite Homogeneity:	Poor

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Client: Shive-Hattery
C/O: Grant Bridgford
Re: Cottage 202 Pine; 2142203390

Date of Sampling: 10-27-2022
Date of Receipt: 10-31-2022
Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Location: HA-002, Yellow Wall Mastic

Lab ID-Version‡: 14822090-1

Sample Layers	Asbestos Content
Yellow Mastic	ND
Sample Composite Homogeneity:	Good

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 204 Pine; 2142203390
EML ID: 3071833

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 204 Pine; 2142203390

Date of Sampling: 10-27-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	3
Total Samples Analyzed:	3
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14822145-1

Sample Layers	Asbestos Content
Yellow Mastic	ND
White Joint Compound	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Poor

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14822146-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper and Multilayered Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14822147-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper and Multilayered Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 301 Pine; 2142203390
EML ID: 3071856

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 301 Pine; 2142203390

Date of Sampling: 10-26-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	3
Total Samples Analyzed:	3
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14821546-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14821547-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14821548-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 302 Pine; 2142203390
EML ID: 3071831

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 302 Pine; 2142203390

Date of Sampling: 10-27-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted: 3
Total Samples Analyzed: 3
Total Samples with Layer Asbestos Content > 1%: 0

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14822161-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper and White Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14822162-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper and White Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14822163-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper and White Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 303 Pine; 2142203390
EML ID: 3071855

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 303 Pine; 2142203390

Date of Sampling: 10-26-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	3
Total Samples Analyzed:	3
Total Samples with Layer Asbestos Content > 1%:	0

Location: 303.HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14821980-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
White Drywall with Brown Paper and White Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: 303.HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14821981-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
White Drywall with Brown Paper and White Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: 303.HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14821982-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper and White Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 304 Pine; 21422033090
EML ID: 3071825

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 304 Pine; 21422033090

Date of Sampling: 10-27-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	3
Total Samples Analyzed:	3
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA-001A, Sheetrock and Joint Compound

Lab ID-Version‡: 14822154-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA-001B, Sheetrock and Joint Compound

Lab ID-Version‡: 14822155-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA-001C, Sheetrock and Joint Compound

Lab ID-Version‡: 14822156-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 103 Cedar St.; 2142203390
EML ID: 3071848

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 103 Cedar St.; 2142203390

Date of Sampling: 10-26-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	3
Total Samples Analyzed:	3
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14821669-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14821670-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14821671-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

CHAIN OF CUSTODY



ASBESTOS ANALYSIS

REQUESTED SERVICES (✓ Boxes)

866.888.6653 www.EMLabPK.com
 Phoenix, AZ: NVLAP Lab Code 500031-0; CO-ELAP # AL-17343
 Ft. Lauderdale, FL: NVLAP Lab C
 Orange County, CA: NVLAP Lab Code 200577-0
 Cherry Hill, NJ: NVLAP Lab Code
 San Bruno, CA: NVLAP Lab Code 200728-0; AIHA IHLAP #102856
 Ft. Worth, TX: NVLAP Lab Code
 San Diego, CA: NVLAP Lab Code 500034-0



CONTACT INFORMATION

Company: Shive-Hattery
 Address: 4125 Westown Pkwy #100, West Des Moines, IA 50266
 Contact: Grant Bridgford
 Phone: 515.971.8844
 Special Instructions:
 *Point Count All Results Between 1-3%
 *Stop at 1st Positive Greater Than 10%
 *Email results to gbriddford@shive-hattery.com

PROJECT INFORMATION

Project ID: Cottage 103 Cedar St.
 Project Desc: 21422203390
 Project: Sampling Date & Time: 10.26.02
 ZIP Code: SD - Same Business Day Rush*
 PO Number: *RUSHES AVAILABLE FROM LOCATIONS LISTED ABOVE

TURN AROUND TIME CODES - (TAT)

STD - Standard (DEFAULT)
 NID - Next Business Day
 Rushes received after 2pm or on weekends, will be considered received the next business day
 Please alert us in advance of weekend analysis needs.

SAMPLE ID	DESCRIPTION	Sample Type (Below)	TAT (Above)	Total Volume (Air Samples Only)	NOTES
HA-0014	Sweatshop & Joint Compound B		STD		
B					
C					

SAMPLE TYPE CODES

A - Air W - Wipe
 B - Bulk T - Tape
 D - Dust R - Rock
 SO - Soil O - Other

RELINQUISHED BY

Grant Bridgford

DATE & TIME

10.28.02 0800

RECEIVED BY

Grant Cooper

DATE & TIME

10-31-02 01:30 PM

PCM Air	PLM				Rock & Soil	Other Requests
	Bulk	Soil	Soil	Soil		
Fiber Count (NIOSH 7400)						
OSHA with TWA						
EPA Method 600/R-93/116			X			
EPA Point Count (200 Point Count)						
EPA Point Count (400 Point Count)						
EPA Point Count (1000 Point Count)						
Gravimetric Point Count						
CARB 435 Method - Pre-crushed Sample						
CARB 435 Method - Regular Sample (7 Bus. Days)						
Non-Asbestos Fiber Ct. (NIOSH 7400) - *B* Counting Rules						
Lead Analysis						

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 201 Cedar St; 2142203390
EML ID: 3071802

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 201 Cedar St; 2142203390

Date of Sampling: 10-26-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	3
Total Samples Analyzed:	3
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14821870-1

Sample Layers	Asbestos Content
Semi-Transparent Caulk with White Paint	ND
White Joint Compound with White Paint	ND
Brown Drywall with Brown/Green Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14821871-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
Brown Drywall with Brown/Green Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14821872-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
Brown Drywall with Brown/Green Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

CHAIN OF CUSTODY



866.888.6653 www.EMLabPK.com
 Phoenix, AZ: NVLAP Lab Code 500031-0; CO-ELAP # AL-17343
 Orange County, CA: NVLAP Lab Code 200577-0
 San Bruno, CA: NVLAP Lab Code 200728-0; AIHA IHLAP #102856
 San Diego, CA: NVLAP Lab Code 500034-0

Ft. Lauderdale, FL: NVLAP Lab Co
 Cherry Hill, NJ: NVLAP Lab Code 2
 Ft. Worth, TX: NVLAP Lab Code 21

003071802



CONTACT INFORMATION

Company: Shive-Hattery
 Address: 4125 Westown Pkwy #100, West Des Moines, IA 50286
 Contact: Grant Bridgford
 Phone: 515.971.8844

Special Instructions:
 * Point Count All Results Between 1-3%
 * Stop at 1st Positive Greater Than 10%
 * Email results to gbridgford@shive-hattery.com

PROJECT INFORMATION

Project ID: *Coffage 201 Cedar St*
 Project Desc: *2142203390*
 Project Zip Code: *10.26.02*
 PO Number:

TURN AROUND TIME CODES - (TAT)

STD - Standard (DEFAULT)
 ND - Next Business Day
 SD - Same Business Day Rush*
 * RUSHES AVAILABLE FROM LOCATIONS LISTED ABOVE

Rushes received after 2pm or on weekends, will be considered received the next business day. Please alert us in advance of weekend analysis needs.

SAMPLE ID	DESCRIPTION	Sample Type (Below)	TAT (Above)	Total Volume (Air Samples Only)	NOTES
<i>H4 001A</i>	<i>Sweetrat & Joint Compound B</i>	<i>B</i>	<i>STD</i>		
<i>B</i>		<i>I</i>	<i>I</i>		
<i>C</i>		<i>I</i>	<i>I</i>		

SAMPLE TYPE CODES

A - Air	W - Wipe
B - Bulk	T - Tape
D - Dust	R - Rock
SO - Soil	O - Other

RELINQUISHED BY

Grant Bridgford

DATE & TIME

10.26.02 0800

RECEIVED BY

Grant Bridgford

DATE & TIME

10-31-02 9:30am

ASBESTOS ANALYSIS REQUESTED SERVICES (✓ Boxes)

PCM Air	<input type="checkbox"/>
PLM Bulk	EPA Method 600/R-93/116 <input checked="" type="checkbox"/>
	EPA Point Count (200 Point Count) <input type="checkbox"/>
	EPA Point Count (400 Point Count) <input type="checkbox"/>
	EPA Point Count (1000 Point Count) <input type="checkbox"/>
	Gravimetric Point Count <input type="checkbox"/>
Rock & Soil	CARB 435 Method - Pre-crushed Sample <input type="checkbox"/>
	CARB 435 Method - Regular Sample (7 Bus. Days) <input type="checkbox"/>
Other Requests	Non-Asbestos Fiber Ct. (NIOSH 7400) - *B* Counting Rules <input type="checkbox"/>
	Lead Analysis <input type="checkbox"/>

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 101 Cherry Ln; 2142203390
EML ID: 3071793

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 101 Cherry Ln; 2142203390

Date of Sampling: 10-26-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	3
Total Samples Analyzed:	3
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14821967-1

Sample Layers	Asbestos Content
Off-White Compound	ND
White Compound with White Paint	ND
Brown Adhesive	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose < 1% Glass Fibers
Sample Composite Homogeneity:	Poor

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14821968-1

Sample Layers	Asbestos Content
Off-White Compound	ND
White Compound with White Paint	ND
Brown Adhesive	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose < 1% Glass Fibers
Sample Composite Homogeneity:	Poor

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14821969-1

Sample Layers	Asbestos Content
Off-White Compound	ND
White Compound with White Paint	ND
Brown Adhesive	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose < 1% Glass Fibers
Sample Composite Homogeneity:	Poor

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

866.888.6653 www.EMLabPK.com
 Phoenix, AZ: NVLAP Lab Code 500031-0; CO-ELAP # AL-17343
 Orange County, CA: NVLAP Lab Code 200577-0
 San Bruno, CA: NVLAP Lab Code 200728-0; AIHA IHLAP #102856
 San Diego, CA: NVLAP Lab Code 500034-0



ASBESTOS ANALYSIS
 REQUESTED SERVICES (✓ Boxes)

CONTACT INFORMATION

Company: Shive-Hattery
 Contact: Grant Bridgford
 Phone: 515.971.8844
 Address: 4125 Westown Pkwy #100, West Des Moines, IA 50266
 Special Instructions:
 *Point Count All Results Between 1-3%
 *Stop at 1st Positive Greater Than 10%
 *Email results to gbridgford@shive-hattery.com



PROJECT INFORMATION

Project ID: Cottage 101 Cherry Ln
 Project Desc: 2142203390
 Project: Sampling Date & Time: 10-26-22
 Zip Code:
 PO Number:
 STD - Standard (DEFAULT)
 ND - Next Business Day
 SD - Same Business Day Rush*
 *RUSHES AVAILABLE FROM LOCATIONS LISTED ABOVE

TURN AROUND TIME CODES - (TAT)

Rushes received after 2pm or on weekends, will be considered received the next business day. Please alert us in advance of weekend analysis needs.

SAMPLE ID	DESCRIPTION	Sample Type (Below)	TAT (Above)	Total Volume (Air Samples Only)	NOTES
HA-001A	Sweetrock & Joint compound	B	STD		
B					
C					

SAMPLE TYPE CODES	RELINQUISHED BY	DATE & TIME	RECEIVED BY	DATE & TIME
A - Air		10-28-22 0800		10-28-22 2:30 PM
B - Bulk				
D - Dust				
SO - Soil				
O - Other				

By submitting this Chain of Custody, you agree to be bound by the terms and conditions set forth at <http://www.emlab.com/s/main/service/terms.html>
 Copyright © 2002-2010 EMLab P&K
 Adhesives COC, Doc # 04071, Rev08, 09/01/0, Page 1 of 1, Q4

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 103 Cherry Ln; 2142203390
EML ID: 3071814

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 103 Cherry Ln; 2142203390

Date of Sampling: 10-26-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	4
Total Samples Analyzed:	4
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA.0001, Red Linoleum

Lab ID-Version‡: 14821737-1

Sample Layers	Asbestos Content
Red Insulation	ND
Yellow Mastic	ND
Sample Composite Homogeneity:	Moderate

Location: HA.002A, Sheetrock & Joint Compound

Lab ID-Version‡: 14821738-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.002B, Sheetrock & Joint Compound

Lab ID-Version‡: 14821739-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.002C, Sheetrock & Joint Compound

Lab ID-Version‡: 14821740-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	< 1% Chrysotile
White Drywall with Brown Paper	ND
Composite Asbestos Fibrous Content:	< 1% Asbestos
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Comments: Composite content provided for this analysis has been performed by following the NESHAP guidelines.

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 104 Cherry Ln; 2145503390
EML ID: 3071817

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 104 Cherry Ln; 2145503390

Date of Sampling: 10-27-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted: 3
Total Samples Analyzed: 3
Total Samples with Layer Asbestos Content > 1%: 0

Location: HA-001A, Sheetrock and Joint Compound

Lab ID-Version‡: 14821999-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper and White Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA-001B, Sheetrock and Joint Compound

Lab ID-Version‡: 14822000-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper and White Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA-001C, Sheetrock and Joint Compound

Lab ID-Version‡: 14822001-1

Sample Layers	Asbestos Content
White Joint Compound	ND
White Drywall with Brown Paper and White Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 105 Cherry Ln; 2142203390
EML ID: 3071808

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 105 Cherry Ln; 2142203390

Date of Sampling: 10-26-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	3
Total Samples Analyzed:	3
Total Samples with Layer Asbestos Content > 1%:	0

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14821831-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
White Drywall with Brown/Green Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14821832-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
White Drywall with Brown/Green Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14821833-1

Sample Layers	Asbestos Content
White Joint Compound with White Paint	ND
White Drywall with Brown/Green Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

866.888.6653 www.EMLabPK.com
 Phoenix, AZ: NVLAP Lab Code 500031-0; CO-ELAP # AL-17343
 Orange County, CA: NVLAP Lab Code 200577-0
 San Bruno, CA: NVLAP Lab Code 200728-0; AIHA IHLAP #102856
 San Diego, CA: NVLAP Lab Code 500034-0



CONTACT INFORMATION

Company: Shive-Hattery
 Contact: Grant Bridgford
 Phone: 515.971.8844
 Address: 4125 Westown Pkwy #100, West Des Moines, IA 50266
 Special Instructions:
 *Point Count All Results Between 1-3%
 *Stop at 1st Positive Greater Than 10%
 *Email results to gbridgford@shive-hattery.com

TURN AROUND TIME CODES - (TAT)

Project ID: Cottage 105 Cherry Ln
 Project Desc: 2142203340
 Project: Sampling Date & Time: 10.26.09
 ZIP Code: PO Number:
 STD - Standard (DEFAULT)
 NID - Next Business Day
 SD - Same Business Day Rush
 *RUSHES AVAILABLE FROM LOCATIONS LISTED ABOVE
 Rushes received after 2pm or on weekends, will be considered received the next business day. Please alert us in advance of weekend analysis needs.

SAMPLE ID	DESCRIPTION	Sample Type (Below)	TAT (Above)	Total Volume (Air Samples Only)	NOTES
WH-001A	Sneetch joint compound	B	STD		
B					
C					

SAMPLE TYPE CODES

A - Air	W - Wipe
B - Bulk	T - Tape
D - Dust	R - Rock
SO - Soil	O - Other

RELINQUISHED BY

Grant Bridgford

DATE & TIME

10.28.09 0800

RECEIVED BY

Grant Bridgford

DATE & TIME

10-31-09 12:30 pm

ASBESTOS ANALYSIS

REQUESTED SERVICES (✓ Boxes)

PCM Air	PLM				Rock & Soil	Other Requests
	Bulk	Soil	Rock & Soil	Other Requests		
Fiber Count (NIOSH 7400)						
OSHA with TWA						
EPA Method 600/R-93/116						
EPA Point Count (200 Point Count)						
EPA Point Count (400 Point Count)						
EPA Point Count (1000 Point Count)						
Gravimetric Point Count						
CARB 435 Method - Pre-crushed Sample						
CARB 435 Method - Regular Sample (7 Bus. Days)						
Non-Asbestos Fiber Ct. (NIOSH 7400) - "B" Counting Rules						
Lead Analysis						

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Cottage 107 Cherry Ln; 2142203390
EML ID: 3071805

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Cottage 107 Cherry Ln; 2142203390

Date of Sampling: 10-26-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted: 3
Total Samples Analyzed: 3
Total Samples with Layer Asbestos Content > 1%: 0

Location: HA.001A, Sheetrock & Joint Compound

Lab ID-Version‡: 14821838-1

Sample Layers	Asbestos Content
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown/Green Paper and Multilayered Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001B, Sheetrock & Joint Compound

Lab ID-Version‡: 14821839-1

Sample Layers	Asbestos Content
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown/Green Paper and Multilayered Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

Location: HA.001C, Sheetrock & Joint Compound

Lab ID-Version‡: 14821840-1



Sample Layers	Asbestos Content
White Joint Compound with Multilayered Paint	ND
White Drywall with Brown/Green Paper and Multilayered Paint	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Bld. 101F




BLUESTONE P&E RESERVES PROPRIETARY RIGHTS, INCLUDING
 COPYRIGHT, TO THE DRAWING AND THE DATA THEREON. THESE
 SHOWN DRAWINGS ARE THE PROPERTY OF
 BLUESTONE P&E AND SHALL NOT BE REPRODUCED
 FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN
 APPROVAL AND PARTICIPATION OF BLUESTONE P&E.
 © 2011 BLUESTONE P&E


UNIT STYLE C PLUMBING PLANS	D.A.S. WOODWARD MECHANICAL UPGRADES 1251 34TH STREET WOODWARD, IOWA 50276		DEPARTMENT OF ADMINISTRATIVE SERVICES HOOVER STATE OFFICE BUILDING 1305 EAST WALNUT ST., DES MOINES, IOWA 50319		PROJECT NO. 112-089		 bluestone engineering	DATE	BY	DATE
	REVISION		DESIGNED	DRAWN	CHECKED	LAST UPDATE		DATE	BY	DATE

SHEET
PIC

Bid. 103F



1 COTTAGE STYLE "A" PLUMBING DEMO PLAN



2 COTTAGE STYLE "A" PLUMBING PLAN

- KEYED NOTES (ENTIRE SHEET):**
1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECREATION PIPING, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FINE PROTECTION REMAINS TO REMAIN.
 2. INSTALL NEW 24" x 24" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. GOODWAY LOCATION WITH ROOF BRUSSE LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE ISSUED TO A INDUSTRIES TO SERIES. INSTALL PER MANUFACTURERS REQUIREMENTS.
 3. CONNECT DEDICATED HW400 LINE TO DRAINWASHER.
 4. SKYLIGHT DO NOT ROUTE PIPING IN THIS AREA.
 5. DEMO EXISTING MIXING VALVE ASSEMBLY BENEATH SINK. RECONNECT SINK TO DOMESTIC HOT WATER LINE.

- GENERAL NOTES (ENTIRE SHEET):**
1. ROUTE ALL PIPING IN ATTIC SPACE.
 2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
 3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 8'-0".
 4. DEMO ALL EXISTING HWC PIPING IN ATTIC. PIPING TO BE REPLACED.
 5. REFER TO DRAWING P2.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FIXTURE TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 109.9 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

DATE	BY	REVISION
4.23.13	INC	LAST UPDATE
4.23.13	INC	
4.23.13	INC	
4.23.13	INC	

PROJECT NO. 117-089


bluestone

DEPARTMENT OF ADMINISTRATIVE SERVICES
 HOWE STATE OFFICE BUILDING
 1306 EAST WALNUT ST., DES MOINES, IOWA 50319


D.A.S. WOODWARD
 MECHANICAL UPGRADES
 1251 334TH STREET
 WOODWARD, IOWA 50276

UNIT STYLE A PLUMBING PLANS

BLUESTONE PUR PROVIDES PROPRIETARY RIGHTS. BELIEVING CONTRACTOR TO BE OBLIGED TO USE THE DATA HEREIN EXCLUSIVELY FOR THE PROJECT AND NOT TO BE USED OR REPRODUCED WITHOUT THE APPROVAL AND PARTICIPATION OF BLUESTONE AND D.A.S. WOODWARD.



1 COTTAGE STYLE "C" PLUMBING DEMO PLAN



1 COTTAGE STYLE "C" PLUMBING PLAN

Bld. 104F

KEYED NOTES (ENTIRE SHEET):

1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PIPING, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
2. INSTALL NEW 3/4" x 1/2" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING, APPROPRIATE LOCATION, IN THE ROOF TRUSS LOCATING AIR VALVE LOCATION. ACCESS PANEL TO BE MANUFACTURED ACCORDINGLY.
3. DEMO EXISTING HWH40 PIPING TO EXISTING DISHWASHER.
4. CONNECT NEW DEDICATED HWH40 PIPING TO EXISTING DISHWASHER.
5. DEMO EXISTING MIXING VALVE ASSEMBLY BENEATH SINK.
6. RECONNECT SINK TO EXISTING HOT WATER PIPING.
7. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.

GENERAL NOTES (ENTIRE SHEET):

1. ROUTE ALL PIPING IN ATTIC SPACE.
2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 6'-0".
4. DEMO ALL EXISTING HWC PIPING IN ATTIC. PIPING TO BE REPLACED.
5. REFER TO DRAWING P2.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE


CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FIXTURES TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 109.9 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.


BLUESTONE PLS. RESERVE PROMPTLY. HOLDING CONTRACTS TO THE WORK AND TO ALL OTHERS. NO DRAWING, COPY OR PART OF THE FOLLOWING PROPERTY OF BLUESTONE PLS. AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE WRITTEN APPROVAL AND PARTICIPATION OF BLUESTONE PLS. © 2011 BLUESTONE PLS.

REVISION	DATE	BY	DATE
ISSUED	04/29/13	DKC	04/29/13
REVISION		DKC	04/29/13
CHANGED		DKC	04/29/13
LAST UPDATE: 04/29/13			
PROJECT NO. 112-089			
DEPARTMENT OF ADMINISTRATIVE SERVICES HOOVER STATE OFFICE BUILDING 1305 EAST WALNUT ST., DES MOINES, IOWA 50319			
D.A.S. WOODWARD MECHANICAL UPGRADES 1251 334TH STREET WOODWARD, IOWA 50276			
UNIT STYLE C PLUMBING PLANS			
SHEET PIC			



1 COTTAGE STYLE "B" PLUMBING DEMO PLAN

BID. 105 F



1 COTTAGE STYLE "B" PLUMBING PLAN

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FIXTURE TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 109.8 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

KEYED NOTES (ENTIRE SHEETS)

1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PIPING, WINDING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING PRIOR TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
2. INSTALL NEW 2 1/2" x 2 1/2" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO A.I. INDUSTRIES TO COMPLY. INSTALL PER MANUFACTURERS REQUIREMENTS.
3. DEMO EXISTING HWRWD PIPING TO EXISTING DISHWASHER.
4. CONNECT NEW DEDICATED HWRWD PIPING TO EXISTING DISHWASHER.
5. RECONNECT SINK TO EXISTING HOT WATER PIPING.
6. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.

GENERAL NOTES (ENTIRE SHEETS)

1. ROUTE ALL PIPING IN ATTIC SPACE.
2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & WATCHING.
3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 8'-0".
4. DEMO ALL EXISTING HWRWD PIPING IN ATTIC. PIPING TO BE REPLACED.
5. REFER TO DRAWING P210 FOR THE FOLLOWING DETAILS:
 - WATER METER AND WINDING VALVE

DATE	BY
4.29.13	DWG
4.29.13	COO
4.29.13	CHKD
4.29.13	INC
4.29.13	LAST UPDATE

NO. 000000

DATE



PROJECT NO. 112-089


DEPARTMENT OF ADMINISTRATIVE SERVICES
HOOPER STATE OFFICE BUILDING
1305 EAST WALNUT ST., DES MOINES, IOWA 50319

D.A.S. WOODWARD
MECHANICAL UPGRADES
1231 184TH STREET
WOODWARD, IOWA 50276

UNIT STYLE B PLUMBING PLANS

SHEET P18

BLUESTONE INC. RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, IN THIS DRAWING AND THE DATA THEREON. REUSE, REPRODUCTION, AND/OR SALE ARE THE EXCLUSIVE PROPERTY OF BLUESTONE INC. AND SHALL BE SUBJECT TO WRITTEN APPROVAL AND PARTICIPATION OF BLUESTONE INC. ©2013 BLUESTONE INC.



1 COTTAGE STYLE "C" PLUMBING DEMO PLAN


Bid. 107 F

KEYED NOTES (ENTIRE SHEET):

1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PIPING, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
2. INSTALL NEW 3/4" x 1/2" THRU-ROOF FREE HANG ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH POOL TRUSS LOCATION AND VALVE LOCATION. ACCESS PANEL TO BE EQUAL TO A INDUSTRIES PD SERIES. INSTALL PER MANUFACTURER'S REQUIREMENTS.
3. DEMO EXISTING HURAD PIPING TO EXISTING DISHWASHER.
4. CONNECT NEW DEDICATED HURAD PIPING TO EXISTING DISHWASHER.
5. DEMO EXISTING MIXING VALVE ASSEMBLY BENEATH SINK.
6. RECONNECT SINK TO EXISTING HOT WATER PIPING.
7. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.

GENERAL NOTES (ENTIRE SHEET):

1. ROUTE ALL PIPING IN ATTIC SPACE.
 2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
 3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 8'-0".
 4. DEMO ALL EXISTING HWC PIPING IN ATTIC. PIPING TO BE REPLACED.
- REFER TO DRAWING P2.0 FOR THE FOLLOWING DETAILS:
- WATER METER AND MIXING VALVE



1 COTTAGE STYLE "C" PLUMBING PLAN

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:


- DATE & TIME OF TEST
- PLUMBING FIXTURE TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 100.8 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.


BLUESTONE P&E RESERVES PROPRIETARY RIGHTS. HOLDINGS CONTAINED TO THE DRAWING AND THE CLIENT. THESE DRAWINGS AND ALL DATA ARE THE SOLE PROPERTY OF BLUESTONE P&E AND SHALL NOT BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, WITHOUT THE WRITTEN APPROVAL AND PARTICIPATION OF BLUESTONE P&E. © 2024 BLUESTONE P&E

DATE	BY	DESIGNED	CHECKED	DATE
4.28.17	JMC	JMC	JMC	4.28.17
REVISION	DATE	BY	DESCRIPTION	DATE
PROJECT NO. 112-089				
DEPARTMENT OF ADMINISTRATIVE SERVICES HOWES STATE OFFICE BUILDING 100 EAST WALNUT ST., DES MOINES, IOWA 50319				
D.A.S. WOODWARD MECHANICAL UPGRADES 1251 34TH STREET WOODWARD, IOWA 50276				
UNIT STYLE C PLUMBING PLANS				
				SHEET PIC

Bld 108 F



1 COTTAGE STYLE "A" PLUMBING DEMO PLAN
19-114



2 COTTAGE STYLE "A" PLUMBING PLAN
19-114

- KEYED NOTES (ENTIRE SHEET):**
1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PIPING, LEAKING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO EXISTING WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. PING PROVISIONS SERVICE TO ROOM.
 2. INSTALL NEW 24"x24" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO J. INDUSTRIES TO SERIES. INSTALL PER MANUFACTURER'S REQUIREMENTS.
 3. CONNECT DEDICATED MHWAD LINE TO DISHWASHER.
 4. SKYLIGHT: DO NOT ROUTE PIPING IN THIS AREA.
 5. DEMO EXISTING WRING VALVE ASSEMBLY BENEATH SINK. RECONNECT SINK TO COME/FRO HOT WATER LINE.
- GENERAL NOTES (ENTIRE SHEET):**
1. ROUTE ALL PIPING IN ATIC SPACE.
 2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & FINISHING.
 3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 8'-0".
 4. DEMO ALL EXISTING HWC PIPING IN ATIC. PIPING TO BE REPLACED.
 5. REFER TO DRAWING P2-0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MESSING VALVE

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE IN TIME OF TEST
- PLUMBING FIXTURE TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL RANGE BETWEEN 100 DEGREES AND 109.9 DEGREES AT ALL TIMES. IF SYSTEM OPER BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

PROJECT NO.	112-089
	112-089
DATE	4.23.13
BY	ENC 4.23.13
DESIGNED	ENC 4.23.13
DRAWN	ENC 4.23.13
CHECKED	ENC 4.23.13
LAST UPDATE	ENC 4.23.13

bluestone


DEPARTMENT OF ADMINISTRATIVE SERVICES
HOOPER STATE OFFICE BUILDING
1301 EAST WALNUT ST., OSAGE MORNINGS, IOWA 50209

D.A.S. WOODWARD
MECHANICAL UPGRADIES
1331 334TH STREET
WOODWARD, IOWA 50276


UNIT STYLE A PLUMBING PLANS

SHEET
P1A

BLUESTONE INC. PROVIDES PROPRIETARY HOVELS, PIPING, EQUIPMENT, AND SERVICES TO THE BUILDING INDUSTRY. ALL RIGHTS ARE RESERVED. BLUESTONE INC. AND ALL ITS SERVICES ARE THE PROPERTY OF BLUESTONE INC. AND ALL RIGHTS ARE RESERVED. NO PART OF THIS DOCUMENT OR ANY INFORMATION CONTAINED HEREIN MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, WITHOUT THE EXPRESS WRITTEN PERMISSION AND PARTICIPATION OF BLUESTONE INC. © 2013 BLUESTONE INC.



1 COTTAGE STYLE "B" PLUMBING DEMO PLAN



1 COTTAGE STYLE "B" PLUMBING PLAN

Bid. 109F

KEYED NOTES (ENTIRE SHEET):

1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PUMP, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR RECONSTRUCTION. FIRE PROTECTION SERVICE TO REMAIN.
2. INSTALL NEW 24" x 24" 1-1/2" HIGH FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS EQUAL TO J. INDUSTRIES TO SERVE. ACCESS PANEL TO BE MANUFACTURERS RECOMMENDATIONS.
3. DEMO EXISTING 1/2" x 40" PIPING TO EXISTING DISHWASHER.
4. CONNECT NEW DEDICATED 1/2" x 40" PIPING TO EXISTING DISHWASHER.
5. RECONNECT SHWR TO EXISTING HOT WATER PIPING.
6. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.

GENERAL NOTES (ENTIRE SHEET):

1. ROUTE ALL PIPING IN ATTIC SPACE.
2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 6'-0".
4. DEMO ALL EXISTING PWC PIPING IN ATTIC. PIPING TO BE REPLACED.
5. REFER TO DRAWING P&ID FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE


CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FIXTURE TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 108.5 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

BLUESTONE HAS RECEIVED PROPRIETARY RIGHTS INCLUDING PATENT RIGHTS IN THE DESIGN AND CONSTRUCTION OF THE BLUESTONE MECHANICAL UPGRADES. BLUESTONE HAS AND SHALL HAVE THE SOLE AND EXCLUSIVE RIGHT TO USE AND REPRODUCE THE DESIGN AND CONSTRUCTION OF THE BLUESTONE MECHANICAL UPGRADES. ANY REPRODUCTION OR USE OF THIS DESIGN OR CONSTRUCTION WITHOUT THE WRITTEN PERMISSION OF BLUESTONE IS PROHIBITED.

REVISION	DATE	BY	CHK	DATE	
PROJECT NO.	112-085	PROJECT NAME	D.A.S. WOODWARD MECHANICAL UPGRADES		
			1251 SIXTH STREET WOODWARD, IOWA 50276		
DRAWN BY	CHK	DATE	UNIT STYLE B PLUMBING PLANS		
				SHEET P1B	
CHECKED BY	INC	DATE	D.A.S. WOODWARD MECHANICAL UPGRADES		
				1251 SIXTH STREET WOODWARD, IOWA 50276	
LAST UPDATE	INC	DATE	UNIT STYLE B PLUMBING PLANS		
				SHEET P1B	



1 COTTAGE STYLE "C" PLUMBING DEMO PLAN
18'-0"

B/D. 200


Franklin

KEYED NOTES (ENTIRE SHEET):

1. DEMO EXISTING HOT WATER PIPING, HOT WATER REGULATION PIPING, MIXING VALVE, REGRIND/SHOUP PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE EXCHANGE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
2. INSTALL NEW 24"x24" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO A. INDUSTRIES FD SPECIES. INSTALL PER MANUFACTURERS REQUIREMENTS.
3. DEMO EXISTING HW40 PIPING TO EXISTING DISHWASHER.
4. CONNECT NEW DEDICATED HW40 PIPING TO EXISTING DISHWASHER.
5. DEMO EXISTING MIXING VALVE ASSEMBLY BENEATH SINK.
6. RECONNECT SINK TO EXISTING HOT WATER PIPING.
7. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.

GENERAL NOTES (ENTIRE SHEET):

1. ROUTE ALL PIPING IN ATTIC SPACE.
2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
3. HOT WATER PIPING DEAD LEAD LENGTH SHALL NOT EXCEED 8'-0".
4. DEMO ALL EXISTING HMC PIPING IN ATTIC. PIPING TO BE REPLACED.
5. REFER TO DRAWING P2.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE



1 COTTAGE STYLE "C" PLUMBING PLAN
18'-0"

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FIXTURES TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 105 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THE RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

BLUESSTONE P&E SERVICES PROPRIETARY. NOVELL HOLDINGS 100% OWNED. IT'S THE WAY WE DO IT. THE DATA, SPECIFICATIONS, REQUIREMENTS AND/OR SHALL BE THE SOLE PROPERTY OF BLUESSTONE P&E SERVICES. NO PARTS SHALL BE REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF BLUESSTONE P&E. © 2011 BLUESSTONE P&E

UNIT STYLE C PLUMBING PLANS

D.A.S. WOODWARD
MECHANICAL UPGRADES
1281 SOUTH STREET
WOODWARD, IOWA 50276

DEPARTMENT OF
ADMINISTRATIVE SERVICES
HOOPER STATE OFFICES BUILDING
1306 EAST WALNUT ST., DES MOINES, IOWA 50319


PROJECT NO.
112-089

bluesstone
engineers/pc

DATE: 4/29/13
BY: DMC
CHECKED: DMC
LAST UPDATE: 4/29/13

SHEET
P1C


2% Chrysotile
Sample Location



Bld. 201

Franklin

1 COTTAGE STYLE "A" PLUMBING DEMO PLAN
1/8"=1'-0"



2 COTTAGE STYLE "A" PLUMBING PLAN
1/8"=1'-0"

- KEYED NOTES (ENTIRE SHEET):**
1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PIPING, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR REIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
 2. INSTALL NEW 24"X24" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO A HANOVERSUL SERIES. INSTALL MEP MANUFACTURERS REQUIREMENTS.
 3. CONNECT DEDICATED 1/2"X1/2" LINE TO DISHWASHER.
 4. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.
 5. DEMO EXISTING MIXING VALVE ASSEMBLY BENEATH SINK. RECONNECT SINK TO DOMESTIC HOT WATER LINE.

- GENERAL NOTES (ENTIRE SHEET):**
1. ROUTE ALL PIPING IN ATTIC SPACE.
 2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
 3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 2'-0".
 4. DEMO ALL EXISTING HMC PIPING IN ATTIC. PIPING TO BE REPLACED.
 5. REFER TO DRAWING P3.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE


CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FIXTURE TESTED
- HOT WATER TEMPERATURE


HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 109.9 DEGREES AT ALL TIMES. IF SYSTEM OPERATES BELOW THIS RANGE CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

BLUESTONE INC. RESERVES PROPRIETARY RIGHTS, INCLUDING BUT NOT LIMITED TO THE DRAWING AND THE DATA HEREIN, TENDERS, BLUEPRINTS, PHOTOGRAPHS, AND ALL INFORMATION CONTAINED HEREIN. NO PART OF THIS DRAWING OR DATA MAY BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, WITHOUT THE WRITTEN APPROVAL AND PARTICIPATION OF BLUESTONE INC. © 2012 BLUESTONE INC.

DATE	BY	DESIGNED	REVISION	DATE
4.28.13	ENG	4.28.13		
4.28.13	CAD	4.28.13		
4.28.13	CHECKED	4.28.13		
4.28.13	LAST UPDATE	4.28.13		
PROJECT NO. 112-089				
DEPARTMENT OF ADMINISTRATIVE SERVICES HOOPER STATE OFFICE BUILDING 1309 EAST WALNUT ST., DES MOINES, IOWA 50319				
D.A.S. WOODWARD MECHANICAL UPGRADES 1231 334TH STREET WOODWARD, IOWA 50276				
UNIT STYLE A PLUMBING PLANS				
				SHEET P1A



1 COTTAGE STYLE "B" PLUMBING DEMO PLAN



1 COTTAGE STYLE "B" PLUMBING PLAN

Bld. 202

Franklin

001A
XX-002

001B

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FIXTURE TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 108.8 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

KEYED NOTES (ENTIRE SHEET):


1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PIPING, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
2. INSTALL NEW 2" x 1/2" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE IDENTICAL TO ALL INDUSTRIES TO SERIES. INSTALL POP IN MANUFACTURER'S REQUIREMENTS.
3. DEMO EXISTING HWRAS PIPING TO EXISTING DISHWASHER.
4. CONNECT NEW DEDICATED HWRAS PIPING TO EXISTING DISHWASHER.
5. RECONNECT SINK TO EXISTING HOT WATER PIPING.
6. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.

GENERAL NOTES (ENTIRE SHEET):


1. ROUTE ALL PIPING IN ATTIC SPACE.
2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 6'-0".
4. DEMO ALL EXISTING HWC PIPING IN ATTIC. PIPING TO BE REPLACED.
5. REFER TO DRAWING P2.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE

DATE	DATE	DATE	DATE
BY	BY	BY	BY
DESIGNED	DESIGNED	DESIGNED	DESIGNED
DRAWN	DRAWN	DRAWN	DRAWN
CHECKED	CHECKED	CHECKED	CHECKED
LAST UPDATE	LAST UPDATE	LAST UPDATE	LAST UPDATE
PROJECT NO.	PROJECT NO.	PROJECT NO.	PROJECT NO.
112-089	112-089	112-089	112-089
DEPARTMENT OF ADMINISTRATIVE SERVICES	DEPARTMENT OF ADMINISTRATIVE SERVICES	DEPARTMENT OF ADMINISTRATIVE SERVICES	DEPARTMENT OF ADMINISTRATIVE SERVICES
HOODIES STATE OFFICE BUILDING	HOODIES STATE OFFICE BUILDING	HOODIES STATE OFFICE BUILDING	HOODIES STATE OFFICE BUILDING
1305 EAST WALNUT ST., DES MOINES, IOWA 50319	1305 EAST WALNUT ST., DES MOINES, IOWA 50319	1305 EAST WALNUT ST., DES MOINES, IOWA 50319	1305 EAST WALNUT ST., DES MOINES, IOWA 50319
D.A.S. WOODWARD MECHANICAL UPGRADES	D.A.S. WOODWARD MECHANICAL UPGRADES	D.A.S. WOODWARD MECHANICAL UPGRADES	D.A.S. WOODWARD MECHANICAL UPGRADES
1251 344TH STREET WOODWARD, IOWA 50276	1251 344TH STREET WOODWARD, IOWA 50276	1251 344TH STREET WOODWARD, IOWA 50276	1251 344TH STREET WOODWARD, IOWA 50276
UNIT STYLE B PLUMBING PLANS	UNIT STYLE B PLUMBING PLANS	UNIT STYLE B PLUMBING PLANS	UNIT STYLE B PLUMBING PLANS
SHEET P1B	SHEET P1B	SHEET P1B	SHEET P1B

BLUESTONE P&C RECEIVES PROPRIETARY RIGHTS, INCLUDING EXPLOITATION TO THE MAXIMUM OF THE SAME, INCLUDING BUT NOT LIMITED TO THE RIGHT TO REPRODUCE, COPY, TRANSMIT, AND OTHERWISE USE THE CONTENTS OF THIS DRAWING AND/OR DATA, AND THE EXISTENCE OF THIS DRAWING AND/OR DATA SHALL NOT BE LIMITED BY ANY OTHER PROJECT OR CONTRACT DOCUMENTS. APPROVAL AND PARTICIPATION OF BLUESTONE P&C © 2013 BLUESTONE, INC.



1 COTTAGE STYLE "B" PLUMBING DEMO PLAN
1/8"=1'-0"



1 COTTAGE STYLE "B" PLUMBING PLAN
1/8"=1'-0"

BLD. 203

Franklin

CONTRACTOR TO CREATE BALANCE REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FIXTURE TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 104.5 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

KEYED NOTES (ENTIRE SHEET):

1. DEMO EXISTING HOT WATER PIPING, HOT WATER REDCIRCULATION PIPING, WIRING VALVE, REDCIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
2. INSTALL NEW 2" X 1/2" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO UL INDUSTRIES FD SERIES. INSTALL PER MANUFACTURER'S REQUIREMENTS.
3. DEMO EXISTING HOOKUP PIPING TO EXISTING DISHWASHER.
4. CONNECT NEW DEDICATED HOOKUP PIPING TO EXISTING DISHWASHER.
5. RECONNECT SINK TO EXISTING HOT WATER PIPING.
6. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.


GENERAL NOTES (ENTIRE SHEET):

1. ROUTE ALL PIPING IN ATRIC SPACE.
2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 6'-0".
4. DEMO ALL EXISTING HWC PIPING IN ATRIC. PIPING TO BE REPLACED.
5. REFER TO DRAWING P2.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE


BLUESTONE P&E RESERVES PROPRIETARY RIGHTS INCLUDING COPYRIGHT TO THE DRAWING AND ITS DATA. THIS DRAWING AND/OR DATA ARE THE EXCLUSIVE PROPERTY OF BLUESTONE P&E AND SHALL NOT BE LOANED, REPRODUCED, COPIED, OR OTHERWISE USED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PERMISSION OF BLUESTONE P&E.
© 2013 BLUESTONE P&E

DATE	NOVEMBER 11, 2013
BY	4.25.13
DESIGNED	4.25.13
DRAWN	4.25.13
CHECKED	4.25.13
LAST UPDATE	4.25.13
PROJECT NO.	112-089
DEPARTMENT OF ADMINISTRATIVE SERVICES HOOPER STATE OFFICE BUILDING 1265 EAST WALNUT ST., DES MOINES, IOWA 50319	
D.A.S. WOODWARD MECHANICAL UPGRADES 1253 34 TH STREET WOODWARD, IOWA 50276	
UNIT STYLE B PLUMBING PLANS	
SHEET	P1B

Bl. 202 P



1 COTTAGE STYLE "A" PLUMBING DEMO PLAN



2 COTTAGE STYLE "A" PLUMBING PLAN

KEYED NOTES (ENTIRE SHEET):

1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PIPING, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR RELOCATION. FINE PROTECTION SERVICE TO REMAIN.
2. INSTALL NEW 24"X24" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE MANUFACTURER'S REQUIREMENTS.
3. CONNECT DEDICATED 1/2"X1/2" LINE TO DISHWASHER.
4. SCHEDULE. DO NOT ROUTE PIPING IN THIS AREA.
5. DEMO EXISTING MIXING VALVE ASSEMBLY BENEATH SINK. RECONNECT SINK TO DOMESTIC HOT WATER LINE.

GENERAL NOTES (ENTIRE SHEET):

1. ROUTE ALL PIPING IN ATIC SPACE.
2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 8'-0".
4. DEMO ALL EXISTING HWC PIPING IN ATIC. PIPING TO BE REPLACED.
5. REFER TO DRAWING P10 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FEATURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FEATURE TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 109.9 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

DATE	BY	DATE
4.29.13	DWG	4.29.13
	CHKD	4.29.13
	DRWN	4.29.13
	CHGRD	DWG
		4.29.13
		LAST UPDATE


PROJECT NO. 112 689

DEPARTMENT OF ADMINISTRATIVE SERVICES
KROGER STATE OFFICE BUILDING
1305 EAST WALNUT ST., 2ND FLOOR, IOWA 50209


D.A.S. WOODWARD
MECHANICAL UPGRADES
1201 34TH STREET
WOODWARD, IOWA 50276

UNIT STYLE A PLUMBING PLANS

bluesone



1 COTTAGE STYLE "B" PLUMBING DEMO PLAN



1 COTTAGE STYLE "B" PLUMBING PLAN

Bld. 204F

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FIXTURE TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 100.8 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

KEYED NOTES (ENTIRE SHEET):

1. DEMO EXISTING HOT WATER PIPING, HOT WATER RE-CIRCULATION PIPING, HOT WATER RE-CIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
2. INSTALL NEW 24"x24" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO U.S. INDUSTRIES PD SPECIES. INSTALL PDP MANUFACTURERS REQUIREMENTS.
3. DEMO EXISTING HORIZONTAL PIPING TO EXISTING DISHWASHER.
4. CONNECT NEW DEDICATED HORIZONTAL PIPING TO EXISTING DISHWASHER.
5. RECONNECT SHUK TO EXISTING HOT WATER PIPING.
6. DRYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.


GENERAL NOTES (ENTIRE SHEET):

1. ROUTE ALL PIPING IN ATTIC SPACE.
2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 6'-0".
4. DEMO ALL EXISTING HING PIPING IN ATTIC. PIPING TO BE REPLACED.
5. REFER TO DRAWING P2.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE


DATE	4.29.13
BY	DMC
DESIGNED	DMC
DRAWN	DMC
CHECKED	DMC
LAST UPDATE	4.29.13
REASON	
DATE	
BY	
DESIGNED	
DRAWN	
CHECKED	
LAST UPDATE	
PROJECT NO.	112-080
DEPARTMENT OF ADMINISTRATIVE SERVICES	
HOOVER STATE OFFICE BUILDING	
1308 EAST WALNUT ST., DES MOINES, IOWA 50319	
UNIT STYLE B PLUMBING PLANS	
D.A.S. WOODWARD MECHANICAL UPGRADES	
1251 34TH STREET	
WOODWARD, IOWA 50276	
SHEET	P1B

BLUESTONE INC. RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHT, IN THE DRAWING AND THE DATA THEREON. BLUESTONE INC. AND SHALL BE THE SOLE PROPERTY OF BLUESTONE INC. FOR ANY OTHER PROJECT, WITHOUT THE WRITTEN APPROVAL AND PARTICIPATION OF BLUESTONE INC. © 2013 BLUESTONE INC.

Bid. 301
Pine



1 COTTAGE STYLE "A" PLUMBING DEMO PLAN
1/8"=1'-0"



2 COTTAGE STYLE "A" PLUMBING PLAN
1/8"=1'-0"

- KEYED NOTES (ENTIRE SHEET):**
1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECYCLATION PIPING, ISING VALVE, RECYCLATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
 2. INSTALL NEW 24"x24" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO U.S. ROOFING'S TD SERIES. INSTALL PER MANUFACTURER'S REQUIREMENTS.
 3. CONNECT DEDICATED HW40 LINE TO DSHWASHER.
 4. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.
 5. DEMO EXISTING URING VALVE ASSEMBLY BENEATH PINK RECONNECT SINK TO DOMESTIC HOT WATER LINE.
- GENERAL NOTES (ENTIRE SHEET):**
1. ROUTE ALL PIPING IN ATTIC SPACE.
 2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
 3. HOT WATER PIPING DEAD LED LENGTH SHALL NOT EXCEED 4'-0"
 4. DEMO ALL EXISTING HW40 PIPING IN ATTIC. PIPING TO BE REPLACED.
 5. REFER TO DRAWING P2.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FIXTURE TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 100.9 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

BLUESTONE P&E RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, TO THE DRAWINGS AND THE DATA HEREIN. THESE DRAWINGS, SPECIFICATIONS AND THE CONTENTS THEREOF ARE THE PROPERTY OF BLUESTONE P&E AND SHALL BE USED EXCLUSIVELY FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF BLUESTONE P&E.
© 2014 BLUESTONE P&E

DATE	BY	REVISION	DATE	BY	REVISION
4.2.13.1	INC				
4.2.13.2	CAR				
4.2.13.3	INC				
4.2.13.4	INC				
4.2.13.5	INC				
4.2.13.6	INC				
4.2.13.7	INC				
4.2.13.8	INC				
4.2.13.9	INC				
4.2.13.10	INC				
4.2.13.11	INC				
4.2.13.12	INC				
4.2.13.13	INC				
4.2.13.14	INC				
4.2.13.15	INC				
4.2.13.16	INC				
4.2.13.17	INC				
4.2.13.18	INC				
4.2.13.19	INC				
4.2.13.20	INC				
4.2.13.21	INC				
4.2.13.22	INC				
4.2.13.23	INC				
4.2.13.24	INC				
4.2.13.25	INC				
4.2.13.26	INC				
4.2.13.27	INC				
4.2.13.28	INC				
4.2.13.29	INC				
4.2.13.30	INC				
4.2.13.31	INC				
4.2.13.32	INC				
4.2.13.33	INC				
4.2.13.34	INC				
4.2.13.35	INC				
4.2.13.36	INC				
4.2.13.37	INC				
4.2.13.38	INC				
4.2.13.39	INC				
4.2.13.40	INC				
4.2.13.41	INC				
4.2.13.42	INC				
4.2.13.43	INC				
4.2.13.44	INC				
4.2.13.45	INC				
4.2.13.46	INC				
4.2.13.47	INC				
4.2.13.48	INC				
4.2.13.49	INC				
4.2.13.50	INC				
4.2.13.51	INC				
4.2.13.52	INC				
4.2.13.53	INC				
4.2.13.54	INC				
4.2.13.55	INC				
4.2.13.56	INC				
4.2.13.57	INC				
4.2.13.58	INC				
4.2.13.59	INC				
4.2.13.60	INC				
4.2.13.61	INC				
4.2.13.62	INC				
4.2.13.63	INC				
4.2.13.64	INC				
4.2.13.65	INC				
4.2.13.66	INC				
4.2.13.67	INC				
4.2.13.68	INC				
4.2.13.69	INC				
4.2.13.70	INC				
4.2.13.71	INC				
4.2.13.72	INC				
4.2.13.73	INC				
4.2.13.74	INC				
4.2.13.75	INC				
4.2.13.76	INC				
4.2.13.77	INC				
4.2.13.78	INC				
4.2.13.79	INC				
4.2.13.80	INC				
4.2.13.81	INC				
4.2.13.82	INC				
4.2.13.83	INC				
4.2.13.84	INC				
4.2.13.85	INC				
4.2.13.86	INC				
4.2.13.87	INC				
4.2.13.88	INC				
4.2.13.89	INC				
4.2.13.90	INC				
4.2.13.91	INC				
4.2.13.92	INC				
4.2.13.93	INC				
4.2.13.94	INC				
4.2.13.95	INC				
4.2.13.96	INC				
4.2.13.97	INC				
4.2.13.98	INC				
4.2.13.99	INC				
4.2.13.100	INC				

SHEET
P1A

PROJECT NO.
112-089

DEPARTMENT OF
ADMINISTRATIVE SERVICES
HOOVER'S STATE OFFICE BUILDING
1305 EAST WALNUT ST., DES MOINES, IOWA 50319



D.A.S. WOODWARD
MECHANICAL UPGRADES
1251 164TH STREET
WOODWARD, IOWA 50276

UNIT STYLE A PLUMBING PLANS

SHEET
P1A

Bld. 302

Pine



KEYED NOTES (ENTIRE SHEET):

1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PIPING, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION REMAINS TO REMAIN.
2. INSTALL NEW 24"x24" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO & INSTALLED TO SERIES. INSTALL PER MANUFACTURER'S REQUIREMENTS.
3. CONNECT DEDICATED DWV40 LINE TO OSHKUBER.
4. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.
5. DEMO EXISTING MIXING VALVE ASSEMBLY BENEATH SINK. RECONNECT SINK TO DOMESTIC HOT WATER LINE.

GENERAL NOTES (ENTIRE SHEET):

1. ROUTE ALL PIPING IN ATTIC SPACE.
2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 8'-0".
4. DEMO ALL EXISTING HMC PIPING IN ATTIC. PIPING TO BE REPLACED.
5. REFER TO DRAWING P3.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FEATURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FEATURE TESTED
- HOT WATER TEMPERATURE


HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 100.8 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

BLUESTONE P&E RECEIVES PROPRIETARY RIGHTS INCLUDING COPYRIGHT, BY THE DESIGN AND THE DESIGN AND/OR INVENTION. ALL RIGHTS ARE RESERVED AND WILL NOT BE USED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF BLUESTONE P&E.
© 2018 BLUESTONE P&E


DATE	DATE	BY	DATE	DATE	DATE	DATE	
		ENG	4.23.13	ENG	4.23.13	ENG	4.23.13
		DRAWN	CAD	CHKD	CHKD	CHKD	CHKD
		CHECKED	CHKD	CHKD	CHKD	CHKD	CHKD
		LAST UPDATE	DATE	DATE	DATE	DATE	DATE
PROJECT NO. 112-059							
DEPARTMENT OF ADMINISTRATIVE SERVICES HOOPER STATE OFFICE BUILDING 1308 EAST WALNUT ST., DES MOINES, IOWA 50319							
D.A.S. WOODWARD MECHANICAL UPGRADES 1251 34TH STREET WOODWARD, IOWA 50276							
UNIT STYLE A PLUMBING PLANS							
SHEET P1A							

Bld. 303

Pine



1 COTTAGE STYLE "A" PLUMBING DEMO PLAN



2 COTTAGE STYLE "A" PLUMBING PLAN

KEYED NOTES (ENTIRE SHEET):

1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PANEL, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
2. INSTALL NEW 24"x24" 1-HOUR FIRE RATED ACCESS PANEL IN CELLING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO A. INDUSTRIES TO SERIALS. INSTALL PER MANUFACTURER'S REQUIREMENTS.
3. CONNECT DEDICATED HW400 LINE TO DISHWASHER
4. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.
5. DEMO EXISTING MIXING VALVE ASSEMBLY BENEATH SINK. RECONNECT SINK TO DOMESTIC HOT WATER LINE.

GENERAL NOTES (ENTIRE SHEET):

1. ROUTE ALL PIPING BY ATTIC SPACE.
2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 6'-0"
4. DEMO ALL EXISTING HWG PIPING IN ATTIC. PIPING TO BE REPLACED.
5. REFER TO DRAWING P2.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FIXTURE TESTED
- HOT WATER TEMPERATURE


HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 190 DEGREES AND 198.8 DEGREES AT ALL TEST LOCATIONS. CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

BLUESTONE P&E RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, IN THIS DRAWING AND THE DATA FROM THIS DRAWING. NO PART OF THIS DRAWING OR THE INFORMATION CONTAINED HEREIN IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF BLUESTONE P&E. © 2013 BLUESTONE P&E


DATE	4.29.11
BY	4.29.11
DESIGNED	4.29.11
DRAWN	4.29.11
CHECKED	4.29.11
LAST UPDATE	4.29.13
PROJECT NO.	112-859
DEPARTMENT OF ADMINISTRATIVE SERVICES	
HOOPER STATE OFFICE BUILDING	
1306 EAST WALNUT ST., DES MOINES, IOWA 50319	
D.A.S. WOODWARD MECHANICAL UPGRADES	
1251 34TH STREET	
WOODWARD, IOWA 50276	
UNIT STYLE A PLUMBING PLANS	
SHEET	PIA

Bld. 304

Pine



1 COTTAGE STYLE "A" PLUMBING DEMO PLAN



2 COTTAGE STYLE "A" PLUMBING PLAN

- KEYED NOTES (ENTIRE SHEET):**
1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PIPING, HEATING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FINE PROTECTION SOURCE TO REMAIN.
 2. INSTALL NEW 2 1/2" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO & INSTALLED TO CODES. INSTALL PER MANUFACTURER'S REQUIREMENTS.
 3. CONNECT DEDICATED 1/2" CWI LINE TO DISHWASHER.
 4. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.
 5. DEMO EXISTING MIXING VALVE ASSEMBLY BENEATH SINK. RECONNECT SINK TO DOMESTIC HOT WATER LINE.

- GENERAL NOTES (ENTIRE SHEET):**
1. ROUTE ALL PIPING IN ATTIC SPACE.
 2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
 3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 8'-0".
 4. DEMO ALL EXISTING HMC PIPING IN ATTIC. PIPING TO BE REPLACED.
 5. REFER TO DRAWING P3.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FEATURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:


- DATE & TIME OF TEST
- PLUMBING FEATURE TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 120 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.


PROJECT NO.	112-089
	112-089
DEPARTMENT OF ADMINISTRATIVE SERVICES HOOPER STATE OFFICE BUILDING 1306 EAST WALNUT ST., DES MOINES, IOWA 50319	DATE
	4.19.13
UNIT STYLE A PLUMBING PLANS	BY
	ENC
D.A.S. WOODWARD MECHANICAL UPGRADES 1251 334TH STREET WOODWARD, IOWA 50276	REVISION
	ENC
SHEET PIA	DATE
	4.23.13
BLUESTONE INC. RESERVES PROPRIETARY RIGHTS INCLUDING COPYRIGHT, IN THE DRAWING AND THE DATA THEREIN. BLUESTONE INC. AND ALL ITS AFFILIATES SHALL BE THE SOLE PROPERTY OF THE AFFILIATED PROJECT OWNER. NO REPRODUCTION, APPROVAL, AND PARTICIPATION OF BLUESTONE INC. OR ITS AFFILIATES.	CHECKED
	ENC
BLUESTONE INC. 1111 UNIVERSITY AVENUE DES MOINES, IOWA 50319 515.281.1000 www.bluestoneinc.com	LAST UPDATE
	4.23.13

Bld. 103 EC

Cedar St



1 COTTAGE STYLE "A" PLUMBING DEMO PLAN
1/8"=1'-0"



2 COTTAGE STYLE "A" PLUMBING PLAN
1/8"=1'-0"

- KEYED NOTES (ENTIRE SHEET):**
1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PIPING, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
 2. INSTALL NEW 24"X24" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TROSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO A.I.A. INDUSTRIES FD SERIES. INSTALL PER MANUFACTURER'S REQUIREMENTS.
 3. CONNECT DEDICATED MIXING VALVE TO DISHWASHER.
 4. SKYLIGHT: DO NOT ROUTE PIPING IN THIS AREA.
 5. DEMO EXISTING MIXING VALVE ASSEMBLY BENEATH SINK. RECONNECT SINK TO DOMESTIC HOT WATER LINE.
- GENERAL NOTES (ENTIRE SHEET):**
1. ROUTE ALL PIPING IN ATTIC SPACE.
 2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
 3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 8'-0"
 4. DEMO ALL EXISTING HMD PIPING IN ATTIC. PIPING TO BE REPLACED.
 5. REFER TO DRAWING P200 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FEATURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FEATURE TESTED
- HOT WATER TEMPERATURE


HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 100.5 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

BLUESTONE P&E RETAINS PROPRIETARY RIGHTS INCLUDING COPYRIGHTS IN THE DRAWING AND THE DATA THEREIN. NO DRAWING, PART OR DATA ARE THE EXCLUSIVE PROPERTY OF BLUESTONE P&E AND SHALL NOT BE USED OR REPRODUCED IN ANY MANNER WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF BLUESTONE P&E. ©2016 BLUESTONE P&E


DATE	BY	DATE	PROJECT NO.
	DESIGNED	11/2/13	
REVISION	DRAWN	CHECKED	DEPARTMENT OF ADMINISTRATIVE SERVICES IOWA STATE OFFICE BUILDING 1805 EAST WALNUT ST., DES MOINES, IOWA 50319
			D.A.S. WOODWARD MECHANICAL UPGRADES 1251 34TH STREET WOODWARD, IOWA 50276
UNIT STYLE A PLUMBING PLANS			
SHEET P1A			

Bid. 201N

Cedar St.



1 COTTAGE STYLE "A" PLUMBING DEMO PLAN



2 COTTAGE STYLE "A" PLUMBING PLAN

- KEYED NOTES (ENTIRE SHEET):**
1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PIPING, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICES TO REMAIN.
 2. INSTALL NEW 24" X 24" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO & INDUSTRIES' TO SERIES. INSTALL PER MANUFACTURERS REQUIREMENTS.
 3. CONNECT DEDICATED HW40 LINE TO DISHWASHER.
 4. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.
 5. DEMO EXISTING MIXING VALVE ASSEMBLY BENEATH SINK. RECONNECT SINK TO DOMESTIC HOT WATER LINE.

- GENERAL NOTES (ENTIRE SHEET):**
1. ROUTE ALL PIPING IN ATTIC SPACE.
 2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
 3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 8'-0".
 4. DEMO ALL EXISTING HMC PIPING IN ATRC. PIPING TO BE REPLACED.
 5. REFER TO DRAWING P2.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FITURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:


- DATE & TIME OF TEST
- PLUMBING FITURE TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 100.8 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.


BLUESTONE PLS. RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHTS, IN THE DRAWING AND THE DATA HEREIN. THESE DRAWINGS AND/OR DATA ARE THE SOLE PROPERTY OF BLUESTONE PLS. AND SHALL NOT BE USED OR REPRODUCED FOR ANY OTHER PROJECT WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF BLUESTONE PLS. © 2015 BLUESTONE PLS.

DATE	BY	DESIGNED	CHECKED	LAST UPDATE
4.25.15	INC	INC	INC	4.25.13
DATE	BY	DESIGNED	CHECKED	LAST UPDATE
PROJECT NO. 112-089 DEPARTMENT OF ADMINISTRATIVE SERVICES HOOPER STATE OFFICE BUILDING 1905 EAST WALNUT ST., DES MOINES, IOWA 50319 D.A.S. WOODWARD MECHANICAL UPGRADES 1251 34TH STREET WOODYARD, IOWA 50276				
UNIT STYLE A PLUMBING PLANS				
				SHEET PIA

BID. 101
Cherry Ln.



1 COTTAGE STYLE "A" PLUMBING DEMO PLAN



2 COTTAGE STYLE "A" PLUMBING PLAN

- KEYED NOTES (ENTIRE SHEET):**
1. DEMO EXISTING HOT WATER PIPING, WOI WATER RECIRCULATION PUMP, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO EXISTING WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
 2. INSTALL NEW 24"x24" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO A INDUSTRIES TO SERIES. INSTALL PER MANUFACTURER'S REQUIREMENTS.
 3. CONNECT DEDICATED PWH45 LINE TO DSHWASHER.
 4. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.
 5. DEMO EXISTING MIXING VALVE ASSEMBLY BENEATH SINK. RECONNECT SINK TO DOMESTIC HOT WATER LINE.

- GENERAL NOTES (ENTIRE SHEET):**
1. ROUTE ALL PIPING IN ATTIC SPACE.
 2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
 3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 8'-0".
 4. DEMO ALL EXISTING HMC PIPING IN ATTIC. PIPING TO BE REPLACED.
 5. REFER TO DRAWING #2.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FEATURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FEATURE TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 108.8 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

BLUESTONE P.L.L.C. RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHT, IN THE DRAWING AND THE DATA THEREON. NO PARTING, REUSE, OR DISSEMINATION OF THIS DRAWING OR DATA IS PERMITTED WITHOUT THE WRITTEN APPROVAL AND PARTICIPATION OF BLUESTONE P.L.L.C. ©2020 BLUESTONE P.L.L.C.

DATE	BY	DISCLOSED	REVISION	DATE
4.29.13	INC	4.29.13		
	CAD	4.29.13		
	DRAWN	4.29.13		
	CHECKED	4.29.13		
	INC	4.29.13		
	LAST UPDATE	4.29.13		


PROJECT NO. 112-050

DEPARTMENT OF ADMINISTRATIVE SERVICES
HOOVER STATE OFFICE BUILDING
1305 EAST WALNUT ST., DES MOINES, IOWA 50319

D.A.S. WOODWARD
MECHANICAL UPGRADES
1251 34TH STREET
WOODWARD, IOWA 50276


UNIT STYLE A PLUMBING PLANS

SHEET P1A



1 COTTAGE STYLE "A" PLUMBING DEMO PLAN

Bld. 103
Cherry Ln.



2 COTTAGE STYLE "A" PLUMBING PLAN

- KEYED NOTES (ENTIRE SHEET):**
- DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PANEL, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSIBLES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
 - INSTALL NEW 24"x24" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND HANGERS LOCATION. ACCESS PANEL TO BE EQUAL TO A HIDEITILE TO SERIES. INSTALL PER MANUFACTURERS REQUIREMENTS.
 - CONNECT DEDICATED 1/2" CWI LINE TO DISHWASHER.
 - EXTINGUISH DO NOT ROUTE PIPING IN THIS AREA.
 - DEMO EXISTING MIXING VALVE ASSEMBLY BENEATH SINK. RECONNECT SINK TO DOMESTIC HOT WATER LINE.
- GENERAL NOTES (ENTIRE SHEET):**
- ROUTE ALL PIPING IN ATTIC SPACE.
 - PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
 - HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 2'-10"
 - DEMO ALL EXISTING HWS PIPING IN ATTIC. PIPING TO BE REPLACED.
 - REFER TO DRAWING P20 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE


CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE IN TIME OF TEST
- PLUMBING FIXTURE TESTED
- HOT WATER TEMPERATURE


HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 100.8 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

BLUESTONE PNE RECEIVES PROPRIETARY RIGHTS, INCLUDING COMPENSATION TO THE DRAWING AND THE DATA FROM THE ORIGINAL CONTRACTOR. BLUESTONE PNE SHALL NOT BE HELD RESPONSIBLE FOR ANY OTHER PROJECTS IN WHICH THE CONTRACTOR OBTAINS APPROVAL AND PARTICIPATION OF BLUESTONE PNE.

 bluestone <small>PNE</small>	DATE	4.29.13
	BY	4.29.13
	DESIGNED	4.29.13
	DRAWN	4.29.13
PROJECT NO.	112-089	
DEPARTMENT OF ADMINISTRATIVE SERVICES HOOPER STATE OFFICE BUILDING 1201 EAST WALNUT ST., DES MOINES, IOWA 50319		
D.A.S. WOODWARD MECHANICAL UPGRADES 1201 EAST WALNUT STREET WOODWARD, IOWA 50375		
UNIT STYLE A PLUMBING PLANS		
SHEET P1A		



1 COTTAGE STYLE "B" PLUMBING DEMO PLAN



1 COTTAGE STYLE "B" PLUMBING PLAN

Bld. W4C

Cherry Ln.

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FIXTURES TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 108.8 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

KEYED NOTES (ENTIRE SHEET):

1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PIPING, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
2. INSTALL NEW 2 1/2" x 2 1/2" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO & MONITORED TO SERVICE. INSTALL PER MANUFACTURERS REQUIREMENTS.
3. DEMO EXISTING HWM40 PIPING TO EXISTING DISHWASHER.
4. CONNECT NEW DEDICATED HWM40 PIPING TO EXISTING DISHWASHER.
5. RECONNECT SINK TO EXISTING HOT WATER PIPING.
6. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.

GENERAL NOTES (ENTIRE SHEET):

1. ROUTE ALL PIPING IN ATTIC SPACE.
2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 8'-0".
4. DEMO ALL EXISTING HMO PIPING IN ATTIC. PIPING TO BE REPLACED.
5. REFER TO DRAWING P2.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE

BY	DATE
ENG	4.29.13
CAD	4.29.13
CHK	4.29.13
INC	4.29.13

REVISION

DATE



PROJECT NO.
112-989


DEPARTMENT OF
ADMINISTRATIVE SERVICES
HOOPER STATE OFFICES BUILDING
1308 EAST WALNUT ST., DES MOINES, IOWA 50319

D.A.S. WOODWARD
MECHANICAL UPGRADES
1231 34TH STREET
WOODWARD, IOWA 50276


UNIT STYLE B PLUMBING PLANS

SHEET
P1B

BLUESTONE P&E RESERVES PROPRIETARY RIGHTS, INCLUDING COPYRIGHT, IN THE ORIGINAL AND ALL REVISIONS THEREOF. NO PART OF THIS DOCUMENT IS TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF BLUESTONE P&E.
©2013 BLUESTONE P&E



1 COTTAGE STYLE "B" PLUMBING DEMO PLAN
18" x 24"



1 COTTAGE STYLE "B" PLUMBING PLAN
18" x 24"

Bld. 105

Cherry Ln.

KEYED NOTES (ENTIRE SHEET):

1. DEMO EXISTING HOT WATER PIPING, HOT WATER RECIRCULATION PIPING, MIXING VALVE, RECIRCULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO DOMESTIC WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
2. INSTALL NEW 24"x24" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATIONS. ACCESS PANEL TO BE EQUAL TO & INSTALLED TO COMPLY WITH PER MANUFACTURER'S REQUIREMENTS.
3. DEMO EXISTING HWR40 PIPING TO EXISTING DISHWASHER.
4. CONNECT NEW DEBELLATED HWR40 PIPING TO EXISTING DISHWASHER.
5. RECONNECT SINK TO EXISTING HOT WATER PIPING.
6. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.

GENERAL NOTES (ENTIRE SHEET):

1. ROUTE ALL PIPING IN ATTIC SPACE.
2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION BENDS & PATCHING.
3. HOT WATER PIPING DEAD LEG LENGTH SHALL NOT EXCEED 8'-0".
4. DEMO ALL EXISTING HWC PIPING IN ATTIC. PIPING TO BE REPLACED.
5. REFER TO DRAWING P2.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:


- DATE & TIME OF TEST
- PLUMBING FIXTURE TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 160 DEGREES AND 180 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

BLUESTONE P&E RETAINS PROPRIETARY RIGHTS, INCLUDING BUT NOT LIMITED TO THE DESIGN AND THE DATA SHOWN HEREON. NO PART OF THIS DRAWING SHALL BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE EXPRESS WRITTEN PERMISSION AND PARTICIPATION OF BLUESTONE P&E.
© 2011 BLUESTONE P&E

REVISION	DATE	BY	DATE
	DESCRIBED	CHKD	DATE
NO.	DATE	BY	DATE
1	4.29.11	ENG	4.29.11
2	4.29.11	COO	4.29.11
3	4.29.11	CHKD	4.29.11
4	4.29.11	ENG	4.29.11
LAST UPDATE: 4.29.11			
PROJECT NO. 112-680			
DEPARTMENT OF ADMINISTRATIVE SERVICES ILLINOIS STATE OFFICE BUILDING 1305 EAST WALNUT ST., DES MOINES, IOWA 50319			
D.A.S. WOODWARD MECHANICAL UPGRADES 1251 34TH STREET WOODWARD, IOWA 50276			
UNIT STYLE B PLUMBING PLANS			
SHEET P1B			

W



1 COTTAGE STYLE "C" PLUMBING DEMO PLAN

Bld. 101


Cherry Ln.

KEYED NOTES (ENTIRE SHEET):

1. DEMO EXISTING HOT WATER PIPING, HOT WATER REGULATION PIPING, MIXING VALVE, REGULATION PUMP, AND ACCESSORIES IN THIS AREA. CONTRACTOR TO DEMO EXISTING WATER PIPING BACK TO WATER SERVICE ENTRANCE FOR MODIFICATION. FIRE PROTECTION SERVICE TO REMAIN.
2. INSTALL NEW 24" x 24" 1-HOUR FIRE RATED ACCESS PANEL IN CEILING. COORDINATE LOCATION WITH ROOF TRUSS LOCATIONS AND VALVE LOCATION. ACCESS PANEL TO BE INSTALLED TO MEET MANUFACTURER'S REQUIREMENTS.
3. DEMO EXISTING 1/2" x 1/2" PIPING TO EXISTING DISHWASHER.
4. CONNECT NEW DEDICATED 1/2" x 1/2" PIPING TO EXISTING DISHWASHER.
5. DEMO EXISTING MIXING VALVE ASSEMBLY BENEATH SINK.
6. RECONNECT SINK TO EXISTING HOT WATER PIPING.
7. SKYLIGHT. DO NOT ROUTE PIPING IN THIS AREA.

GENERAL NOTES (ENTIRE SHEET):

1. ROUTE ALL PIPING IN ATTIC SPACE.
2. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR ALL GENERAL CONSTRUCTION DEMO & PATCHING.
3. HOT WATER PIPING DEMO LEAD LENGTH SHALL NOT EXCEED 8'-0".
4. DEMO ALL EXISTING HVAC PIPING IN ATTIC. PIPING TO BE REPLACED.
5. REFER TO DRAWING P2.0 FOR THE FOLLOWING DETAILS:
 - WATER METER AND MIXING VALVE



1 COTTAGE STYLE "C" PLUMBING PLAN

CONTRACTOR TO CREATE BALANCING REPORT FOR ALL PLUMBING FIXTURES. REPORT SHALL LIST THE FOLLOWING INFORMATION:

- DATE & TIME OF TEST
- PLUMBING FIXTURES TESTED
- HOT WATER TEMPERATURE

HOT WATER TEMPERATURE SHALL REMAIN BETWEEN 100 DEGREES AND 100.8 DEGREES AT ALL TIMES. IF SYSTEM DIPS BELOW THIS RANGE, CONTRACTOR SHALL RE-BALANCE ENTIRE PLUMBING SYSTEM WITHIN THE BUILDING.

BLUESTONE P&C RESERVE PROPRIETARY RIGHTS INCLUDING COPYRIGHTS IN THE DRAWING AND ALL RIGHTS RESERVED. THIS DRAWING AND/OR DATA ARE THE SOLE PROPERTY OF BLUESTONE P&C AND SHALL NOT BE USED OR REPRODUCED IN ANY MANNER WITHOUT THE EXPRESS WRITTEN APPROVAL AND PARTICIPATION OF BLUESTONE P&C. © 2016 BLUESTONE P&C

SHEET
PIC

UNIT STYLE C PLUMBING PLANS

D.A.S. WOODWARD
MECHANICAL UPGRADES
1251 34TH STREET
WOODWARD, IOWA 50276

DEPARTMENT OF
ADMINISTRATIVE SERVICES
IOWA'S STATE OFFICE BUILDING
1305 EAST WALNUT ST., DES MOINES, IOWA 50319

PROJECT NO.
112-089

bluestone
engineers

DATE

REVISION

DESIGNED BY
DRAWN BY
CHECKED BY
LAST UPDATE

DATE
BY
CHK
DATE
CHK
DATE
CHK
DATE
CHK

November 10, 2022

Woodward Resource Center
ATTN: Mr. Rodney Carr
Facility Manager
1251 334th Street
Woodward, IA 50276

RE: Woodward Resource Center – Myers Hall – Asbestos Survey & Paint Chip Sampling

Dear Mr. Carr:

Per your request and authorization, Shive-Hattery, Inc. performed an asbestos survey and paint chip sampling for the above referenced project on October 25, 2022. It is our understanding that the building will undergo renovations that may disturb suspect asbestos-containing building materials and potential lead-based paint. It was the intent of the survey to determine what materials within the project area contain asbestos and lead.

Methods and Procedures

The review for this project was performed by personnel trained and certified under the National Emission Standards for Hazardous Air Pollutants (NESHAP) regulations. Partial or destructive testing was not performed to reveal concealed conditions.

A sample from each suspect homogeneous area was collected from the project areas at Woodward Resource Center Myers Hall. Pertinent information such as location, color, etc. was recorded for each suspect material. The samples were then sent to an NAVLAP accredited laboratory for analysis.

The samples were analyzed for asbestos fibers utilizing the Polarized Light Microscopy method of analysis by EMLab P&K of Phoenix, AZ. Each sample was analyzed for the six different types of fibrous asbestos forms of which a percentage, by volume, is estimated and summarized. As defined by the U.S. Environmental Protection Agency mandated NESHAP regulations, the suspect material is considered an asbestos-containing material (ACM) if the material contains more than 1.0 percent of any one or a combination of asbestos fibers.

A composite bulk paint chip sample from suspect painted substrate areas was collected from project areas at Myers Hall. The bulk sample was sent to an AIHA accredited laboratory for analysis.

The bulk sample was analyzed for lead-based paint using flame atomic absorption spectrometry (Flame AA) under NIOSH 7082 and EPA 7000B modified, by EMLab P&K of Phoenix, AZ. Flame AA provides the most economical means of determining at risk environments to lead exposure. The EPA mandated method reporting limit for lead-based paint is 39 ppm (parts per million). Paint is lead containing at 0.5% by weight or 5,000 parts per million (ppm).

Pertinent information for each bulk sample has been summarized on the sample analytical results which can be found at the end of this report.



Summary of Findings

Eighteen (18) samples were collected from 25 homogeneous areas located at Woodward Resource Center Myers Hall. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. Cream Floor Tile 12"x12"	0%
2. Yellow Mastic	0%
3. Light Gray Floor Tile 12"x12"	0%
4. Yellow mastic	0%
5. Yellow Floor Tile 12"x12"	0%
6. Yellow Mastic	0%
7. Orange Floor Tile 12"x12"	0%
8. Yellow Mastic	0%
9. Blue Floor Tile 12"x12"	0%
10. Yellow Mastic	0%
11. Red Floor Tile 12'x12"	0%
12. Yellow Mastic	0%
13. Blue Ceramic Wall Tile	0%
14. Yellow Mastic	0%
15. Yellow Mastic a/w Black Cove Base	0%
16. White Wall Compound w/ Multilayered Paint	0%
17. Transparent Mastic	0%
18. Gray Leveling Compound	0%
19. White Compound w/ White Paint	0%
20. Cream Tape	0%
21. White Joint Compound	0%
22. White Drywall w/ Brown Paper	0%
23. Gray Wall	0%
24. Gray Ceiling Plaster	0%
25. White Ceiling Tile 2'x2'	0%

Lead-based Paint Analysis

Sample Results

1. Bulk Paint Chip Sample (Myers Hall)	<39 ppm
--	---------

Recommendations

Thus, it appears that the proposed project will not disturb any asbestos-containing materials and asbestos abatement is not required. There was also no paint identified as lead-containing within the project area.

Please call our office if you should have any questions or comments.

Sincerely,

SHIVE-HATTERY, INC.



Grant W. Bridgford
License Number IA 22-7928 INSP
Expiration Date: February 10, 2023

And



Samuel Becker
Environmental Specialist
Lead Inspector/Risk Assessor
LEAD-INSP10002

GWB/SSB/mas

Encs.

Copy: Chad Siems, S-H

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Myers Hall; 2142203390
EML ID: 3071854

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Myers Hall; 2142203390

Date of Sampling: 10-25-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted: 18
Total Samples Analyzed: 18
Total Samples with Layer Asbestos Content > 1%: 0

Location: MH.HA.001, Cream W/Specks 12"X12" VFT W/Mastic Lab ID-Version‡: 14821608-1

Sample Layers	Asbestos Content
Cream Floor Tile	ND
Yellow Mastic	ND
Sample Composite Homogeneity:	Moderate

Location: MH.HA.002, Light Gray W/Specks 12"X12" VFT W/Mastic Lab ID-Version‡: 14821609-1

Sample Layers	Asbestos Content
Light Gray Floor Tile	ND
Yellow Mastic	ND
Sample Composite Homogeneity:	Moderate

Location: MH.HA.003, Yellow 12"X12" VFT W/Mastic Lab ID-Version‡: 14821610-1

Sample Layers	Asbestos Content
Yellow Floor Tile	ND
Yellow Mastic	ND
Sample Composite Homogeneity:	Moderate

Location: MH.HA.004, Orange 12"X12" VFT W/Mastic Lab ID-Version‡: 14821611-1

Sample Layers	Asbestos Content
Orange Floor Tile	ND
Yellow Mastic	ND
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Myers Hall; 2142203390

Date of Sampling: 10-25-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Location: MH.HA.005, Blue 12"X12" VFT W/Mastic

Lab ID-Version‡: 14821612-1

Sample Layers	Asbestos Content
Blue Floor Tile	ND
Yellow Mastic	ND
Sample Composite Homogeneity: Moderate	

Location: MH.HA.006, Red 12"X12" VFT W/Mastic

Lab ID-Version‡: 14821613-1

Sample Layers	Asbestos Content
Red Floor Tile	ND
Yellow Mastic	ND
Sample Composite Homogeneity: Moderate	

Location: MH.HA.007, Ceramic Wall Tile W/Mastic

Lab ID-Version‡: 14821614-1

Sample Layers	Asbestos Content
Blue Ceramic Tile	ND
Yellow Mastic	ND
Sample Composite Homogeneity: Moderate	

Location: MH.HA.008, Yellow Mastic A/W Black Cove Base

Lab ID-Version‡: 14821615-1

Sample Layers	Asbestos Content
Yellow Mastic	ND
White Compound with Multilayered Paint	ND
Sample Composite Homogeneity: Moderate	

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Myers Hall; 2142203390

Date of Sampling: 10-25-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Location: MH.HA.009, Gray Leveling Compound

Lab ID-Version‡: 14821616-1

Sample Layers	Asbestos Content
Transparent Mastic	ND
Gray Leveling Compound	ND
Sample Composite Homogeneity: Moderate	

Location: MH.HA.010, Sheetrock & Joint Compound

Lab ID-Version‡: 14821616-1

Sample Layers	Asbestos Content
White Compound with White Paint	ND
Cream Tape	ND
White Joint Compound	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	15% Cellulose
Sample Composite Homogeneity:	Poor

Location: MH.HA.011A, Plaster Walls & Ceilings

Lab ID-Version‡: 14821618-1

Sample Layers	Asbestos Content
Gray Plaster	ND
Composite Non-Asbestos Content:	< 1% Hair/Wool
Sample Composite Homogeneity:	Good

Location: MH.HA.011B, Plaster Walls & Ceilings

Lab ID-Version‡: 14821619-1

Sample Layers	Asbestos Content
Gray Plaster	ND
Composite Non-Asbestos Content:	< 1% Hair/Wool
Sample Composite Homogeneity:	Good

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Myers Hall; 2142203390

Date of Sampling: 10-25-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Location: MH.HA.011C, Plaster Walls & Ceilings

Lab ID-Version‡: 14821620-1

Sample Layers	Asbestos Content
Gray Plaster	ND
Composite Non-Asbestos Content:	< 1% Hair/Wool
Sample Composite Homogeneity:	Good

Location: MH.HA.011D, Plaster Walls & Ceilings

Lab ID-Version‡: 14821621-1

Sample Layers	Asbestos Content
Gray Plaster	ND
Composite Non-Asbestos Content:	< 1% Hair/Wool
Sample Composite Homogeneity:	Good

Location: MH.HA.011E, Plaster Walls & Ceilings

Lab ID-Version‡: 14821622-1

Sample Layers	Asbestos Content
Gray Plaster	ND
Composite Non-Asbestos Content:	< 1% Hair/Wool
Sample Composite Homogeneity:	Good

Location: MH.HA.011F, Plaster Walls & Ceilings

Lab ID-Version‡: 14821623-1

Sample Layers	Asbestos Content
Gray Plaster	ND
Composite Non-Asbestos Content:	< 1% Hair/Wool
Sample Composite Homogeneity:	Good

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Myers Hall; 2142203390

Date of Sampling: 10-25-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Location: MH.HA.011G, Plaster Walls & Ceilings

Lab ID-Version‡: 14821624-1

Sample Layers	Asbestos Content
Gray Plaster	ND
Composite Non-Asbestos Content:	< 1% Hair/Wool
Sample Composite Homogeneity:	Good

Location: MH.HA.012, 2'x2' White ACT Pinholes And Fissures

Lab ID-Version‡: 14821625-1

Sample Layers	Asbestos Content
Gray Ceiling Tile with White Surface	ND
Composite Non-Asbestos Content:	40% Cellulose 40% Glass Fibers
Sample Composite Homogeneity:	Good

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".



PROJECT: Woodward Resource Center JOB NO. 2142203390 PAGE: _____ JES

SUBJECT: _____ DATE: _____ COMP BY: _____ OK'D BY: _____

Myers Hall

1. MH·HA·001 - Cream w/specks 12"x12" VFT w/Mastic
2. MH·HA·002 - Light Gray w/Specks 12"x12" VFT w/Mastic
3. MH·HA·003 - Yellow 12"x12" VFT w/Mastic
4. MH·HA·004 - Orange 12"x12" VFT w/Mastic
5. MH·HA·005 - Blue 12"x12" VFT w/Mastic
6. MH·HA·006 - Red 12"x12" VFT w/Mastic
7. MH·HA·007 - Ceramic wall tile w/Mastic
8. MH·HA·008 - Yellow Mastic a/w Black covc Base
9. MH·HA·009 - Gray Leveling Compound
10. MH·HA·010 - Sheetrock & Joint Compound
11. MH·HA·011A - Plaster walls & ceilings
 B - " " "
 C - " " "
 D - " " "
 E - " " "
 F - " " "
 G - " " "
12. MH·HA·012 - 2'x2' white ACT Pinholes and Fissures

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins EPK Built Environment Testing, LLC
Project: Myers Hall; 2142203390
EML ID: 3071858

Approved by:



Laboratory Manager
Danny Li

Dates of Analysis:

Lead - Flame AA: 11-04-2022

Service SOPs: Lead - Flame AA (EM-BC-S-8443)
AIHA-LAP, LLC accredited service, Lab ID #178697

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. Due to the nature of the analyses performed, field blank correction of results is not applied. The results relate only to the samples as received and tested. Sample size, as it relates to Wipe samples only, is supplied by the client.

Eurofins EPK Built Environment Testing, LLC ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Eurofins EPK Built Environment Testing, LLC's LabServe® reporting system includes automated fail-safes to ensure that all AIHA-LAP, LLC quality requirements are met and notifications are added to reports when any quality steps remain pending.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Myers Hall; 2142203390

Date of Sampling: 10-25-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-04-2022

LEAD: FLAME ATOMIC ABSORPTION SPECTROMETRY

Location:	MH-ES-001: Bulk Sample Paint
Comments (see below)	A
Lab ID-Version‡:	14821160-1
Analysis Date:	11/04/2022
Sample type	Paint Chip sample
Method*	NIOSH 7082 & EPA 7000B modified
† Method Reporting Limit	39 ppm
Sample size	0.2589 grams
§Total Lead Result	< 39 ppm

Comments: A) The relative percent difference of the matrix duplicate pair was above control limits. The laboratory control sample and matrix blank were both within control limits and validated the batch.

Sample results have not been corrected for blank values.

Bulk samples are not covered under the AIHA-LAP, LLC service accreditation.


Wipe samples must meet ASTM E1792 criteria. Method Reporting Limits may not be valid for non-ASTM E1792 wipe samples.

*Sample preparation and analytical methods are based upon NIOSH 7082 and EPA 7000B.


† The Method Reporting Limit is the minimum concentration of Lead that the laboratory can confidently detect in the sample.

§ Total Lead Result has been rounded to two significant figures to reflect analytical precision.


‡ A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".





ELEVATION
TYPICAL AT CLOSED WINDOWS




TYPICAL AT CLOSED WINDOWS




TYPICAL ROUND UNIT



SECTION 1
SCALE 3/4"=1'-0"




SECTION 2
SCALE 3/4"=1'-0"



SECTION 3
SCALE 3/4"=1'-0"

SECTION 4
SCALE 3/4"=1'-0"



TYPICAL AT CLOSED WINDOWS
IN TOILET ROOMS

DOOR SCHEDULE

bldg	door no	door		frame					hardware	label	sign	remarks
		size	type	matl	type	matl	head	jamb				
	100	2'-0" x 7'-0"	B	SWG	I	L.M.	2	---	6A	---		
	101	NOT USED							6A	---		
	102	2'-0" x 7'-0"	B	SWG	I	H.P.	2	---	6A	---		
	103		A					---	6A	---		
	104		A					---	6A	---		
	105		A					---	6A	---		
	106		A					---	6A	---		
	107		A					---	6A	---		

FLOOR	FINISH						REMARKS	SCHEDULE	
	BASE	NORTH	EAST	SOUTH	WEST	FINISH		ROOM NUMBER	ROOM NAME
	A	A	A	A	A	A	CLASSROOM	100	
	C	A	A	A	A	A	ELECTRICAL ROOM	101	
	B	P	P	P	P	P	LOBBY	102	
	A	A	A	A	A	A	CORRIDOR	103	
	A	A	A	A	A	A	STAGE	104	
	A	A	A	A	A	A	AUDITORIUM	105	
	C	A	A	A	A	A	CORRIDOR	106	
	C	A	A	A	A	A	MCH. SHAFT	107	
	C	A	A	A	A	A	MCH. SHAFT	108	
	C	A	A	A	A	A	MCH. SHAFT	109	
	A	A	A	A	A	A	STAIR	110	
	A	A	A	A	A	A	VESTIBULE	111	
	C	A	A	A	A	A	CLASSROOM	112	
	C	A	A	A	A	A	CLASSROOM	113	
	A	B	P	P	P	P	COUNSEL	114	
	A	B	P	P	P	P	TRAINING	115	
	A	B	P	P	P	P	HANDICAP CLOSET	116	
	A	A	A	A	A	A	ELEVATOR	117	
	C	A	A	A	A	A	OFFICE	118	
	C	A	A	A	A	A	CORRIDOR	119	
	C	A	A	A	A	A	CORRIDOR	120	
	C	A	A	A	A	A	CORRIDOR	121	
	C	A	A	A	A	A	CORRIDOR	122	
	C	A	A	A	A	A	CORRIDOR	123	
	C	A	A	A	A	A	CORRIDOR	124	
	C	A	A	A	A	A	CORRIDOR	125	
	C	A	A	A	A	A	CORRIDOR	126	
	C	A	A	A	A	A	CORRIDOR	127	
	C	A	A	A	A	A	CORRIDOR	128	
	C	A	A	A	A	A	STAIR	129	
	C	A	A	A	A	A	STAIR	130	
	C	A	A	A	A	A	VESTIBULE	131	

CEILING		BASE	
A	A.T.C. 2x2 (3)	A	CERAMIC TILE
B	A.T.C. 2x2 (4)	B	SHEET RUBBER
C	GYP. BD. (PAINT)	C	VINYL PLATE P-REPAIRS
D		D	
E		E	
F		F	
G		G	
H		H	
I		I	

WALLS		FLOOR	
A	PAINT	A	CERAMIC TILE
B	PAINT (SPECIAL) A-REPAIRS	B	SHEET RUBBER
C		C	
D		D	
E		E	
F		F	
G		G	
H		H	
I		I	

REMARKS	
A EVERY PAINT	
B NEW WALLS ONLY	

KIRKHAM, MICHAEL AND ASSOCIATES





Interim Renovations for Title XIX
Woodward State Hospital-School
phase 4

WOODWARD, IOWA

FLOOR PLAN
SCHOOL FIRST FLOOR

A1-2

TO MOVE EXISTING PRECAST HEADS OF THESE WINDOWS CONTINUE NEW BRICK ON UP



DOOR SCHEDULE


bldg	door no	door		frame				hardware	label	sign	remarks
		size	type	mat'l	type	mat'l	head				
	200	4'-0\"/>									

FLOOR	BASE	WALLS				CLG.	FINISH	REMARKS	SCHEDULE	
		NORTH	SOUTH	WEST	EAST				ROOM NAME	ROOM NUMBER
B	B	A	A	A	A	A		CLASSROOM	200	
B	C	A	A	A	A	A		CLASSROOM	201	
B	B	A	A	A	A	A		CLASSROOM	202	
B	B	A	A	A	A	A		CLASSROOM	203	
B	B	A	A	A	A	A		CLASSROOM	204	
B	B	A	A	A	A	A		CLASSROOM	205	
B	B	A	A	A	A	A		CLASSROOM	206	
B	B	A	A	A	A	A		CLASSROOM	207	
B	B	A	A	A	A	A		CLASSROOM	208	
B	B	A	A	A	A	A		CLASSROOM	209	
B	B	A	A	A	A	A		CLASSROOM	210	
B	B	A	A	A	A	A		CLASSROOM	211	
B	B	A	A	A	A	A		CLASSROOM	212	
B	B	A	A	A	A	A		CLASSROOM	213	
B	B	A	A	A	A	A		CLASSROOM	214	
B	B	A	A	A	A	A		CLASSROOM	215	
B	B	A	A	A	A	A		CLASSROOM	216	
B	B	A	A	A	A	A		CLASSROOM	217	
B	B	A	A	A	A	A		CLASSROOM	218	
B	B	A	A	A	A	A		CLASSROOM	219	
B	B	A	A	A	A	A		CLASSROOM	220	
B	B	A	A	A	A	A		CLASSROOM	221	
B	B	A	A	A	A	A		CLASSROOM	222	
B	B	A	A	A	A	A		CLASSROOM	223	
B	B	A	A	A	A	A		CLASSROOM	224	
B	B	A	A	A	A	A		CLASSROOM	225	
B	B	A	A	A	A	A		CLASSROOM	226	
B	B	A	A	A	A	A		CLASSROOM	227	
B	B	A	A	A	A	A		CLASSROOM	228	
B	B	A	A	A	A	A		CLASSROOM	229	
B	B	A	A	A	A	A		CLASSROOM	230	
B	B	A	A	A	A	A		CLASSROOM	231	
B	B	A	A	A	A	A		CLASSROOM	232	
B	B	A	A	A	A	A		CLASSROOM	233	
B	B	A	A	A	A	A		CLASSROOM	234	
B	B	A	A	A	A	A		CLASSROOM	235	
B	B	A	A	A	A	A		CLASSROOM	236	
B	B	A	A	A	A	A		CLASSROOM	237	
B	B	A	A	A	A	A		CLASSROOM	238	
B	B	A	A	A	A	A		CLASSROOM	239	
B	B	A	A	A	A	A		CLASSROOM	240	
B	B	A	A	A	A	A		CLASSROOM	241	
B	B	A	A	A	A	A		CLASSROOM	242	
B	B	A	A	A	A	A		CLASSROOM	243	
B	B	A	A	A	A	A		CLASSROOM	244	
B	B	A	A	A	A	A		CLASSROOM	245	
B	B	A	A	A	A	A		CLASSROOM	246	
B	B	A	A	A	A	A		CLASSROOM	247	
B	B	A	A	A	A	A		CLASSROOM	248	
B	B	A	A	A	A	A		CLASSROOM	249	
B	B	A	A	A	A	A		CLASSROOM	250	
B	B	A	A	A	A	A		CLASSROOM	251	
B	B	A	A	A	A	A		CLASSROOM	252	
B	B	A	A	A	A	A		CLASSROOM	253	
B	B	A	A	A	A	A		CLASSROOM	254	
B	B	A	A	A	A	A		CLASSROOM	255	
B	B	A	A	A	A	A		CLASSROOM	256	
B	B	A	A	A	A	A		CLASSROOM	257	
B	B	A	A	A	A	A		CLASSROOM	258	
B	B	A	A	A	A	A		CLASSROOM	259	
B	B	A	A	A	A	A		CLASSROOM	260	
B	B	A	A	A	A	A		CLASSROOM	261	
B	B	A	A	A	A	A		CLASSROOM	262	
B	B	A	A	A	A	A		CLASSROOM	263	
B	B	A	A	A	A	A		CLASSROOM	264	
B	B	A	A	A	A	A		CLASSROOM	265	
B	B	A	A	A	A	A		CLASSROOM	266	
B	B	A	A	A	A	A		CLASSROOM	267	
B	B	A	A	A	A	A		CLASSROOM	268	
B	B	A	A	A	A	A		CLASSROOM	269	
B	B	A	A	A	A	A		CLASSROOM	270	
B	B	A	A	A	A	A		CLASSROOM	271	
B	B	A	A	A	A	A		CLASSROOM	272	
B	B	A	A	A	A	A		CLASSROOM	273	
B	B	A	A	A	A	A		CLASSROOM	274	
B	B	A	A	A	A	A		CLASSROOM	275	
B	B	A	A	A	A	A		CLASSROOM	276	
B	B	A	A	A	A	A		CLASSROOM	277	
B	B	A	A	A	A	A		CLASSROOM	278	
B	B	A	A	A	A	A		CLASSROOM	279	
B	B	A	A	A	A	A		CLASSROOM	280	
B	B	A	A	A	A	A		CLASSROOM	281	
B	B	A	A	A	A	A		CLASSROOM	282	
B	B	A	A	A	A	A		CLASSROOM	283	
B	B	A	A	A	A	A		CLASSROOM	284	
B	B	A	A	A	A	A		CLASSROOM	285	
B	B	A	A	A	A	A		CLASSROOM	286	
B	B	A	A	A	A	A		CLASSROOM	287	
B	B	A	A	A	A	A		CLASSROOM	288	
B	B	A	A	A	A	A		CLASSROOM	289	
B	B	A	A	A	A	A		CLASSROOM	290	
B	B	A	A	A	A	A		CLASSROOM	291	
B	B	A	A	A	A	A		CLASSROOM	292	
B	B	A	A	A	A	A		CLASSROOM	293	
B	B	A	A	A	A	A		CLASSROOM	294	
B	B	A	A	A	A	A		CLASSROOM	295	
B	B	A	A	A	A	A		CLASSROOM	296	
B	B	A	A	A	A	A		CLASSROOM	297	
B	B	A	A	A	A	A		CLASSROOM	298	
B	B	A	A	A	A	A		CLASSROOM	299	
B	B	A	A	A	A	A		CLASSROOM	300	

CEILING		BASE	
A	A.T.C. 2x2 (S)	A	CERAMIC TILE
B	A.T.C. 2x2 (T)	B	SHEET RUBBER
C	GYP. BD. (PAINT)	C	VINYL BASE D-RIBBING
D		D	
E		E	
F		F	
G		G	
H		H	
I		I	

WALLS		FLOOR	
A	PAINT	A	CERAMIC TILE
B	PAINT (SPECIAL) - REMARKS	B	SHEET RUBBER
C		C	
D		D	
E		E	
F		F	
G		G	
H		H	
I		I	

REMARKS
 A EXIST. PART
 B NEW WALLS ONLY



KIRKHAM, MICHAEL AND ASSOCIATES
 ARCHITECTS
 ENGINEERS
 PLANNERS

Interim Renovations for Title XIX
Woodward State Hospital School
 phase 4
 Woodward, Iowa

FLOOR PLAN
SCHOOL SECOND FLOOR

DATE: 11/15/03
 DRAWN BY: [Signature]
 CHECKED BY: [Signature]
 PROJECT NO: B-770244

0001	0201	0301	1103	1303	1403
0001	0201	0301	1103	1303	1403

November 10, 2022

Woodward Resource Center
ATTN: Mr. Rodney Carr
Facility Manager
1251 334th Street
Woodward, IA 50276

RE: Woodward Resource Center – Westwood Building – Asbestos Survey & Paint Chip Sampling

Dear Mr. Carr:

Per your request and authorization, Shive-Hattery, Inc. performed an asbestos survey and paint chip sampling for the above referenced project on October 25, 2022. It is our understanding that the building will undergo renovations that may disturb suspect asbestos-containing building materials and potential lead-based paint. It was the intent of the survey to determine what materials within the project area contain asbestos and lead.

Methods and Procedures

The review for this project was performed by personnel trained and certified under the National Emission Standards for Hazardous Air Pollutants (NESHAP) regulations. Partial or destructive testing was not performed to reveal concealed conditions.

A sample from each suspect homogeneous area was collected from the project areas at the Woodward Resource Center Westwood Building. Pertinent information such as location, color, etc. was recorded for each suspect material. The samples were then sent to an NAVLAP accredited laboratory for analysis.

The samples were analyzed for asbestos fibers utilizing the Polarized Light Microscopy method of analysis by EMLab P&K of Phoenix, AZ. Each sample was analyzed for the six different types of fibrous asbestos forms of which a percentage, by volume, is estimated and summarized. As defined by the U.S. Environmental Protection Agency mandated NESHAP regulations, the suspect material is considered an asbestos-containing material (ACM) if the material contains more than 1.0 percent of any one or a combination of asbestos fibers.

A composite bulk paint chip sample from suspect painted substrate areas was collected from project areas at Westwood. The bulk sample was sent to an AIHA accredited laboratory for analysis.

The bulk sample was analyzed for lead-based paint using flame atomic absorption spectrometry (Flame AA) under NIOSH 7082 and EPA 7000B modified, by EMLab P&K of Phoenix, AZ. Flame AA provides the most economical means of determining at risk environments to lead exposure. The EPA mandated method reporting limit for lead-based paint is 39 ppm (parts per million). Paint is lead containing at 0.5% by weight or 5,000 parts per million (ppm).

Pertinent information for each bulk sample has been summarized on the sample analytical results which can be found at the end of this report.



Summary of Findings

Twenty-five (25) samples were collected from 28 homogeneous areas located at Woodward Resource Center Westwood Building. Materials tested with an asbestos content greater than 1.0% are considered to be asbestos containing. The following table summarizes the sampling results by homogeneous area:

<u>Homogeneous Area</u>	<u>Asbestos Content</u>
1. White Ceramic Tile w/ multilayered Paint	0%
2. Dark Gray Mortar #1	0%
3. Gray Mortar	0%
4. Dark Gray Mortar #2	0%
5. Gray Ceiling Tile w/ White Surface	0%
6. Terrazzo Floor	0%
7. White Texture w/ White Paint Wall	0%
8. White Plaster w/ Yellow Paint Wall	0%
9. Off-White Plaster Wall	0%
10. White Non-fibrous Material	0%
11. White Compound w/ Blue Paint	0%
12. Cream Tape	0%
13. White Joint Compound	0%
14. White Drywall w/ Brown Paper	0%
15. White Compound w/ Green Paint	0%
16. White Compound w/ Multilayered Paint	0%
17. White Skim Coat	0%
18. Off-White Skim Coat	0%
19. White Skim Coat w/ Yellow Paint	0%
20. Brown Mastic	0%
21. White Mastic	0%
22. Dark Brown Mastic	0%
23. Off-White Compound #1	0%
24. Tan Mastic	0%
25. Off-White Compound #2	0%
26. Yellow Ceramic Tile	0%
27. Tan Mastic	0%
28. Brown Flooring	0%

Lead-based Paint Analysis

Sample Results

1. Bulk Paint Chip Sample (Westwood)	49 ppm
--------------------------------------	--------

Recommendations

Thus, it appears that the proposed project will not disturb any asbestos-containing materials and asbestos abatement is not required. There was also no paint identified as lead-containing within the project area.

Please call our office if you should have any questions or comments.

Sincerely,

SHIVE-HATTERY, INC.



Grant W. Bridgford
License Number IA 22-7928 INSP
Expiration Date: February 10, 2023

And



Samuel Becker
Environmental Specialist
Lead Inspector/Risk Assessor
LEAD-INSP10002

GWB/SSB/mas

Encs.

Copy: Chad Siems, S-H

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins Aerotech Built Environment Testing, Inc.
Project: Westwood; 2142203390
EML ID: 3071784

Approved by:

Dates of Analysis:
Asbestos PLM: 11-03-2022



Approved Signatory
Renee Luna-Trepczynski

Service SOPs: Asbestos PLM (EPA 40CFR App E to Sub E of Part 763 & EPA METHOD 600/R-93-116, SOP EM-AS-S-1267)
NVLAP Lab Code 500031-0

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. The results relate only to the samples as received and tested. The results include an inherent uncertainty of measurement associated with estimating percentages by polarized light microscopy. Measurement uncertainty data for sample results with >1% asbestos concentration can be provided when requested.

Eurofins Aerotech Built Environment Testing, Inc. ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Westwood; 2142203390

Date of Sampling: 10-25-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Total Samples Submitted:	25
Total Samples Analyzed:	25
Total Samples with Layer Asbestos Content > 1%:	0

Location: 1, WW-HA-001- White 4"X4" Cement Wall Tile

Lab ID-Version‡: 14821935-1

Sample Layers	Asbestos Content
White Ceramic Tile with Multilayered Paint	ND
Dark Gray Mortar #1	ND
Gray Mortar	ND
Dark Gray Mortar #2	ND
Sample Composite Homogeneity:	Poor

Location: 2, WW-HA-002-White 3'X2' ACT w/ Pinholes and Fissures

Lab ID-Version‡: 14821936-1

Sample Layers	Asbestos Content
Gray Ceiling Tile with White Surface	ND
Composite Non-Asbestos Content:	35% Cellulose 35% Glass Fibers
Sample Composite Homogeneity:	Good

Location: 3, WW-HA-003- Terrazo Floor with Orange Specks

Lab ID-Version‡: 14821937-1

Sample Layers	Asbestos Content
Multicolored Flooring	ND
Sample Composite Homogeneity:	Good

Location: 4A, WW-HA-004A-White Plaster Walls with Texture

Lab ID-Version‡: 14821938-1

Sample Layers	Asbestos Content
White Texture with White Paint	ND
White Plaster with Yellow Paint	ND
Sample Composite Homogeneity:	Moderate

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Client: Shive-Hattery
C/O: Grant Bridgford
Re: Westwood; 2142203390

Date of Sampling: 10-25-2022
Date of Receipt: 10-31-2022
Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Location: 4B, WW-HA-004B-White Plaster Walls with Texture

Lab ID-Version‡: 14821939-1

Sample Layers	Asbestos Content
White Plaster with Yellow Paint	ND
Off-White Plaster	ND
White Non-Fibrous Material	ND
Sample Composite Homogeneity:	Poor

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Westwood; 2142203390

Date of Sampling: 10-25-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Location: 4C, WW-HA-004C-White Plaster Walls with Texture

Lab ID-Version‡: 14821940-1

Sample Layers	Asbestos Content
White Plaster with Yellow Paint	ND
Off-White Plaster	ND
White Non-Fibrous Material	ND
Sample Composite Homogeneity: Poor	

Location: 4D, WW-HA-004D-White Plaster Walls with Texture

Lab ID-Version‡: 14821941-1

Sample Layers	Asbestos Content
White Plaster with Yellow Paint	ND
Off-White Plaster	ND
White Non-Fibrous Material	ND
Sample Composite Homogeneity: Poor	

Location: 4E, WW-HA-004E-White Plaster Walls with Texture

Lab ID-Version‡: 14821942-1

Sample Layers	Asbestos Content
White Plaster with Yellow Paint	ND
Off-White Plaster	ND
White Non-Fibrous Material	ND
Sample Composite Homogeneity: Poor	

Location: 4F, WW-HA-004F-White Plaster Walls with Texture

Lab ID-Version‡: 14821943-1

Sample Layers	Asbestos Content
White Plaster with Yellow Paint	ND
Off-White Plaster	ND
White Non-Fibrous Material	ND
Sample Composite Homogeneity: Poor	

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Westwood; 2142203390

Date of Sampling: 10-25-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Location: 4G, WW-HA-004G-White Plaster Walls with Texture

Lab ID-Version‡: 14821944-1

Sample Layers	Asbestos Content
White Plaster with Yellow Paint	ND
Off-White Plaster	ND
White Non-Fibrous Material	ND
Sample Composite Homogeneity:	Poor

Location: 5A, WW-HA-005A- Sheetrock and Joint Compound

Lab ID-Version‡: 14821945-1

Sample Layers	Asbestos Content
White Compound with Blue Paint	ND
Cream Tape	ND
White Joint Compound	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	15% Cellulose
Sample Composite Homogeneity:	Poor

Location: 5B, WW-HA-005B- Sheetrock and Joint Compound

Lab ID-Version‡: 14821946-1

Sample Layers	Asbestos Content
White Compound with Green Paint	ND
White Compound with Multilayered Paint	ND
Cream Tape	ND
White Joint Compound	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	15% Cellulose
Sample Composite Homogeneity:	Poor

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Westwood; 2142203390

Date of Sampling: 10-25-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Location: 5C, WW-HA-005C- Sheetrock and Joint Compound

Lab ID-Version‡: 14821947-1

Sample Layers	Asbestos Content
White Compound with Green Paint	ND
White Compound with Multilayered Paint	ND
Cream Tape	ND
White Joint Compound	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	15% Cellulose
Sample Composite Homogeneity:	Poor

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Westwood; 2142203390

Date of Sampling: 10-25-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Location: 5D, WW-HA-005D- Sheetrock and Joint Compound

Lab ID-Version‡: 14821948-1

Sample Layers	Asbestos Content
White Compound with Green Paint	ND
White Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Poor

Location: 5E, WW-HA-005E- Sheetrock and Joint Compound

Lab ID-Version‡: 14821949-1

Sample Layers	Asbestos Content
White Compound with Green Paint	ND
White Compound with Multilayered Paint	ND
White Drywall with Brown Paper	ND
Composite Non-Asbestos Content:	10% Cellulose
Sample Composite Homogeneity:	Poor

Location: 6A, WW-HA-006A-Plaster Ceilings with Texture

Lab ID-Version‡: 14821950-1

Sample Layers	Asbestos Content
White Skim Coat	ND
Off-White Base Coat	ND
Sample Composite Homogeneity:	Moderate

Location: 6B, WW-HA-006B-Plaster Ceilings with Texture

Lab ID-Version‡: 14821951-1

Sample Layers	Asbestos Content
White Skim Coat with Yellow Paint	ND
Off-White Base Coat	ND
White Non-Fibrous Material	ND
Sample Composite Homogeneity:	Poor

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Westwood; 2142203390

Date of Sampling: 10-25-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Location: 6C, WW-HA-006C-Plaster Ceilings with Texture

Lab ID-Version‡: 14821952-1

Sample Layers	Asbestos Content
White Skim Coat	ND
Off-White Base Coat	ND
Sample Composite Homogeneity: Moderate	

Location: 6D, WW-HA-006D-Plaster Ceilings with Texture

Lab ID-Version‡: 14821953-1

Sample Layers	Asbestos Content
White Skim Coat	ND
Off-White Base Coat	ND
Sample Composite Homogeneity: Moderate	

Location: 6E, WW-HA-006E-Plaster Ceilings with Texture

Lab ID-Version‡: 14821954-1

Sample Layers	Asbestos Content
White Skim Coat	ND
Off-White Base Coat	ND
Sample Composite Homogeneity: Moderate	

Location: 6F, WW-HA-006F-Plaster Ceilings with Texture

Lab ID-Version‡: 14821955-1

Sample Layers	Asbestos Content
White Skim Coat	ND
Off-White Base Coat	ND
Sample Composite Homogeneity: Moderate	

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Westwood; 2142203390

Date of Sampling: 10-25-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-03-2022

ASBESTOS PLM REPORT

Location: 6G, WW-HA-006G-Plaster Ceilings with Texture

Lab ID-Version‡: 14821956-1

Sample Layers	Asbestos Content
White Skim Coat	ND
Off-White Base Coat	ND
Sample Composite Homogeneity: Moderate	

Location: 7, WW-HA-007- Brown Cove Base Mastic

Lab ID-Version‡: 14821957-1

Sample Layers	Asbestos Content
Brown Mastic	ND
White Mastic	ND
Dark Brown Mastic	ND
Off-White Compound #1	ND
Tan Mastic	ND
Off-White Compound #2	ND
Sample Composite Homogeneity: Poor	

Location: 8, WW-HA-008-Yellow Ceramic Tile Mastic Wall Base Trim

Lab ID-Version‡: 14821958-1

Sample Layers	Asbestos Content
Yellow Ceramic Tile	ND
Gray Mortar	ND
Tan Mastic	ND
Sample Composite Homogeneity: Poor	

Location: 9, WW-HA-009- Brown Vinyl Flooring w/ Mastic

Lab ID-Version‡: 14821959-1

Sample Layers	Asbestos Content
Brown Flooring	ND
White Mastic	ND
Sample Composite Homogeneity: Moderate	

The test report shall not be reproduced except in full, without written approval of the laboratory. The report must not be used by the client to claim product certification, approval, or endorsement by any agency of the federal government. The Company reserves the right to dispose of all samples after a period of thirty (30) days, according to all state and federal guidelines, unless otherwise specified.

Inhomogeneous samples are separated into homogeneous subsamples and analyzed individually. ND means no fibers were detected. When detected, the minimum detection and reporting limit is less than 1% unless point counting is performed. Floor tile samples may contain large amounts of interference material and it is recommended that the sample be analyzed by gravimetric point count analysis to lower the detection limit and to aid in asbestos identification.

‡ A "Version" indicated by "-x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".




PROJECT: Woodward Resource Center NO. 2142203390 PAGE _____ OF _____ PAGES

SUBJECT: _____ DATE: _____ COMP BY: _____ OK'D BY: _____

Westwood


1. WW·HA·001 - white 4'x4" cement wall tile
2. WW·HA·002 - 2'x2' white ACT w/ Pinholes & fissures
3. WW·HA·003 - Terrazo floor w/ orange specks
4. WW·HA·004A - white Plaster walls w/ texture



5. WW·HA·005A - sheetrock & joint compound



6. WW·HA·006A - Plaster ceilings w/ texture



7. WW·HA·007 - Brown Cove Base Mastic
8. WW·HA·008 - Yellow Ceramic Tile mastic wall Base trim
9. WW·HA·009 - Brown vinyl Flooring w/ Mastic

Report for:

Grant Bridgford
Shive-Hattery
2839 Northgate Dr.
Iowa City, IA 52245

Regarding: Eurofins EPK Built Environment Testing, LLC
Project: Westwood; 2142203390
EML ID: 3071862

Approved by:



Laboratory Manager
Danny Li

Dates of Analysis:

Lead - Flame AA: 11-07-2022

Service SOPs: Lead - Flame AA (EM-BC-S-8443)
AIHA-LAP, LLC accredited service, Lab ID #178697

All samples were received in acceptable condition unless noted in the Report Comments portion in the body of the report. Due to the nature of the analyses performed, field blank correction of results is not applied. The results relate only to the samples as received and tested. Sample size, as it relates to Wipe samples only, is supplied by the client.

Eurofins EPK Built Environment Testing, LLC ("the Company"), a member of the Eurofins Built Environment Testing group of companies, shall have no liability to the client or the client's customer with respect to decisions or recommendations made, actions taken or courses of conduct implemented by either the client or the client's customer as a result of or based upon the Test Results. In no event shall the Company be liable to the client with respect to the Test Results except for the Company's own willful misconduct or gross negligence nor shall the Company be liable for incidental or consequential damages or lost profits or revenues to the fullest extent such liability may be disclaimed by law, even if the Company has been advised of the possibility of such damages, lost profits or lost revenues. In no event shall the Company's liability with respect to the Test Results exceed the amount paid to the Company by the client therefor.

Eurofins EPK Built Environment Testing, LLC's LabServe® reporting system includes automated fail-safes to ensure that all AIHA-LAP, LLC quality requirements are met and notifications are added to reports when any quality steps remain pending.

Client: Shive-Hattery
 C/O: Grant Bridgford
 Re: Westwood; 2142203390

Date of Sampling: 10-25-2022
 Date of Receipt: 10-31-2022
 Date of Report: 11-08-2022

LEAD: FLAME ATOMIC ABSORPTION SPECTROMETRY

Location:	WW-PC-001: Bulk Paint Ship Sample
Comments (see below)	None
Lab ID-Version‡:	14821157-1
Analysis Date:	11/07/2022
Sample type	Paint Chip sample
Method*	NIOSH 7082 & EPA 7000B modified
† Method Reporting Limit	0.0039%
Sample size	0.2563 grams
§Total Lead Result	0.0049%

Comments:

Sample results have not been corrected for blank values.

Bulk samples are not covered under the AIHA-LAP, LLC service accreditation.


Wipe samples must meet ASTM E1792 criteria. Method Reporting Limits may not be valid for non-ASTM E1792 wipe samples.

*Sample preparation and analytical methods are based upon NIOSH 7082 and EPA 7000B.

† The Method Reporting Limit is the minimum concentration of Lead that the laboratory can confidently detect in the sample.

§ Total Lead Result has been rounded to two significant figures to reflect analytical precision.

‡ A "Version" indicated by -"x" after the Lab ID# with a value greater than 1 indicates a sample with amended data. The revision number is reflected by the value of "x".




REFLECTED CEILING LEGEND	
	RETURN AIR REGISTERS
	SUPPLY AIR DIFFUSERS
	EXHAUST AIR REGISTERS
	RECESSED FLUORESCENT LIGHT FIXTURES
	RECESSED INCANDESCENT LIGHT FIXTURES
	NEW 2-HR. FIRE RATED PARTITION
	NEW 1-HR. FIRE RATED PARTITION

FINISH SCHEDULE			
HEIGHT	FINISH	ROOM NAME	ROOM NUMBER
1111	11	STAIR	1111
1111	11	STAIR	1112
1111	11	STAIR	1113
1111	11	STAIR	1114
1111	11	STAIR	1115
1111	11	STAIR	1116
1111	11	STAIR	1117
1111	11	STAIR	1118
1111	11	STAIR	1119
1111	11	STAIR	1120
1111	11	STAIR	1121
1111	11	STAIR	1122
1111	11	STAIR	1123
1111	11	STAIR	1124
1111	11	STAIR	1125
1111	11	STAIR	1126
1111	11	STAIR	1127
1111	11	STAIR	1128
1111	11	STAIR	1129
1111	11	STAIR	1130
1111	11	STAIR	1131
1111	11	STAIR	1132
1111	11	STAIR	1133
1111	11	STAIR	1134
1111	11	STAIR	1135
1111	11	STAIR	1136
1111	11	STAIR	1137
1111	11	STAIR	1138
1111	11	STAIR	1139
1111	11	STAIR	1140
1111	11	STAIR	1141
1111	11	STAIR	1142
1111	11	STAIR	1143
1111	11	STAIR	1144
1111	11	STAIR	1145
1111	11	STAIR	1146
1111	11	STAIR	1147
1111	11	STAIR	1148
1111	11	STAIR	1149
1111	11	STAIR	1150
1111	11	STAIR	1151
1111	11	STAIR	1152
1111	11	STAIR	1153
1111	11	STAIR	1154
1111	11	STAIR	1155
1111	11	STAIR	1156
1111	11	STAIR	1157
1111	11	STAIR	1158
1111	11	STAIR	1159
1111	11	STAIR	1160
1111	11	STAIR	1161
1111	11	STAIR	1162
1111	11	STAIR	1163
1111	11	STAIR	1164
1111	11	STAIR	1165
1111	11	STAIR	1166
1111	11	STAIR	1167
1111	11	STAIR	1168
1111	11	STAIR	1169
1111	11	STAIR	1170
1111	11	STAIR	1171
1111	11	STAIR	1172
1111	11	STAIR	1173
1111	11	STAIR	1174
1111	11	STAIR	1175
1111	11	STAIR	1176
1111	11	STAIR	1177
1111	11	STAIR	1178
1111	11	STAIR	1179
1111	11	STAIR	1180
1111	11	STAIR	1181
1111	11	STAIR	1182
1111	11	STAIR	1183
1111	11	STAIR	1184
1111	11	STAIR	1185
1111	11	STAIR	1186
1111	11	STAIR	1187
1111	11	STAIR	1188
1111	11	STAIR	1189
1111	11	STAIR	1190
1111	11	STAIR	1191
1111	11	STAIR	1192
1111	11	STAIR	1193
1111	11	STAIR	1194
1111	11	STAIR	1195
1111	11	STAIR	1196
1111	11	STAIR	1197
1111	11	STAIR	1198
1111	11	STAIR	1199
1111	11	STAIR	1200

FINISH SCHEDULE			
HEIGHT	FINISH	ROOM NAME	ROOM NUMBER
1111	11	OFFICE	121
1111	11	STORAGE	122
1111	11	STORAGE	123
1111	11	STORAGE	124
1111	11	STORAGE	125
1111	11	STORAGE	126
1111	11	STORAGE	127
1111	11	STORAGE	128
1111	11	STORAGE	129
1111	11	STORAGE	130
1111	11	STORAGE	131
1111	11	STORAGE	132
1111	11	STORAGE	133
1111	11	STORAGE	134
1111	11	STORAGE	135
1111	11	STORAGE	136
1111	11	STORAGE	137
1111	11	STORAGE	138
1111	11	STORAGE	139
1111	11	STORAGE	140
1111	11	STORAGE	141
1111	11	STORAGE	142
1111	11	STORAGE	143
1111	11	STORAGE	144
1111	11	STORAGE	145
1111	11	STORAGE	146
1111	11	STORAGE	147
1111	11	STORAGE	148
1111	11	STORAGE	149
1111	11	STORAGE	150
1111	11	STORAGE	151
1111	11	STORAGE	152
1111	11	STORAGE	153
1111	11	STORAGE	154
1111	11	STORAGE	155
1111	11	STORAGE	156
1111	11	STORAGE	157
1111	11	STORAGE	158
1111	11	STORAGE	159
1111	11	STORAGE	160
1111	11	STORAGE	161
1111	11	STORAGE	162
1111	11	STORAGE	163
1111	11	STORAGE	164
1111	11	STORAGE	165
1111	11	STORAGE	166
1111	11	STORAGE	167
1111	11	STORAGE	168
1111	11	STORAGE	169
1111	11	STORAGE	170
1111	11	STORAGE	171
1111	11	STORAGE	172
1111	11	STORAGE	173
1111	11	STORAGE	174
1111	11	STORAGE	175
1111	11	STORAGE	176
1111	11	STORAGE	177
1111	11	STORAGE	178
1111	11	STORAGE	179
1111	11	STORAGE	180
1111	11	STORAGE	181
1111	11	STORAGE	182
1111	11	STORAGE	183
1111	11	STORAGE	184
1111	11	STORAGE	185
1111	11	STORAGE	186
1111	11	STORAGE	187
1111	11	STORAGE	188
1111	11	STORAGE	189
1111	11	STORAGE	190
1111	11	STORAGE	191
1111	11	STORAGE	192
1111	11	STORAGE	193
1111	11	STORAGE	194
1111	11	STORAGE	195
1111	11	STORAGE	196
1111	11	STORAGE	197
1111	11	STORAGE	198
1111	11	STORAGE	199
1111	11	STORAGE	200

FINISH SCHEDULE			
HEIGHT	FINISH	ROOM NAME	ROOM NUMBER
1111	11	DAY ROOM	201
1111	11	OFFICE	202
1111	11	TOILET	203
1111	11	JANITOR CLOSET	204
1111	11	TOILET	205
1111	11	COUNSEL	206
1111	11	CORRIDOR	207
1111	11	CORRIDOR	208
1111	11	TOILET	209
1111	11	TOILET	210
1111	11	COUNSEL	211
1111	11	BEDROOM	212
1111	11	TOILET	213
1111	11	TOILET	214
1111	11	COUNSEL	215
1111	11	BEDROOM	216
1111	11	TOILET	217
1111	11	TOILET	218
1111	11	COUNSEL	219
1111	11	BEDROOM	220
1111	11	TOILET	221
1111	11	TOILET	222
1111	11	COUNSEL	223
1111	11	BEDROOM	224
1111	11	TOILET	225
1111	11	TOILET	226
1111	11	COUNSEL	227
1111	11	BEDROOM	228
1111	11	TOILET	229
1111	11	TOILET	230
1111	11	COUNSEL	231
1111	11	BEDROOM	232
1111	11	TOILET	233
1111	11	TOILET	234
1111	11	COUNSEL	235
1111	11	BEDROOM	236
1111	11	TOILET	237
1111	11	TOILET	238
1111	11	COUNSEL	239
1111	11	BEDROOM	240
1111	11	TOILET	241
1111	11	TOILET	242
1111	11	COUNSEL	243
1111	11	BEDROOM	244
1111	11	TOILET	245
1111	11	TOILET	246
1111	11	COUNSEL	247
1111	11	BEDROOM	248
1111	11	TOILET	249
1111	11	TOILET	250
1111	11	COUNSEL	251
1111	11	BEDROOM	252
1111	11	TOILET	253
1111	11	TOILET	254
1111	11	COUNSEL	255
1111	11	BEDROOM	256
1111	11	TOILET	257
1111	11	TOILET	258
1111	11	COUNSEL	259
1111	11	BEDROOM	260
1111	11	TOILET	261
1111	11	TOILET	262
1111	11	COUNSEL	263
1111	11	BEDROOM	264
1111	11	TOILET	265
1111	11	TOILET	266
1111	11	COUNSEL	267
1111	11	BEDROOM	268
1111	11	TOILET	269
1111	11	TOILET	270
1111	11	COUNSEL	271
1111	11	BEDROOM	272
1111	11	TOILET	273
1111	11	TOILET	274
1111	11	COUNSEL	275
1111	11	BEDROOM	276
1111	11	TOILET	277
1111	11	TOILET	278
1111	11	COUNSEL	279
1111	11	BEDROOM	280
1111	11	TOILET	281
1111	11	TOILET	282
1111	11	COUNSEL	283
1111	11	BEDROOM	284
1111	11	TOILET	285
1111	11	TOILET	286
1111	11	COUNSEL	287
1111	11	BEDROOM	288
1111	11	TOILET	289
1111	11	TOILET	290
1111	11	COUNSEL	291
1111	11	BEDROOM	292
1111	11	TOILET	293
1111	11	TOILET	294
1111	11	COUNSEL	295
1111	11	BEDROOM	296
1111	11	TOILET	297
1111	11	TOILET	298
1111	11	COUNSEL	299
1111	11	BEDROOM	300






REFLECTED CEILING LEGEND	
	RETURN AIR REGISTERS
	SUPPLY AIR DIFFUSERS
	EXHAUST AIR REGISTERS
	RECESSED FLUORESCENT LIGHT FIXTURES
	RECESSED INCANDESCENT LIGHT FIXTURES
	NEW 2-HR. FIRE RATED PARTITION
	NEW 1-HR. FIRE RATED PARTITION

FINISH SCHEDULE			
CLG.	HEIGHT	FINISH	ROOM NAME
0	10	A	OFFICE 121
0	10	A	OFFICE 122
0	10	A	TOILET 123
0	10	A	BEDROOM 124
0	10	A	BEDROOM 124A
0	10	A	COUNSEL 125
0	10	A	BEDROOM 126
0	10	A	TOILET 127
0	10	A	TOILET 127A
0	10	A	UNITOR CLOSET 127A
0	10	A	CORRIDOR 128
0	10	A	CORRIDOR 128A
0	10	A	COUNSEL 129A
0	10	A	BEDROOM 130
0	10	A	TOILET 131
0	10	A	DAY ROOM 131
0	10	A	OFFICE 132
0	10	A	CORRIDOR 133
0	10	A	CORRIDOR 134
0	10	A	CORRIDOR 134
0	10	A	STAIR S1
0	10	A	STAIR S2
0	10	A	STAIR S3
0	10	A	STAIR S4
0	10	A	STAIR S5
0	10	A	STAIR S6
0	10	A	STAIR S7
0	10	A	STAIR S8
0	10	A	STAIR S9
0	10	A	STAIR S10
0	10	A	STAIR S11
0	10	A	STAIR S12
0	10	A	STAIR S13
0	10	A	STAIR S14
0	10	A	STAIR S15
0	10	A	STAIR S16
0	10	A	STAIR S17
0	10	A	STAIR S18
0	10	A	STAIR S19
0	10	A	STAIR S20
0	10	A	STAIR S21
0	10	A	STAIR S22
0	10	A	STAIR S23
0	10	A	STAIR S24
0	10	A	STAIR S25
0	10	A	STAIR S26
0	10	A	STAIR S27
0	10	A	STAIR S28
0	10	A	STAIR S29
0	10	A	STAIR S30
0	10	A	STAIR S31
0	10	A	STAIR S32
0	10	A	STAIR S33
0	10	A	STAIR S34
0	10	A	STAIR S35
0	10	A	STAIR S36
0	10	A	STAIR S37
0	10	A	STAIR S38
0	10	A	STAIR S39
0	10	A	STAIR S40
0	10	A	STAIR S41
0	10	A	STAIR S42
0	10	A	STAIR S43
0	10	A	STAIR S44
0	10	A	STAIR S45
0	10	A	STAIR S46
0	10	A	STAIR S47
0	10	A	STAIR S48
0	10	A	STAIR S49
0	10	A	STAIR S50
0	10	A	STAIR S51
0	10	A	STAIR S52
0	10	A	STAIR S53
0	10	A	STAIR S54
0	10	A	STAIR S55
0	10	A	STAIR S56
0	10	A	STAIR S57
0	10	A	STAIR S58
0	10	A	STAIR S59
0	10	A	STAIR S60
0	10	A	STAIR S61
0	10	A	STAIR S62
0	10	A	STAIR S63
0	10	A	STAIR S64
0	10	A	STAIR S65
0	10	A	STAIR S66
0	10	A	STAIR S67
0	10	A	STAIR S68
0	10	A	STAIR S69
0	10	A	STAIR S70
0	10	A	STAIR S71
0	10	A	STAIR S72
0	10	A	STAIR S73
0	10	A	STAIR S74
0	10	A	STAIR S75
0	10	A	STAIR S76
0	10	A	STAIR S77
0	10	A	STAIR S78
0	10	A	STAIR S79
0	10	A	STAIR S80
0	10	A	STAIR S81
0	10	A	STAIR S82
0	10	A	STAIR S83
0	10	A	STAIR S84
0	10	A	STAIR S85
0	10	A	STAIR S86
0	10	A	STAIR S87
0	10	A	STAIR S88
0	10	A	STAIR S89
0	10	A	STAIR S90
0	10	A	STAIR S91
0	10	A	STAIR S92
0	10	A	STAIR S93
0	10	A	STAIR S94
0	10	A	STAIR S95
0	10	A	STAIR S96
0	10	A	STAIR S97
0	10	A	STAIR S98
0	10	A	STAIR S99
0	10	A	STAIR S100

FINISH SCHEDULE			
CLG.	HEIGHT	FINISH	ROOM NAME
0	10	A	DAY ROOM 100
0	10	A	OFFICE 101
0	10	A	TOILET 102
0	10	A	TOILET 103
0	10	A	STAFF TOILET 104
0	10	A	COUNSEL 105
0	10	A	BEDROOM 106
0	10	A	CORRIDOR 107
0	10	A	TOILET 108
0	10	A	TOILET 109
0	10	A	COUNSEL 110
0	10	A	BEDROOM 111
0	10	A	BEDROOM 112
0	10	A	STORAGE 113
0	10	A	MECHANICAL 114
0	10	A	CLOSET 115
0	10	A	OFFICE 116
0	10	A	DAY ROOM 117
0	10	A	LET 118
0	10	A	ACTIVITY 119
0	10	A	TOILET 120
0	10	A	KITCHEN 121
0	10	A	STAFF SERVICE 122
0	10	A	LOBBY 123





REFLECTED CEILING LEGEND

- RETURN AIR REGISTERS
- SUPPLY AIR DIFFUSERS
- EXHAUST AIR REGISTERS
- RECESSED FLUORESCENT LIGHT FIXTURES
- RECESSED INCANDESCENT LIGHT FIXTURES
- NEW 2-HR. FIRE RATED PARTITION
- NEW 1-HR. FIRE RATED PARTITION

ARCHITECTS
 ENGINEERS
 PLANNERS
KIRKHAM, MICHAEL AND ASSOCIATES

Interim Renovations for Title XIX
Woodward State Hospital-School
 phase 3
 Woodward, Iowa

FINISH SCHEDULE

CLG.	HEIGHT	FINISH	REMARKS	ROOM NAME	ROOM NUMBER
001	8'-0"	AC		CLASSROOM	001
002	8'-0"	AC		MECHANICAL	002
003	8'-0"	AC		TOILET	003
004	8'-0"	AC		TOILET	004
005	8'-0"	AC		STAFF TOILET	005
006	8'-0"	AC		STAFF TOILET	006
007	8'-0"	AC		CORRIDOR	007
008	8'-0"	AC		OFFICE	008
009	8'-0"	AC		STORAGE	009
010	8'-0"	AC		OFFICE	010
011	8'-0"	AC		STORAGE	011
012	8'-0"	AC		CLASS ROOM	012
013	8'-0"	AC		MECHANICAL	013
014	8'-0"	AC		OFFICE	014
015	8'-0"	AC		UNITOR CLOSET	015
016	8'-0"	AC		FORCH	016
017	8'-0"	AC		FORCH	017
018	8'-0"	AC		COMMON AREA	018
019	8'-0"	AC		ACTIVITY	019
020	8'-0"	AC		STAIR	020
021	8'-0"	AC		STAIR	021
022	8'-0"	AC		ACTIVITY	022
023	8'-0"	AC		EMPLOYEE TOILET	023
024	8'-0"	AC		ACTIVITY	024
025	8'-0"	AC		COOLER	025
026	8'-0"	AC		OFFICE	026
027	8'-0"	AC		OFFICE	027
028	8'-0"	AC		UNITOR CLOSET	028
029	8'-0"	AC		UNITOR CLOSET	029
030	8'-0"	AC		LOBBY	030
031	8'-0"	AC		MECHANICAL	031

FINISH SCHEDULE

CLG.	HEIGHT	FINISH	REMARKS	ROOM NAME	ROOM NUMBER
001	8'-0"	AC		CLASSROOM	001
002	8'-0"	AC		MECHANICAL	002
003	8'-0"	AC		TOILET	003
004	8'-0"	AC		TOILET	004
005	8'-0"	AC		STAFF TOILET	005
006	8'-0"	AC		STAFF TOILET	006
007	8'-0"	AC		CORRIDOR	007
008	8'-0"	AC		OFFICE	008
009	8'-0"	AC		STORAGE	009
010	8'-0"	AC		OFFICE	010
011	8'-0"	AC		STORAGE	011
012	8'-0"	AC		CLASS ROOM	012
013	8'-0"	AC		MECHANICAL	013
014	8'-0"	AC		OFFICE	014
015	8'-0"	AC		UNITOR CLOSET	015
016	8'-0"	AC		FORCH	016
017	8'-0"	AC		FORCH	017
018	8'-0"	AC		COMMON AREA	018
019	8'-0"	AC		ACTIVITY	019
020	8'-0"	AC		STAIR	020
021	8'-0"	AC		STAIR	021
022	8'-0"	AC		ACTIVITY	022
023	8'-0"	AC		EMPLOYEE TOILET	023
024	8'-0"	AC		ACTIVITY	024
025	8'-0"	AC		COOLER	025
026	8'-0"	AC		OFFICE	026
027	8'-0"	AC		OFFICE	027
028	8'-0"	AC		UNITOR CLOSET	028
029	8'-0"	AC		UNITOR CLOSET	029
030	8'-0"	AC		LOBBY	030
031	8'-0"	AC		MECHANICAL	031



REFLECTED CEILING PLAN
WESTWOOD BASEMENT

A2-1
 1101 1301
 1101 1301



Kleene, Jennifer <jennifer.kleene@iowa.gov>

Cottage 201 asbestos

1 message

Tyson L. Scheidecker <tscheidecker@shive-hattery.com>

Tue, Nov 29, 2022 at 12:51 PM

To: "Rodney Carr (rcarr@dhs.state.ia.us)" <rcarr@dhs.state.ia.us>

Cc: Jennifer Kleene <jennifer.kleene@iowa.gov>, Sam Vorrie <sam.vorrie@storycon.com>, Jeff Reams <jreams@storycon.com>

Rodney,

I spoke with our hazardous material team about the asbestos in cottage 201 and have a few updates. First, the positive test was white compound on the wall behind the tile in what are calling the northeast restroom. There was nothing on the ceilings.

Secondly, since we are ceiling mounting all the new fire alarm devices, we can put notes on the drawings about the asbestos locations and note for the contractor to avoid those locations and use safe handling procedures around those areas of work, such as wetting surfaces.

We do have to consider that area positive for asbestos, regardless of if it was a false positive or not. So even if you retest it so there's not a lot to gain by retesting and not a lot to gain by testing additional areas since we have all ceiling mounted devices.

Let me know if you have any questions.

Thanks,

Tyson L. Scheidecker, P.E.

Mechanical Engineer

Shive-Hattery

[4125 Westown Parkway | Suite 100 | West Des Moines, IA 50266](#)

515.223.8104 | 515.333.4896 | 800.798.8104

SHIVEHATTERY
ARCHITECTURE+ENGINEERING



Sign-in Sheet

Name	Company	Email Address	Telephone
Jeffrey Reams	Story Construction Co.	jreams@storycon.com	515-291-8185
Sam Vorrie	Story Construction Co.	sam.vorrie@storycon.com	515-291-4483
Darren Milliken	Story Construction Co.	darren.milliken@storycon.com	515-291-5358
Elijah Ralston	Story Construction Co.	elijah.ralston@storycon.com	515-290-1135
Jennifer Kleene	DAS	jennifer.kleene@iowa.gov	515-725-0454
Rodney Carr	WRC	rcarr@dhs.state.ia.us	
Rob Jaeger	CEC	rjaeger@cecinfo.com	515-991-7655
Andy White	JCI/Simpler	Andrew.J.White@JCI.com	712-878-5024
Tyson Scheidecker	Shive-Hattery	tyson@shive-hattery.com	515-223-8104
Eric Maguire	"	EMAGUIRE "	"
Kevin Bruvorn	"	KBruvorn@ "	"
Larry Meiners	ACI Mechanical	lmeiners@acimech.com	515-232-1236
Krista Carter	Heartland Companies	Kristac@heartland.us	515.244.8900
Bob Mahoney	Mahoney Fire Sprinkler	bob3@mahoneyfiresprinkler.com	402-553-1221
Dan Macaitis	Mahoney Fire		402-553-1221
PAT ASTOR	Siemens	Pat.Astor-111@siemens.com	515-661-9688
Matt Smith	Siemens	Matt@Siemens.com	515-371-3746

Jeremy Denmon
Zeb Anderson

Siemens
Tri-City Electric

jeremy.denmon@siemens.com
zanderson@tricityelectric.com

515 553 7019
563-210-9131