

**Iowa Communications Network Statement of Work
OSP Log 04220105, New Link 1523, 12 Fiber Cable
Appanoose County, Centerville, County Sheriff Office, 22158 Dewey Road**

Project Overview:

THE ICN INTENDS TO INSTALL A 12-STRAND ARMORED FIBER CABLE CONNECTION FROM THE ICN DATA ROOM ON THE INDIAN HILLS COLLEGE CAMPUS, CENTERVILLE, IA TO THE NEW APPANOOSE COUNTY SHERIFFS OFFICE, CENTERVILLE, IA. THIS WILL REQUIRE CONDUIT OF APPROXIMATELY 15,868 FEET AND A TOTAL CABLE FOOTAGE OF APPROXIMATELY 19,000 FEET.

Access Point for this project will be Indian Hills Community College at 721 N 1st St, Centerville, IA

Please see the maps and pictures in the attached CONSTRUCTION DRAWING(S). All work to be completed per the attached STANDARD INSTALLATION REQUIREMENTS and TYPICALS except where noted within this STATEMENT OF WORK (SOW). Upon notification of completion, the ICN will perform a review using the attached PUNCHLIST. Any corrections will need to be made prior to ICN issuing payment for work completed.

FIBER OPTIC CABLE SPLICING EXCLUDED FROM THIS CONSTRUCTION BID

ICN Responsibilities:

1. Project Management
2. ICN will secure all necessary DOT, County, or City ROW permits.
3. **ICN Provided Materials per attached table in construction drawings:** Contractor shall pick up ICN-provided materials at the ICN warehouse in Des Moines. Contact the ICN warehouse 48 hours in advance to pick up materials; contact Paul Damage (515-725-4749) to ensure availability.

Contractor Responsibilities:

1. Contractor shall supply all other materials required for proper installation, including but not limited to: Handholes, HDPE, Grounding and Tracer Wires, Rock, Wire Mesh, etc.
2. Construction and/or excavation permits and/or bonds as required by ROW jurisdiction.

Bid/Job Showing: N/A

Work Start Date: Work may begin upon award of the bid and completion of the contract. The ICN anticipates work to begin in April 2022 (contractor can begin earlier if conditions allow).

Completion Date: Substantial completion not later than June 17th, 2022. Contractor's option to work during winter months but no allowance for extras will be provided. Contractor is required to coordinate with the County Sheriff's Office for tie-in to the future building entrance conduit and final cable installation into the site.

Only written modifications to this Scope of Work are binding - Verbal changes to this scope of work by any person or persons are not binding, unless confirmed in writing.

Quotes:

1. Quotes must be **SEALED** and received by Sheri Stephens, ICN Contracting, **NLT 2PM on February 4, 2022.**
2. Contractors must submit a quote for Construction Bid as outlined in the SOW and per the Engineering drawings. ICN requires a breakdown of lump sum bids into labor and materials.

Completion of Work:

1. Upon notification of construction completion, ICN will have 2 weeks to complete the Punch List.
2. Upon initial completion of Punch List, the Contractor will have 2 weeks to correct any issues identified on the Punch List.
3. Upon notification of corrections, the ICN will have 1 week to verify corrections were completed to the ICN's satisfaction.
4. No payment will be made until all work is completed per the contract unless agreed upon by both parties.

Attachments: The following are included by reference and as provided within Bid Documents.

Statement of Work (SOW), this document

Construction Drawings (includes Materials list and Typical Installation Drawings)

Punch List