


SATURATED BUFFER CONSTRUCTION PLANS

SCOTT CO, IOWA
SECTION 07 - T78N - R2E




**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES



ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	7/31/2023
DRAWN BY	ANDREW MACKRILL	DATE	7/31/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	7/31/2023
APPROVED BY			



COVER SHEET

FILE NAME

DRAWING SET
SHEET 1 OF 6


Staking Control Points(NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	585413.8	2383475.2	718.2
2	Distribution Line	585224.2	2383742.2	718.1
3	Distribution Line	585069.5	2383969.5	718.7
4	Distribution Line	584849.7	2384288.4	718.8
5	Distribution Line	584706.1	2384494.1	719.9
6	Distribution Line	584616.5	2384581.5	720.0
7	Benchmark	5853330.5	2383463.6	719.0

DATE 7/31/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

PLAN MAP



FILE NAME
 DRAWING SET SHEET 2 OF 6




PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 585330.5
 Easting: 2383463.6
 Elevation: 719.0

Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 8" Non-Perforated CPT
- Proposed 8" CMP Outlet
- Existing 8" CPT Main
- Proposed Water Control Structure
- 2' Contours
- Benchmark
- Staking Point

Cross-Section




DESIGNED BY ANDREW MACKRILL 7/31/23
 DRAWN BY ANDREW MACKRILL 7/31/23
 CHECKED BY ANDY CRAIG, PE, TSP 7/31/23
 APPROVED BY _____






BUFFER AND BANK CROSS SECTION



FILE NAME
 DRAWING SET
 SHEET 3 OF 6



Legend

-  All Season Water Table
-  Proposed Water Control Structure
-  Proposed 6" CPT Distribution Line
-  Existing Ground Surface
-  Lowest Farmed Elevation


DESIGNED BY	ANDREW MACKRILL	DATE	7/31/23
DRAWN BY	ANDREW MACKRILL		7/31/23
CHECKED BY	ANDY CRAIG, PE, TSP		7/31/23
APPROVED BY			

PROFILE ALONG DISTRIBUTION LINE




FILE NAME
A
DRAWING SET
SHEET 4 OF 6

LANDOWNER	LOCATION	SECTION 07 - T78N - R2E
-----------	----------	-------------------------




TYPICAL SECTION




- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 8 in.	1	IA-21, IA-26, CPS-587
8" Non-perforated Pipe (ft)	40	IA-21, IA-45
8" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	1366	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers



PLAN



IN-LINE CONTROL STRUCTURE

DATE 7/31/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

3 CHAMBER STRUCTURE DETAIL



FILE NAME
 DRAWING SET
 SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE 7/31/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

CONSTRUCTION NOTES



FILE NAME

A

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 07 - T78N - R2E


SATURATED BUFFER CONSTRUCTION PLANS

SCOTT CO, IOWA
SECTION 07 - T78N - R2E



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 8/2/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: _____ All

ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	8/2/2023
DRAWN BY	ANDREW MACKRILL	DATE	8/2/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	8/2/2023
APPROVED BY			



COVER SHEET

FILE NAME

DRAWING SET
SHEET 1 OF 6


Staking Control Points(NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	584735.4	2384342.2	718.4
2	Distribution Line	584763.9	2384299.1	718.7
3	Distribution Line	584867.6	2384139.5	717.9
4	Distribution Line	585013.6	2383916.3	717.9
5	Distribution Line	585150.9	2383715.4	718.0
6	Distribution Line	585300.9	2383498.8	718.1
7	Benchmark	585330.5	2383463.6	719.0

DATE 7/31/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

PLAN MAP



FILE NAME
 DRAWING SET SHEET 2 OF 6



PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 585330.5
 Easting: 2383463.6
 Elevation: 719.0

Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 10" Non-Perforated CPT
- Existing 10" CPT Main
- Proposed 10" CMP Outlet
- Proposed Water Control Structure
- 2' Contours
- Benchmark
- Staking Point


Buffer Cross Section, See Sheet 3

1015' of 6" CPT at 0.0% Grade

New 10" CMP Outlet With Rodent Guard

Existing 10" Tile

Cross-Section



DESIGNED BY ANDREW MACKRILL 7/31/23
 DRAWN BY ANDREW MACKRILL 7/31/23
 CHECKED BY ANDY CRAIG, PE, TSP 7/31/23
 APPROVED BY _____


BUFFER AND BANK CROSS SECTION








FILE NAME
A
 DRAWING SET
SHEET 3 OF 6

DESIGNED BY ANDREW MACKRILL 7/31/23
 DRAWN BY ANDREW MACKRILL 7/31/23
 CHECKED BY ANDY CRAIG, PE, TSP 7/31/23
 APPROVED BY _____

PROFILE ALONG DISTRIBUTION LINE




Legend

-  All Season Water Table
-  Proposed Water Control Structure
-  Proposed 6" CPT Distribution Line
-  Existing Ground Surface
-  Lowest Farmed Elevation



FILE NAME


DRAWING SET
SHEET 4 OF 6




TYPICAL SECTION

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 10 in.	1	IA-21, IA-26, CPS-587
10" Non-perforated Pipe (ft)	30	IA-21, IA-45
10" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	1016	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587



PLAN



IN-LINE CONTROL STRUCTURE

*Quantities Do Not Include Couplers

DATE 7/31/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

3 CHAMBER STRUCTURE DETAIL



FILE NAME
 DRAWING SET
 SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE 7/31/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 07 - T78N - R2E


SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 16 - T79N - R3W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 8/8/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: _____ All

ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	8/8/2023
DRAWN BY	ANDREW MACKRILL	DATE	8/8/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	8/8/2023
APPROVED BY			



COVER SHEET

FILE NAME



DRAWING SET

SHEET 1 OF 6









Staking Control Points				
Point	Description	Northing	Easting	Elevation
1	WCS	606556.1	2266863.6	715.0
2	Distribution Line	606724.2	2266871.6	715.1
3	Distribution Line	606899.4	2266863.0	715.5
4	Distribution Line	607048.9	2266855.5	716.3
5	Distribution Line	607162.0	2266849.9	717.1
6	Distribution Line	607279.9	2266844.2	718.0
7	Benchmark	607477.8	2266804.4	719.2

PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 607477.8
 Easting: 2266804.4
 Elevation: 719.2

Legend

-  Proposed 6" Perforated CPT Distribution Line
-  Proposed 10" Non-Perforated CPT
-  Proposed 10" CMP Outlet
-  Proposed 10" CPT Main
-  Benchmark
-  Proposed Water Control Structure
-  Staking Point
-  2' Contours

Existing 8" Tile to be Replaced with 10" Non-Perf Pipe and 10" CMP with Rodent Guard

720' of 6" CPT at 0.0% Grade

Buffer Cross Section, See Sheet 3

Abandoned 4-Inch outlet to be destroyed



DATE 8/8/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG PE.TSP
 APPROVED BY


PLAN MAP



FILE NAME

DRAWING SET SHEET 2 OF 6

Buffer Cross-Section




DESIGNED BY	ANDREW MACKRILL	DATE	8/8/23
DRAWN BY	ANDREW MACKRILL		8/8/23
CHECKED BY	ANDY CRAIG, PE,TSP		8/8/23
APPROVED BY			

BUFFER AND BANK CROSS SECTION



FILE NAME	
DRAWING SET	SHEET 3 OF 6

LANDOWNER		LOCATION	SECTION 16 - T79N - R3W
-----------	--	----------	-------------------------



- #### Legend
- All Season Water Table
 - Proposed Water Control Structure
 - Proposed 6" CPT Distribution Line
 - Existing Ground Surface
 - Lowest Farmed Elevation


DATE
 DESIGNED BY ANDREW MACKRILL 8/8/23
 DRAWN BY ANDREW MACKRILL 8/8/23
 CHECKED BY ANDY CRAIG, PE TSP 8/8/23
 APPROVED BY _____

PROFILE ALONG DISTRIBUTION LINE




FILE NAME

DRAWING SET
 SHEET 4 OF 6




TYPICAL SECTION



QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 10 in.	1	IA-21, IA-26, CPS-587
10" Non-perforated Pipe (ft)	30	IA-21, IA-45
10" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	720	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587


*Quantities Do Not Include Couplers



PLAN

NOTES:

1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
3. Couplings between the water control section and the non-perforated tile shall be water tight.
4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.



IN-LINE CONTROL STRUCTURE

DATE	8/8/23
DESIGNED BY ANDREW MACKRILL	8/8/23
DRAWN BY ANDREW MACKRILL	8/8/23
CHECKED BY ANDY CRAIG, PE,TSP	8/8/23
APPROVED BY	

3 CHAMBER STRUCTURE DETAIL



FILE NAME

DRAWING SET
SHEET 5 OF 6

LANDOWNER

LOCATION

SECTION 16 - T79N - R3W

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE 8/8/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE,TSP
 APPROVED BY

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 16 - T79N - R3W


SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 33 - T80N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 8/22/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: _____ All

ENGINEERING CLASS 3

DESIGNED BY	ANDREW MACKRILL	DATE	8/22/2023
DRAWN BY	ANDREW MACKRILL	DATE	8/22/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	8/22/2023
APPROVED BY			



COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 6

PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 625261.0
 Easting: 2237768.1
 Elevation: 738.9

Staking Control Points(NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	625236.7	2237894.5	736.8
2	Distribution Line	625215.8	2238064.9	735.6
3	Distribution Line	625204.8	2238188.1	735.4
4	Distribution Line	625182.2	2238343.5	735.1
5	Distribution Line	625123.1	2238454.7	734.8
6	Distribution Line	625072.2	2238565.2	734.3
7	Benchmark	625261.0	2237768.1	738.9

DATE 8/22/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY



Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 12" Non-Perforated CPT
- Proposed 12" CMP Outlet
- Existing 8" CPT Main
- Proposed 8" Non-Perforated CPT
- Proposed Water Control Structure
- 2' Contours
- Benchmark
- Staking Point


PLAN MAP



FILE NAME

DRAWING SET
 SHEET 2 OF 6

Cross-Section




DESIGNED BY ANDREW MACKRILL 8/22/23
 DRAWN BY ANDREW MACKRILL 8/22/23
 CHECKED BY ANDY CRAIG, PE, TSP 8/22/23
 APPROVED BY _____

BUFFER AND BANK CROSS SECTION



FILE NAME _____
 DRAWING SET SHEET 3 OF 6



Legend

- All Season Water Table
- Proposed Water Control Structure
- Proposed 6" CPT Distribution Line
- Existing Ground Surface
- Lowest Farmed Elevation

DESIGNED BY ANDREW MACKRILL	DATE 8/22/23
DRAWN BY ANDREW MACKRILL	8/22/23
CHECKED BY ANDY CRAIG, PE, TSP	8/22/23
APPROVED BY	


PROFILE ALONG DISTRIBUTION LINE



FILE NAME


DRAWING SET
SHEET 4 OF 6

LANDOWNER	LOCATION	SECTION 33 - T80N - R4W
------------------	-----------------	--------------------------------




TYPICAL SECTION

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.




QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 12 in.	1	IA-21, IA-26, CPS-587
12" Non-perforated Pipe (ft)	40	IA-21, IA-45
12" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-620
8" Non-perforated Pipe (ft)	100	IA-21, IA-45
6" Perforated CPT (ft) Buffer Tile Line	700	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers



PLAN



IN-LINE CONTROL STRUCTURE

DATE 8/22/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

3 CHAMBER STRUCTURE DETAIL



FILE NAME

DRAWING SET
 SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE 8/22/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
SHEET 6 OF 6


SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 29 - T79N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



INDEX OF SHEETS

1. COVER SHEET
2. PLAN MAP
3. BUFFER AND BANK CROSS SECTION
4. PROFILE ALONG DISTRIBUTION LINE
5. STRUCTURE DETAILS
6. CONSTRUCTION NOTES

	<p>I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa</p>
	<p style="text-align: right;"><i>Andy J. Craig</i> _____ 07/28/2023</p> <p>Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2023. Pages or sheets covered by this seal: _____ All _____</p>

ENGINEERING CLASS 2

DESIGNED BY	BEN REINHART	DATE	07/27/2023
DRAWN BY	BEN REINHART	DATE	07/27/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	07/28/2023
APPROVED BY			



COVER SHEET



FILE NAME

DRAWING SET

SHEET 1 OF 6

PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD83, Iowa South, US Survey Feet)
 Northing: 596160.127
 Easting: 2232728.314
 Elevation: 674.3




Staking Control Points (NAD83, Iowa South, US Survey Feet)

Point	Description	Northing	Easting	Elevation
1	Benchmark	596160.127	2232728.314	674.3
2	Control Structure	595848.002	2232576.632	672.5
3	Distribution Line	595949.133	2232604.826	673.2
4	Distribution Line	596045.961	2232645.203	673.7
5	Distribution Line	596134.098	2232702.193	673.8
6	Distribution Line	596233.421	2232734.909	673.6
7	Distribution Line	596329.747	2232776.349	674.0
8	Distribution Line	596424.863	2232820.845	674.3
9	Distribution Line	596516.147	2232872.371	674.0
10	Distribution Line	596600.168	2232934.884	674.0
11	Distribution Line	596682.522	2232999.715	674.6
12	Distribution Line	596764.072	2233065.796	674.5
13	Distribution Line	596843.750	2233134.192	674.8
14	Distribution Line	596925.705	2233199.773	674.9
15	Distribution Line	597000.862	2233273.108	675.1
16	Distribution Line	597086.518	2233333.705	676.1

Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 8" Non-Perforated CPT
- Proposed 8" CMP Outlet
- Proposed Water Control Structure
- Existing 8" CPT Main
- Benchmark
- Staking Points
- 2' Contours



DATE	DESIGNED BY	DRAWN BY	CHECKED BY	APPROVED BY
07/21/23	BEN REINHART	BEN REINHART	ANDY CRAIG, PE, TSP	
07/27/23				
07/28/23				


PLAN MAP



FILE NAME

DRAWING SET
 SHEET 2 OF 6

Buffer Cross Section




DATE
 DESIGNED BY BEN REINHART 07/21/23
 DRAWN BY BEN REINHART 07/27/23
 CHECKED BY ANDY CRAIG, PE, TSP 07/28/23
 APPROVED BY _____

BUFFER AND BANK CROSS SECTION



FILE NAME
 Bo
DRAWING SET
 SHEET 3 OF 6




- #### Legend
- All Season Water Table
 - Proposed Water Control Structure
 - Proposed 6" CPT Distribution Line
 - Existing Ground Surface
 - Lowest Crop Elevation

DATE
 DESIGNED BY BEN REINHART 07/21/23
 DRAWN BY BEN REINHART 07/27/23
 CHECKED BY ANDY CRAIG, PE, TSP 07/28/23
 APPROVED BY _____

PROFILE ALONG DISTRIBUTION LINE



FILE NAME
 DRAWING SET
 SHEET 4 OF 6




TYPICAL SECTION


- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 8 in.	1	IA-21, IA-26, CPS-587
8" Non-perforated CPT (ft)	20	IA-21, IA-45
8" CMP Outlet with Rodent Guard	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	1430	IA-21, IA-45, IA-46
6" Non-perforated CPT (ft) Buffer Tile Line (see Plan Map, Pg 2)	20	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers



PLAN



IN-LINE CONTROL STRUCTURE

DATE
DESIGNED BY BEN REINHART 07/21/23
DRAWN BY BEN REINHART 07/27/23
CHECKED BY ANDY CRAIG, PE, TSP 07/28/23
APPROVED BY

3 CHAMBER STRUCTURE DETAIL



FILE NAME
DRAWING SET
SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE
 DESIGNED BY BEN REINHART 07/21/23
 DRAWN BY BEN REINHART 07/27/23
 CHECKED BY ANDY CRAIG, PE, TSP 07/28/23
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 29 - T79N - R4W


SATURATED BUFFER CONSTRUCTION PLANS

JOHNSON CO, IOWA
SECTION 36 - T80N - R5W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



INDEX OF SHEETS

1. COVER SHEET
2. PLAN MAP
3. BUFFER AND BANK CROSS SECTION
4. PROFILE ALONG DISTRIBUTION LINE
5. STRUCTURE DETAILS
6. CONSTRUCTION NOTES

	<p>I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa</p>
	<p style="text-align: right;"><i>Andy J. Craig</i> _____ 08/02/2023</p> <p>Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2023. Pages or sheets covered by this seal: _____ All _____</p>

ENGINEERING CLASS 2

DESIGNED BY	BEN REINHART	DATE	07/31/2023
DRAWN BY	BEN REINHART	DATE	07/31/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	08/02/2023
APPROVED BY			





COVER SHEET

FILE NAME	
DRAWING SET	SHEET 1 OF 6

PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD83, Iowa South, US Survey Feet)
 Northing: 625150.611
 Easting: 2218841.530
 Elevation: 776.8



Staking Control Points (NAD83, Iowa South, US Survey Feet)

Point	Description	Northing	Easting	Elevation
1	Benchmark	625150.611	2218841.530	776.8
2	Control Structure	625118.602	2218709.047	771.1
3	Distribution Line	625047.713	2218772.452	771.0
4	Distribution Line	624961.137	2218822.192	770.2
5	Distribution Line	624890.201	2218891.457	770.2
6	Distribution Line	624821.809	2218964.330	770.2
7	Distribution Line	624751.297	2219035.240	770.2

DATE 07/31/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

PLAN MAP

New 12" CMP Outlet with Rodent Guard

Existing 12" Tile

500' of 6" CPT at 0.0% Grade

Buffer Cross Section, See Sheet 3


Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 12" Non-Perforated CPT
- Proposed 12" CMP Outlet
- Proposed Water Control Structure
- Existing 12" CPT Main
- Benchmark
- Staking Points
- 2' Contours



FILE NAME
 No
 DRAWING SET
 SHEET 2 OF 6

Buffer Cross Section



DESIGNED BY BEN REINHART 07/31/23
 DRAWN BY BEN REINHART 07/31/23
 CHECKED BY ANDY CRAIG, PE, TSP 08/02/23
 APPROVED BY _____

BUFFER AND BANK CROSS SECTION



FILE NAME

6


DRAWING SET
 SHEET 3 OF 6

LANDOWNER






LOCATION

SECTION 36 - T80N - R5W

Profile Along Distribution Line



Legend

-  All Season Water Table
-  Proposed Water Control Structure
-  Proposed 6" CPT Distribution Line
-  Existing Ground Surface
-  Lowest Crop Elevation


DATE	07/31/23
DESIGNED BY BEN REINHART	07/31/23
DRAWN BY BEN REINHART	07/31/23
CHECKED BY ANDY CRAIG, PE, TSP	08/02/23
APPROVED BY	

PROFILE ALONG DISTRIBUTION LINE





FILE NAME

DRAWING SET
SHEET 4 OF 6




TYPICAL SECTION



PLAN

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.



IN-LINE CONTROL STRUCTURE

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 12 in.	1	IA-21, IA-26, CPS-587
12" Non-perforated CPT (ft)	20	IA-21, IA-45
12" CMP Outlet with Rodent Guard	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	500	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers

DATE	07/31/23
DESIGNED BY BEN REINHART	07/31/23
DRAWN BY BEN REINHART	07/31/23
CHECKED BY ANDY CRAIG, PE, TSP	08/02/23
APPROVED BY	

3 CHAMBER STRUCTURE DETAIL



FILE NAME	
DRAWING SET	
SHEET 5 OF 6	

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE
 DESIGNED BY BEN REINHART 07/31/23
 DRAWN BY BEN REINHART 07/31/23
 CHECKED BY ANDY CRAIG, PE, TSP 08/02/23
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

By

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 36 - T80N - R5W


SATURATED BUFFER CONSTRUCTION PLANS

SECTION 36 - T80N - R5W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



INDEX OF SHEETS

1. COVER SHEET
2. PLAN MAP
3. BUFFER AND BANK CROSS SECTION
4. PROFILE ALONG DISTRIBUTION LINE
5. STRUCTURE DETAILS
6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa
	_____ 08/02/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2023. Pages or sheets covered by this seal: _____ All

ENGINEERING CLASS 2

DESIGNED BY	BEN REINHART	DATE	08/01/2023
DRAWN BY	BEN REINHART	DATE	08/01/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	08/02/2023
APPROVED BY			





COVER SHEET

FILE NAME	
DRAWING SET	SHEET 1 OF 6

PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD83, Iowa South, US Survey Feet)
 ● Located approx. 970-ft north of outlet, E side of ditch

Northing: 625150.611
 Easting: 2218841.530
 Elevation: 776.8




DATE
 DESIGNED BY BEN REINHART 08/01/23
 DRAWN BY BEN REINHART 08/01/23
 CHECKED BY ANDY CRAIG, PE, TSP 08/02/23
 APPROVED BY _____

PLAN MAP

Staking Control Points (NAD83, Iowa South, US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	Benchmark	625150.611	2218841.530	776.8
2	Control Structure	624316.136	2219331.534	764.2
3	Distribution Line	624364.476	2219242.834	764.9
4	Distribution Line	624437.267	2219172.084	765.7
5	Distribution Line	624510.543	2219101.629	766.7
6	Distribution Line	624611.767	2219040.911	767.2

Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 6" Non-Perforated CPT Outlet
- Proposed Water Control Structure
- Existing 6" CPT Main
- Benchmark
- Staking Points
- 2' Contours



Buffer Cross Section, See Sheet 3

425' of 6" CPT at 0.0% Grade


Existing 6" Tile



FILE NAME

DRAWING SET
 SHEET 2 OF 6

Buffer Cross Section



Legend

- - - Existing Ground Surface
- 6" CPT Distribution Line

DESIGNED BY	BEN REINHART	DATE	08/01/23
DRAWN BY	BEN REINHART		08/01/23
CHECKED BY	ANDY CRAIG, PE, TSP		08/02/23
APPROVED BY			

BUFFER AND BANK CROSS SECTION








FILE NAME	
DRAWING SET	
SHEET 3 OF 6	

LANDOWNER


LOCATION

SECTION 36 - T80N - R5W

Legend

-  All Season Water Table
-  Proposed Water Control Structure
-  Proposed 6" CPT Distribution Line
-  Existing Ground Surface
-  Lowest Crop Elevation

Profile Along Distribution Line



DATE
 DESIGNED BY BEN REINHART 08/01/23
 DRAWN BY BEN REINHART 08/01/23
 CHECKED BY ANDY CRAIG, PE, TSP 08/02/23
 APPROVED BY _____

PROFILE ALONG DISTRIBUTION LINE




FILE NAME

DRAWING SET
 SHEET 4 OF 6


LANDOWNER

LOCATION

SECTION 36 - T80N - R5W




TYPICAL SECTION




- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 6 in.	1	IA-21, IA-26, CPS-587
6" Non-perforated CPT (ft)	40	IA-21, IA-45
6" Perforated CPT (ft) Buffer Tile Line	425	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers



PLAN



IN-LINE CONTROL STRUCTURE

DATE 08/01/23
DESIGNED BY BEN REINHART
DRAWN BY BEN REINHART
CHECKED BY ANDY CRAIG, PE, TSP
APPROVED BY

3 CHAMBER STRUCTURE DETAIL



FILE NAME
DRAWING SET
SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE
 DESIGNED BY BEN REINHART 08/01/23
 DRAWN BY BEN REINHART 08/01/23
 CHECKED BY ANDY CRAIG, PE, TSP 08/02/23
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 36 - T80N - R5W


SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 33 - T79N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



INDEX OF SHEETS

1. COVER SHEET
2. PLAN MAP
3. BUFFER AND BANK CROSS SECTION
4. PROFILE ALONG DISTRIBUTION LINE
5. WEST STRUCTURE DETAILS
6. EAST STRUCTURE DETAILS
7. CONSTRUCTION NOTES

	<p>I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa</p>
	<p style="text-align: right;"><i>Andy J. Craig</i> _____ 07/28/2023</p> <p>Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2023. Pages or sheets covered by this seal: _____ All _____</p>

ENGINEERING CLASS 2

DESIGNED BY	BEN REINHART	DATE	07/28/2023
DRAWN BY	BEN REINHART	DATE	07/28/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	07/28/2023
APPROVED BY			




COVER SHEET

FILE NAME

DRAWING SET


SHEET 1 OF 7

Benchmark:
 Top of Lath Hub (NAD83, Iowa South, US Survey Feet)
 Northing: 590861.645
 Easting: 2238550.906
 Elevation: 669.6



Staking Control Points (NAD83, Iowa South, US Survey Feet)

Point	Description	Northing	Easting	Elevation
1	Benchmark	590861.645	2238550.906	669.6
2	West Control Structure	590920.169	2238503.338	668.1
3	East Control Structure	590607.487	2238866.146	668.2
4	Distribution Line	590850.429	2238580.209	668.5
5	Distribution Line	590781.315	2238657.650	668.7
6	Distribution Line	590714.845	2238737.377	668.8
7	Distribution Line	590517.037	2238977.877	668.8
8	Distribution Line	590451.777	2239058.598	668.7
9	Distribution Line	590386.977	2239139.689	668.5
10	Distribution Line	590323.559	2239221.782	668.3
11	Distribution Line	590271.069	2239311.334	667.6
12	Distribution Line	590181.506	2239446.671	666.1




Legend

- Existing 8" CPT Main
- Existing 6" CPT Main
- Proposed 8" Non-Perforated CPT Connection
- Proposed 10" Non-Perforated CPT
- Proposed 10" CMP Outlet
- Proposed 6" Non-Perforated CPT
- Proposed 6" CMP Outlet
- Proposed 6" Perforated CPT Distribution Line
- Proposed Water Control Structure
- Benchmark
- ⊗ Staking Points
- 2' Contours

PLAN MAP



Buffer Cross Section



Legend

- - - Existing Ground Surface
- 6" CPT Distribution Line

BUFFER AND BANK CROSS SECTION



FILE NAME

By


DRAWING SET
SHEET 3 OF 7

DATE
DESIGNED BY BEN REINHART 07/28/23
DRAWN BY BEN REINHART 07/28/23
CHECKED BY ANDY CRAIG, PE, TSP 07/28/23
APPROVED BY _____

LANDOWNER

LOCATION

SECTION 33 - T79N - R4W




DATE 07/28/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

PROFILE ALONG DISTRIBUTION LINE





FILE NAME
 B
 DRAWING SET
 SHEET 4 OF 7



TYPICAL SECTION


QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 10 in.	1	IA-21, IA-26, CPS-587
10" Non-perforated CPT (ft)	20	IA-21, IA-45
10" CMP Outlet with Rodent Guard	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	1180	IA-21, IA-45, IA-46
6" Non-perforated CPT (ft) Buffer Tile Line (see Plan Map, Pg 2)	20	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587
8" Non-perforated CPT (ft) Connection Tile (see Plan Map, Pg 2)	40	IA-21, IA-45

*Quantities Do Not Include Couplers



PLAN

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.




IN-LINE CONTROL STRUCTURE

DATE 07/28/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY



3 CHAMBER STRUCTURE DETAIL (WEST)



FILE NAME
 DRAWING SET
 SHEET 5 OF 7




TYPICAL SECTION



PLAN

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.



IN-LINE CONTROL STRUCTURE

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 6 in.	1	IA-21, IA-26, CPS-587
6" Non-perforated CPT (ft)	20	IA-21, IA-45
6" CMP Outlet with Rodent Guard	20	IA-604, IA-620
Buffer Tile Line Quantities Listed on West Structure Detail, Pg 5	-	-
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers

DATE 07/28/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

3 CHAMBER STRUCTURE DETAIL (EAST)



FILE NAME

DRAWING SET
SHEET 6 OF 7

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE
 DESIGNED BY BEN REINHART 07/28/23
 DRAWN BY BEN REINHART 07/28/23
 CHECKED BY ANDY CRAIG, PE, TSP 07/28/23
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 7 OF 7

LANDOWNER

LOCATION

SECTION 33 - T79N - R4W


SATURATED BUFFER CONSTRUCTION PLANS

MUSCATINE CO, IOWA
SECTION 12 - T78N - R1E



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



INDEX OF SHEETS

1. COVER SHEET
2. PLAN MAP
3. BUFFER AND BANK CROSS SECTION
4. PROFILE ALONG DISTRIBUTION LINE
5. STRUCTURE DETAILS
6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 7/28/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: _____ All

ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	7/27/2023
DRAWN BY	ANDREW MACKRILL	DATE	7/27/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	7/28/2023
APPROVED BY			



COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 6

Staking Control Points(NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	587427.9	2382937.6	715.3
2	Distribution Line	587408.7	2382930.5	715.5
3	Distribution Line	587149.2	2382903.3	715.4
4	Distribution Line	586774.0	2382874.6	716.1
5	Distribution Line	586655.9	2382846.4	716.2
6	Distribution Line	586537.2	2382831.0	716.5
7	Benchmark	586740.8	2382825.0	715.3

PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 586740.8
 Easting: 2382825.0
 Elevation: 715.3

Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 15" Non-Perforated CPT
- Existing 15" CPT Main
- Proposed Water Control Structure
- 2' Contours
- Benchmark
- Staking Point

LANDOWNER

LOCATION

SECTION 12 - T78N - R1E



DATE 7/27/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY


PLAN MAP



FILE NAME

DRAWING SET
 SHEET 2 OF 6

Buffer Cross-Section



Legend

- - - Existing Ground Surface
- 6" CPT Distribution Line

DESIGNED BY	ANDREW MACKRILL	DATE	7/27/23
DRAWN BY	ANDREW MACKRILL		7/27/23
CHECKED BY	ANDY CRAIG, PE, TSP		7/28/23
APPROVED BY			

BUFFER AND BANK CROSS SECTION




FILE NAME

DRAWING SET
SHEET 3 OF 6



LANDOWNER

LOCATION

SECTION 12 - T78N - R1E



Legend

	All Season Water Table
	Proposed Water Control Structure
	Proposed 6" CPT Distribution Line
	Existing Ground Surface
	Lowest Farmed Elevation

DESIGNED BY ANDREW MACKRILL	DATE 7/27/23
DRAWN BY ANDREW MACKRILL	7/27/23
CHECKED BY ANDY CRAIG, PE, TSP	7/28/23
APPROVED BY	

PROFILE ALONG DISTRIBUTION LINE




FILE NAME

DRAWING SET
SHEET 4 OF 6


LANDOWNER

LOCATION

SECTION 12 - T78N - R1E




TYPICAL SECTION




- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 15 in.	1	IA-21, IA-26, CPS-587
15" Non-perforated Pipe (ft)	20	IA-21, IA-45
15" CMP Outlet Pipe With Rodent Guard (ft)	30	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	900	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers



PLAN



IN-LINE CONTROL STRUCTURE

DATE
DESIGNED BY ANDREW MACKRILL 7/27/23
DRAWN BY ANDREW MACKRILL 7/27/23
CHECKED BY ANDY CRAIG, PE, TSP 7/28/23
APPROVED BY

3 CHAMBER STRUCTURE DETAIL



FILE NAME
DRAWING SET
SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE
 DESIGNED BY ANDREW MACKRILL 7/27/23
 DRAWN BY ANDREW MACKRILL 7/27/23
 CHECKED BY ANDY CRAIG, PE, TSP 7/28/23
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 12 - T78N - R1E


SATURATED BUFFER CONSTRUCTION PLANS

MUSCATINE CO, IOWA
SECTION 12 - T78N - R1E



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 7/28/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: All

ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	7/27/2023
DRAWN BY	ANDREW MACKRILL	DATE	7/27/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	7/28/2023
APPROVED BY			



COVER SHEET

FILE NAME

DRAWING SET
SHEET 1 OF 6

Staking Control Points(NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	587877.2	2382845.4	715.5
2	Distribution Line	587162.9	2382828.2	714.8
3	Distribution Line	587033.1	2382837.7	715.8
4	Distribution Line	586775.6	2382807.3	716.4
5	Distribution Line	586611.4	2382774.7	716.3
6	Distribution Line	586440.0	2382757.7	716.5
7	Benchmark	586740.8	2382825.0	715.3

PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 586740.8
 Easting: 2382825.0
 Elevation: 715.3

Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 6" Non-Perforated CPT
- Proposed 6" CMP Outlet
- Existing 6" CPT Main
- Proposed Water Control Structure
- 2' Contours
- Benchmark
- Staking Point

LANDOWNER

LOCATION

SECTION 12 - T78N - R1E



DATE 7/27/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY


PLAN MAP



FILE NAME

DRAWING SET
 SHEET 2 OF 6

Buffer Cross-Section



DESIGNED BY	ANDREW MACKRILL	DATE	7/27/23
DRAWN BY	ANDREW MACKRILL		7/27/23
CHECKED BY	ANDY CRAIG, PE, TSP		7/28/23
APPROVED BY			


BUFFER AND BANK CROSS SECTION








FILE NAME	
DRAWING SET	SHEET 3 OF 6

LANDOWNER		LOCATION	SECTION 12 - T78N - R1E
-----------	--	----------	-------------------------

Profile Along Distribution Line



Legend

-  All Season Water Table
-  Proposed Water Control Structure
-  Proposed 6" CPT Distribution Line
-  Existing Ground Surface
-  Lowest Farmed Elevation

DESIGNED BY	ANDREW MACKRILL	DATE	7/27/23
DRAWN BY	ANDREW MACKRILL		7/27/23
CHECKED BY	ANDY CRAIG, PE, TSP		7/28/23
APPROVED BY			


PROFILE ALONG DISTRIBUTION LINE




FILE NAME

DRAWING SET
SHEET 4 OF 6

LANDOWNER	LOCATION	SECTION 12 - T78N - R1E
-----------	----------	-------------------------




TYPICAL SECTION




- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 6 in.	1	IA-21, IA-26, CPS-587
6" Non-perforated Pipe (ft)	30	IA-21, IA-45
6" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	845	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers



PLAN



IN-LINE CONTROL STRUCTURE

DATE
DESIGNED BY ANDREW MACKRILL 7/27/23
DRAWN BY ANDREW MACKRILL 7/27/23
CHECKED BY ANDY CRAIG, PE, TSP 7/28/23
APPROVED BY

3 CHAMBER STRUCTURE DETAIL



FILE NAME
DRAWING SET
SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE
 DESIGNED BY ANDREW MACKRILL 7/27/23
 DRAWN BY ANDREW MACKRILL 7/27/23
 CHECKED BY ANDY CRAIG, PE, TSP 7/28/23
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 12 - T78N - R1E


SATURATED BUFFER CONSTRUCTION PLANS

MUSCATINE CO, IOWA
SECTION 12 - T78N - R1E



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa
	_____ 7/28/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: _____ All

ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	7/28/2023
DRAWN BY	ANDREW MACKRILL	DATE	7/28/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	7/28/2023
APPROVED BY			



COVER SHEET

FILE NAME	
DRAWING SET	SHEET 1 OF 6

Staking Control Points(NAD 1983 State Plane Iowa South US Survey Feet)

Point	Description	Northing	Easting	Elevation
1	WCS	586201.4	2832737.3	717.1
2	Distribution Line	586330.1	2832728.1	716.4
3	Distribution Line	586041.0	2382832.0	717.1
4	Distribution Line	585953.4	2382893.0	717.1
5	Distribution Line	585851.2	2382963.8	717.3
6	Distribution Line	585804.8	2382988.1	717.3
7	Benchmark	586740.8	2382825.0	715.3

DATE 7/28/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

PLAN MAP

PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 586740.8
 Easting: 2382825.0
 Elevation: 715.3

Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 8" Non-Perforated CPT
- Proposed 8" CMP Outlet
- Existing 8" CPT Main
- Proposed Water Control Structure
- 2' Contours
- Benchmark
- Staking Point


The Benchmark is shared with 2 other projects and sits 537 Ft. North of the outlet



FILE NAME

DRAWING SET SHEET 2 OF 6

Buffer Cross-Section



Legend

- Existing Ground Surface
- 6" CPT Distribution Line

DESIGNED BY	ANDREW MACKRILL	DATE	7/28/23
DRAWN BY	ANDREW MACKRILL		7/28/23
CHECKED BY	ANDY CRAIG, PE, TSP		7/28/23
APPROVED BY			


BUFFER AND BANK CROSS SECTION



FILE NAME	
DRAWING SET	SHEET 3 OF 6

LANDOWNER		LOCATION	SECTION 12 - T78N - R1E
-----------	--	----------	-------------------------

Profile Along Distribution Line



Legend

- All Season Water Table
- Proposed Water Control Structure
- Proposed 6" CPT Distribution Line
- Existing Ground Surface
- Lowest Farmed Elevation

DATE
 DESIGNED BY ANDREW MACKRILL 7/28/23
 DRAWN BY ANDREW MACKRILL 7/28/23
 CHECKED BY ANDY CRAIG, PE, TSP 7/28/23
 APPROVED BY _____


PROFILE ALONG DISTRIBUTION LINE




FILE NAME

DRAWING SET
 SHEET 4 OF 6

LANDOWNER	LOCATION	SECTION 12 - T78N - R1E
------------------	-----------------	--------------------------------




TYPICAL SECTION




- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 8 in.	1	IA-21, IA-26, CPS-587
8" Non-perforated Pipe (ft)	30	IA-21, IA-45
8" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	600	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers



PLAN



IN-LINE CONTROL STRUCTURE

DATE 7/28/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

3 CHAMBER STRUCTURE DETAIL



FILE NAME
 DRAWING SET
 SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE 7/28/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 12 - T78N - R1E


DENITRIFYING BIOREACTOR CONSTRUCTION PLANS

CEDAR COUNTY, IOWA
SECTION 4- T79N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



INDEX OF SHEETS

1. COVER SHEET
2. PLAN MAP
3. CROSS SECTION VIEW
4. PROFILE ALONG CENTERLINE
5. BIOREACTOR DETAIL
6. STRUCTURE DETAIL
7. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 09/14/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2023. Pages or sheets covered by this seal: <u> All </u>

ENGINEERING CLASS 4

DESIGNED BY	BEN REINHART	DATE	09/12/2023
DRAWN BY	BEN REINHART	DATE	09/12/2023
CHECKED BY	ANDY CRAIG, PE	DATE	09/14/2023
APPROVED BY	_____		





COVER SHEET

FILE NAME _____

DRAWING SET

SHEET 1 OF 7

Benchmark:
 Top of Lath Hub (NAD83, Iowa South, USFt)
 Northing: 618996.428
 Easting: 2234559.322
 Elevation: 726.5













Staking Control Points (NAD83, Iowa South, USFt)				
Point	Description	Northing	Easting	Elevation
1	Benchmark	618996.428	2234559.322	726.5
2	Inlet WCS (3-chamber)	619105.532	2234661.239	723.6
3	Outlet WCS (2-chamber)	619020.753	2234561.286	723.9
4	Northwest Corner BID	619034.622	2234559.873	723.3
5	Northeast Corner BID	619084.237	2234646.697	724.2
6	Southeast Corner BID	619062.531	2234659.100	724.8
7	Southwest Corner BID	619012.916	2234572.277	724.4

DATE 09/12/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY _____

PLAN MAP

Legend

-  Existing 10" CPT Main
-  Proposed 10" Non-Perf CPT Main
-  Proposed 6" Non-Perf CPT
-  Proposed 6" Perf CPT
-  Bioreactor Footprint
-  Staking Points
-  Water Control Structure
-  Benchmark
-  2-Ft Contours

Approx. Grade 0.8%
 to existing outlet.



FILE NAME

DRAWING SET
 SHEET 2 OF 7

Bioreactor Cross Section

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface

Grade backfill with existing ground to not create a channelized flow path


Recommend placing approximately 1 ft. of plastic liner outside of chamber and hold in place with stakes

Place geotextile fabric at woodchip/soil interface. Elev. 723.3

Ensure positive drainage away from the bioreactor to prevent ponding or creation of flow paths for surface water

Existing ground surface

4 mil plastic liner to line bioreactor chamber




DESIGNED BY	BEN REINHART	DATE	09/12/23
DRAWN BY	BEN REINHART	DATE	09/12/23
CHECKED BY	ANDY CRAIG, PE	DATE	09/14/23
APPROVED BY			

CROSS SECTION VIEW



FILE NAME	
DRAWING SET	
SHEET 3 OF 7	

Profile Along Centerline



- Legend**
- Earth Fill
 - Woodchip Media
 - Existing Ground Surface
 - Lowest Crop Elevation
 - Plastic Liner
 - Geotextile Fabric
 - 6" Non-Perforated CPT Pipe
 - 6" Perforated CPT Manifold Pipe
 - Water Control Structure
 - Stoplogs

DATE	09/12/23
DESIGNED BY	BEN REINHART
DRAWN BY	BEN REINHART
CHECKED BY	ANDY CRAIG, PE
APPROVED BY	


PROFILE ALONG CENTERLINE



FILE NAME	c	8
DRAWING SET	SHEET 4 OF 7	

LANDOWNER	LOCATION	SECTION 4 - T79N - R4W
-----------	----------	------------------------

ELEVATION





PLAN

- NOTES:
- All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
 - Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
 - Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1-inch long by 1/2-inch thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
 - Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
 - Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
 - See Plan Map for benchmark coordinates.

Legend

- Earth Fill
- Woodchip Media
- Existing 10" Perf CPT Main
- Proposed 10" Non-Perf CPT
- Proposed 6" Non-Perf CPT
- Proposed 6" Perf CPT
- Plastic Liner
- Geotextile Fabric
- Existing Ground Surface
- Bioreactor Footprint

SECTION A-A



DATE	09/12/23
DESIGNED BY BEN REINHART	
DRAWN BY BEN REINHART	
CHECKED BY ANDY CRAIG, PE	
APPROVED BY	


BIOREACTOR DETAIL




FILE NAME	
DRAWING SET	
SHEET 5 OF 7	

LANDOWNER		LOCATION	SECTION 4 - T79N - R4W
-----------	--	----------	------------------------

TYPICAL SECTION UPSTREAM 3-COMPARTMENT STRUCTURE



TYPICAL SECTION DOWNSTREAM 2-COMPARTMENT STRUCTURE




NOTES:

1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, on all lines: upstream, downstream and center. Pipe must be PVC, dual-wall CPT, or CMP.
2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745. Check valve must conform to ASTM D 3034 with SDR35 pipe or stronger.
3. Couplings between the water control structures and the non-perforated tile must be watertight.
4. Stop boards must provide must tight seals under a minimum of 1 foot pressure head (except notched board).
5. Appropriately mark bioreactor perimeter to avoid vehicle, implement, or livestock traffic.
6. Place structure and pipe coupler on a stable base. A stable base may be compacted earth, compacted fill sand, or a concrete pad. Extend the stable base no less than 1 foot beyond structure.
7. Excavated material placed around structure and pipes shall be hand compacted in 4" lifts.

DETAIL 1

Cut 1" Notch In Bottom Of The Bottom Board On The Downstream Structure




Legend

- Earth Fill
- Existing 10" Perf CPT Main
- Proposed 10" Non-Perf CPT
- Proposed 6" Non-Perf CPT
- Existing Ground
- Control Structure Stoplogs

IN-LINE CONTROL STRUCTURES

Side Port Is On The (Circle One) Left/Right Side Of Structure, Looking Downstream



QUANTITIES*	
Water Control Structure, 3 Chamber (H ₁ = 6 ft. d ₁ = 10 in. d ₂ = 6 in.)	1
Water Control Structure, 2 Chamber (H ₂ = 8 ft. d ₃ = 6 in.)	1
10" Non-perforated Pipe (ft)	40
6" Non-perforated Pipe (ft)	125
6" Perforated CPT (ft)	50
6" End Cap (each)	4
Wood Chips (cu. yd.)	510
4 Mil Plastic (sq. yd.)**	484
Geotextile (sq. yd.)	278
Excavation (cu. yd.)	602
Earth Fill (cu. yd.)	186
6" Backflow Check Valve (each)	1

* Quantities do not include tile/pipe couplers or extra material for geotextile/plastic overlap
 ** Accounts for 1 ft. overhang around perimeter

DATE 09/12/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY

STRUCTURE DETAIL



FILE NAME
 DRAWING SET
 SHEET 6 OF 7

CONSTRUCTION NOTES

1. Tile elevations are based on Maverick tile probe depths and are to be considered accurate within margin of error of the instrument.
2. If any surface inlets are currently attached to the tile main or plan to be in the future, they shall be replaced with water quality inlets to minimize trash entry into the tile line before construction of the bioreactor begins.
3. Avoid excessive disturbance of any buffers or grassed water ways during construction. However, if re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded within 14 days according to NRCS Conservation Practice Standard IA-342 Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
4. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion.
5. All carbon media to be placed in the bioreactor shall come from an ESE approved vendor or approved with ESE staff prior to transportation and placement.
6. Contact an ESE representative for inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the bioreactor chamber and tile line trenches
 - b. After placing the water control structures and bioreactor manifolds
 - c. After placement of carbon media, before backfilling with soil
 - d. After connections to existing tile and final grading
7. Any product planned for use in construction must be approved by ESE prior to construction. Save and provide documentation to an ESE representative of all materials used in construction including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths
 - b. Photos and invoices for quantity and quality of woodchips/carbon media
 - c. Photos and invoices or product information to detail quantity and quality of plastic and geotextile fabric
 - d. Photos and invoices or product information for water control structures
8. Construction tolerances are ± 0.5 ft on bioreactor chamber dimensions, and ± 0.1 ft. on all elevations. Outlet WCS sump (bottom) must be below the elevation of the bioreactor chamber at the outlet end. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by a representative from ESE and will be noted in the as-built plan.
9. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.
10. All work shall be performed according to the IA construction and practice specifications in the table below.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-95	Geotextile
IA-605	Denitrifying Bioreactor
IA-620	Underground Outlet

DATE: 09/12/23
 DESIGNED BY: BEN REINHART
 DRAWN BY: BEN REINHART
 CHECKED BY: ANDY CRAIG, PE
 APPROVED BY:

CONSTRUCTION NOTES



FILE NAME:
 DRAWING SET:
 SHEET 7 OF 7


DENITRIFYING BIOREACTOR CONSTRUCTION PLANS

CEDAR COUNTY, IOWA
SECTION 4- T79N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. CROSS SECTION VIEW
 4. PROFILE ALONG CENTERLINE
 5. BIOREACTOR DETAIL
 6. STRUCTURE DETAIL
 7. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 09/14/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2023. Pages or sheets covered by this seal: <u> </u> All

ENGINEERING CLASS 4

DESIGNED BY	BEN REINHART	DATE	09/14/2023
DRAWN BY	BEN REINHART	DATE	09/14/2023
CHECKED BY	ANDY CRAIG, PE	DATE	09/14/2023
APPROVED BY	_____		




COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 7

Benchmark:
 Top of Lath Hub (NAD83, Iowa South, USFt)
 Northing: 618996.428
 Easting: 2234559.322
 Elevation: 726.5



Staking Control Points (NAD83, Iowa South, USFt)				
Point	Description	Northing	Easting	Elevation
1	Benchmark	618996.428	2234559.322	726.5
2	Inlet WCS (3-chamber)	619119.514	2234392.012	724.1
3	Outlet WCS (2-chamber)	619016.535	2234414.909	723.8
4	Northwest Corner BID	619105.941	2234359.858	724.2
5	Northeast Corner BID	619116.421	2234382.556	724.1
6	Southeast Corner BID	619025.632	2234424.477	723.6
7	Southwest Corner BID	619015.152	2234401.779	723.9










DATE 09/14/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY _____


PLAN MAP



FILE NAME _____
 DRAWING SET _____
 SHEET 2 OF 7

Legend

-  Existing 12" CPT Main
-  Proposed 12" Non-Perf CPT Main
-  Proposed 6" Non-Perf CPT
-  Proposed 6" Perf CPT
-  Bioreactor Footprint
-  Staking Points
-  Water Control Structure
-  Benchmark
-  2-Ft Contours




Bioreactor Cross Section

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface

Grade backfill with existing ground to not create a channelized flow path

Place geotextile fabric at woodchip/soil interface.
Elev. 723.5



Ensure positive drainage away from the bioreactor to prevent ponding or creation of flow paths for surface water

Existing ground surface

Recommend placing approximately 1 ft. of plastic liner outside of chamber and hold in place with stakes

4 mil plastic liner to line bioreactor chamber


DESIGNED BY	BEN REINHART	DATE	09/14/23
DRAWN BY	BEN REINHART	DATE	09/14/23
CHECKED BY	ANDY CRAIG, PE	DATE	09/14/23
APPROVED BY			

CROSS SECTION VIEW



FILE NAME	a
DRAWING SET	SHEET 3 OF 7

LANDOWNER	LOCATION	SECTION 4 - T79N - R4W
-----------	-------	----------	------------------------




DATE 09/14/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY

PROFILE ALONG CENTERLINE



FILE NAME
 DRAWING SET
 SHEET 4 OF 7



PLAN

SECTION A-A

Legend

- Earth Fill
- Woodchip Media
- Existing 12" Perf CPT Main
- Proposed 12" Non-Perf CPT
- Proposed 6" Non-Perf CPT
- Proposed 6" Perf CPT
- Plastic Liner
- Geotextile Fabric
- Existing Ground Surface
- Bioreactor Footprint

DATE	09/14/23
DESIGNED BY BEN REINHART	09/14/23
DRAWN BY BEN REINHART	09/14/23
CHECKED BY ANDY CRAIG, PE	09/14/23
APPROVED BY	

BIOREACTOR DETAIL

ELEVATION

NOTES:

1. All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
2. Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
3. Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1-inch long by 1/2-inch thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
4. Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
5. Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
6. See Plan Map for benchmark coordinates.




FILE NAME


DRAWING SET SHEET 5 OF 7

LANDOWNER	LOCATION	SECTION 4 - T79N - R4W
-----------	----------	------------------------

TYPICAL SECTION UPSTREAM 3-COMPARTMENT STRUCTURE



TYPICAL SECTION DOWNSTREAM 2-COMPARTMENT STRUCTURE



QUANTITIES*	
Water Control Structure, 3 Chamber (H ₁ = 6 ft. d ₁ = 12 in. d ₂ = 6 in.)	1
Water Control Structure, 2 Chamber (H ₂ = 6 ft. d ₃ = 6 in.)	1
12" Non-perforated Pipe (ft)	40
6" Non-perforated Pipe (ft)	70
6" Perforated CPT (ft)	50
6" End Cap (each)	3
Wood Chips (cu. yd.)	438
4 Mil Plastic (sq. yd.)**	460
Geotextile (sq. yd.)	278
Excavation (cu. yd.)	491
Earth Fill (cu. yd.)	139
6" Backflow Check Valve (each)	1


NOTES:

1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, on all lines: upstream, downstream and center. Pipe must be PVC, dual-wall CPT, or CMP.
2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745. Check valve must conform to ASTM D 3034 with SDR35 pipe or stronger.
3. Couplings between the water control structures and the non-perforated tile must be watertight.
4. Stop boards must provide must tight seals under a minimum of 1 foot pressure head (except notched board).
5. Appropriately mark bioreactor perimeter to avoid vehicle, implement, or livestock traffic.
6. Place structure and pipe coupler on a stable base. A stable base may be compacted earth, compacted fill sand, or a concrete pad. Extend the stable base no less than 1 foot beyond structure.
7. Excavated material placed around structure and pipes shall be hand compacted in 4" lifts.

* Quantities do not include tile/pipe couplers or extra material for geotextile/plastic overlap
 ** Accounts for 1 ft. overhang around perimeter

DETAIL 1

Cut 1" Notch In Bottom Of The Bottom Board On The Downstream Structure




Legend

- Earth Fill
- Existing 12" Perf CPT Main
- Proposed 12" Non-Perf CPT
- Proposed 6" Non-Perf CPT
- Existing Ground
- Control Structure Stoplogs

IN-LINE CONTROL STRUCTURES

Side Port Is On The (Circle One) Left, Right Side Of Structure, Looking Downstream



DATE 09/14/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY

STRUCTURE DETAIL



FILE NAME
 c
 DRAWING SET
 SHEET 6 OF 7

CONSTRUCTION NOTES

1. Tile elevations are based on Maverick tile probe depths and are to be considered accurate within margin of error of the instrument.
2. If any surface inlets are currently attached to the tile main or plan to be in the future, they shall be replaced with water quality inlets to minimize trash entry into the tile line before construction of the bioreactor begins.
3. Avoid excessive disturbance of any buffers or grassed water ways during construction. However, if re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded within 14 days according to NRCS Conservation Practice Standard IA-342 Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
4. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion.
5. All carbon media to be placed in the bioreactor shall come from an ESE approved vendor or approved with ESE staff prior to transportation and placement.
6. Contact an ESE representative for inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the bioreactor chamber and tile line trenches
 - b. After placing the water control structures and bioreactor manifolds
 - c. After placement of carbon media, before backfilling with soil
 - d. After connections to existing tile and final grading
7. Any product planned for use in construction must be approved by ESE prior to construction. Save and provide documentation to an ESE representative of all materials used in construction including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths
 - b. Photos and invoices for quantity and quality of woodchips/carbon media
 - c. Photos and invoices or product information to detail quantity and quality of plastic and geotextile fabric
 - d. Photos and invoices or product information for water control structures
8. Construction tolerances are ± 0.5 ft on bioreactor chamber dimensions, and ± 0.1 ft. on all elevations. Outlet WCS sump (bottom) must be below the elevation of the bioreactor chamber at the outlet end. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by a representative from ESE and will be noted in the as-built plan.
9. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.
10. All work shall be performed according to the IA construction and practice specifications in the table below.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-95	Geotextile
IA-605	Denitrifying Bioreactor
IA-620	Underground Outlet

DATE 09/14/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

 DRAWING SET
 SHEET 7 OF 7

DENITRIFYING BIOREACTOR CONSTRUCTION PLANS

CEDAR COUNTY, IOWA
SECTION 06- T79N - R03W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. CROSS SECTION VIEW
 4. PROFILE ALONG CENTERLINE
 5. BIOREACTOR DETAIL
 6. STRUCTURE DETAIL
 7. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	9/5/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: All

ENGINEERING CLASS 3

DESIGNED BY	ANDY MACKRILL, TSP	DATE	9/5/2023
DRAWN BY	ANDY MACKRILL, TSP	DATE	9/5/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	9/11/2023
APPROVED BY			




COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 7

Benchmark:
 Top of Outlet (NAD 1983 State
 Plane Iowa South US Survey Feet)
 Northing: 619551.1
 Easting: 2259833.2
 Elevation: 735.5



Staking Control Points (NAD 1983 State Plane Iowa South US SURVEY FEET)				
Point	Description	Northing	Easting	Elevation
1	Southeast Corner BID	619465.6	2259892.4	740.6
2	Southwest Corner BID	619465.3	2259872.3	740.6
3	Northwest Corner BID	619545.5	2259871.4	741.0
4	Northeast Corner BID	619545.7	2259891.4	740.6
5	Inlet WCS (3-chamber)	619565.8	2259894.3	740.8
6	Outlet WCS (2-chamber)	619467.0	2259867.2	740.5
7	Benchmark	619551.1	2259833.2	735.5

New 10" CMP Outlet
 With Rodent Guard

Approx. Grade 0.5%
 Connecting to
 Existing Outlet.

Legend	
	Proposed 6" Perforated CPT
	Proposed 6" Non-Perforated CPT
	Existing 10" CPT Main
	Proposed 10" Non-Perf CPT Main
	Proposed 10" CMP Outlet
	Bioreactor Footprint
	Water Control Structure
	Benchmark
	2 Foot Contours

DATE 9/5/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY _____


PLAN MAP








FILE NAME

DRAWING SET
 SHEET 2 OF 7

Cross-Section



Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface

DESIGNED BY	ANDY MACKRILL	DATE	9/5/23
DRAWN BY	ANDY MACKRILL	DATE	9/5/23
CHECKED BY	ANDY CRAIG	DATE	9/15/23
APPROVED BY			

CROSS SECTION VIEW



FILE NAME

DRAWING SET
SHEET 3 OF 7

LANDOWNER

LOCATION

SECTION 06 - T79N - R03W









Profile Along Centerline


Grade backfill with existing ground to not create a channelized flow path

Inlet WCS Lid Elev. 742.0

Lowest Cropped Elev 741.5

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface
-  6" Non-Perforated CPT Pipe
-  Water Control Structure
-  6" Perforated CPT Manifold Pipe



Existing ground surface

Place geotextile fabric at woodchip/soil interface.

Elevation

Inlet WCS stoplog Elev. 739.3

Inlet WCS Sump Elev. 736.0

6" perforated CPT distribution manifold

Sta. 0+10 Elev. 735.8

Outlet WCS Lid Elev. 741.4

Mound backfill approximately 1 ft. to allow for settling and shed water

Earth fill

Woodchip fill

Inlet WCS stoplog Elev. 738.0

6" perforated CPT collection manifold

Outlet WCS SUMP ELEV. 735.4

Sta. 0+90 Elev. 735.6

Station


DATE 9/5/23
 DESIGNED BY ANDY MACKFILL
 DRAWN BY ANDY MACKFILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

PROFILE ALONG CENTERLINE



FILE NAME

DRAWING SET SHEET 4 OF 7




Legend

	Earth Fill
	Woodchip Media
	Proposed 6" Perforated CPT
	Proposed 6" Non-Perforated CPT
	Existing 10" CPT Main
	Proposed 10" Non-Perforated CPT
	Proposed 10" CMP Outlet
	Plastic Liner
	Geotextile Fabric
	Existing Ground Surface
	Bioreactor Footprint



NOTES:

1. All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
2. Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
3. Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1" long by 1/2" thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
4. Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
5. Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
6. See Plan Map for benchmark coordinates.



ELEVATION


DATE	9/5/23	DESIGNED BY	ANDY MACKRILL	DATE	9/5/23
		DRAWN BY	ANDY MACKRILL	CHECKED BY	ANDY CRAIG
				APPROVED BY	
BIOREACTOR DETAIL					
FILE NAME					
DRAWING SET					
SHEET 5 OF 7					



Legend


- Earth Fill
- 6" Non-Perforated CPT
- Existing 10" CPT Main
- Proposed 10" CPT Main
- Existing Ground Surface

TYPICAL SECTION UPSTREAM STRUCTURE



TYPICAL SECTION DOWNSTREAM STRUCTURE

Side Port Is On The (Circle One) Left / Right Side Of Structure, Looking Downstream



IN-LINE CONTROL STRUCTURES

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, on all lines: upstream, downstream and center. Pipe must be PVC, dual-wall CPT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745. Check valve must conform to ASTM D 3034 with SDR35 pipe or stronger.
 3. Couplings between the water control structures and the non-perforated tile must be watertight.
 4. Stop boards must provide must tight seals under a minimum of 1 foot pressure head (except notched board).
 5. Appropriately mark bioreactor perimeter to avoid vehicle, implement, or livestock traffic.
 6. Place structure and pipe coupler on a stable base. A stable base may be compacted earth, compacted fill sand, or a concrete pad. Extend the stable base no less than 1 foot beyond structure.
 7. Excavated material placed around structure and pipes shall be hand compacted in 4" lifts.

QUANTITIES*	
Water Control Structure, 3 Chamber $H_1 = 6$ ft. $d_1 = 10$ in. $d_2 = 6$ in.	1
Water Control Structure, 2 Chamber $H_2 = 6$ ft. $d_3 = 6$ in.	1
10" Non-perforated Pipe (ft)	40
10" CMP Outlet Pipe With Rodent Guard (ft)	20
6" Non-perforated Pipe (ft)	120
6" Perforated CPT (ft)	40
6" End Cap	2
Wood Chips (cu. yd.)	268
4 Mil Plastic (sq. yd.)**	318
Geotextile (sq. yd.)	178
Excavation (cu. yd.)	320
Earth Fill (cu. yd.)	107
6" Backflow Check Valve	1

* Quantities do not include tile/pipe couplers or extra material for geotextile/plastic overlap
 ** Accounts for 1 ft. overhang around perimeter

DATE 9/5/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

STRUCTURE DETAIL



FILE NAME
 DRAWING SET
 SHEET 6 OF 7

CONSTRUCTION NOTES

1. Tile elevations are based on Maverick tile probe depths and are to be considered accurate within margin of error of the instrument.
2. If any surface inlets are currently attached to the tile main or plan to be in the future, they shall be replaced with water quality inlets to minimize trash entry into the tile line before construction of the bioreactor begins.
3. Avoid excessive disturbance of any buffers or grassed water ways during construction. However, if re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded within 14 days according to NRCS Conservation Practice Standard IA-342 Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
4. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion.
5. All carbon media to be placed in the bioreactor shall come from an ESE approved vendor or approved with ESE staff prior to transportation and placement.
6. Contact an ESE representative for inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the bioreactor chamber and tile line trenches
 - b. After placing the water control structures and bioreactor manifolds
 - c. After placement of carbon media, before backfilling with soil
 - d. After connections to existing tile and final grading
7. Any product planned for use in construction must be approved by ESE prior to construction. Save and provide documentation to an ESE representative of all materials used in construction including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths
 - b. Photos and invoices for quantity and quality of woodchips/carbon media
 - c. Photos and invoices or product information to detail quantity and quality of plastic and geotextile fabric
 - d. Photos and invoices or product information for water control structures
8. Construction tolerances are ± 0.5 ft on bioreactor chamber dimensions, and ± 0.1 ft. on all elevations. Outlet WCS sump (bottom) must be below the elevation of the bioreactor chamber at the outlet end. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by a representative from ESE and will be noted in the as-built plan.
9. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.
10. All work shall be performed according to the IA construction and practice specifications in the table below.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-95	Geotextile
IA-605	Denitrifying Bioreactor
IA-620	Underground Outlet

DESIGNED BY	ANDY MACKRILL	DATE	9/5/23
DRAWN BY	ANDY MACKRILL		9/5/23
CHECKED BY	ANDY CRAIG		9/15/23
APPROVED BY			

CONSTRUCTION NOTES



FILE NAME	
DRAWING SET	
SHEET 7 OF 7	

LANDOWNER		LOCATION	SECTION 06 - T79N - R03W
-----------	--	----------	--------------------------

DENITRIFYING BIOREACTOR CONSTRUCTION PLANS

CEDAR COUNTY, IOWA
SECTION 06- T79N - R03W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. CROSS SECTION VIEW
 4. PROFILE ALONG CENTERLINE
 5. BIOREACTOR DETAIL
 6. STRUCTURE DETAIL
 7. CONSTRUCTION NOTES

ENGINEERING CLASS 3

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	9/15/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: <u>All</u>

DESIGNED BY	ANDY MACKRILL, TSP	DATE	9/5/2023
DRAWN BY	ANDY MACKRILL, TSP	DATE	9/5/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	9/15/2023
APPROVED BY			




COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 7

Benchmark:
 Top of Outlet (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 619820.4
 Easting: 2259799.3
 Elevation: 736.0



Staking Control Points (NAD 1983 State Plane Iowa South US SURVEY FEET)				
Point	Description	Northing	Easting	Elevation
1	Southeast Corner BID	619889.5	2259844.6	742.9
2	Southwest Corner BID	619877.3	2259828.7	742.9
3	Northwest Corner BID	619940.9	2259779.8	742.3
4	Northeast Corner BID	619953.1	2259795.7	742.5
5	Inlet WCS (3-chamber)	619863.7	2259842.9	742.8
6	Outlet WCS (2-chamber)	619937.1	2259778.7	742.1
7	Benchmark	619820.4	2259799.3	736.0










DATE 9/5/23
 DESIGNED BY ANDY MACKFILL
 DRAWN BY ANDY MACKFILL
 CHECKED BY ANDY CRAIG
 APPROVED BY _____

PLAN MAP

Approx. Grade 0.5%
 Connecting to
 Existing Outlet.

New 10" CMP Outlet
 With Rodent Guard

Legend


-  Proposed 6" Perforated CPT
-  Proposed 6" Non-Perforated CPT
-  Existing 10" CPT Main
-  Proposed 10" Non-Perf CPT Main
-  Proposed 10" CMP Outlet
-  Bioreactor Footprint
-  Water Control Structure
-  Benchmark
-  2 Foot Contours








FILE NAME

DRAWING SET
 SHEET 2 OF 7

Cross-Section



Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface

DATE
 DESIGNED BY ANDY MACKRILL 9/5/23
 DRAWN BY ANDY MACKRILL 9/5/23
 CHECKED BY ANDY CRAIG 9/15/23
 APPROVED BY _____

CROSS SECTION VIEW



FILE NAME
 80
 DRAWING SET
 SHEET 3 OF 7

LANDOWNER

LOCATION

SECTION 03 - T79N - R03W









Profile Along Centerline

Grade backfill with existing ground to not create a channelized flow path

Inlet WCS Lid Elev. 743.5

Lowest Cropped Elev 743.3

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface
-  6" Non-Perforated CPT Pipe
-  Water Control Structure
-  6" Perforated CPT Manifold Pipe

Existing ground surface

Outlet WCS Lid Elev. 743.2

Place geotextile fabric at woodchip/soil interface.

Mound backfill approximately 1 ft. to allow for settling and shed water

Elevation

Earth fill

Inlet WCS stoplog Elev. 741.3

Woodchip fill

Inlet WCS Sump Elev. 737.5

Inlet WCS stoplog Elev. 739.7

6" perforated CPT distribution manifold

6" perforated CPT collection manifold

738

Outlet WCS SUMP ELEV. 737.2

736

Sta. 0+10 Elev. 737.6

Sta. 0+90 Elev. 737.4

0+00

0+30

0+60

0+90

1+00

Station

DATE
DESIGNED BY ANDY MACKRILL 9/5/23
DRAWN BY ANDY MACKRILL 9/5/23
CHECKED BY ANDY CRAIG 9/15/23
APPROVED BY

PROFILE ALONG CENTERLINE




FILE NAME

DRAWING SET
SHEET 4 OF 7

LANDOWNER

LOCATION

SECTION 03 - T79N - R03W




PLAN

Legend

	Earth Fill
	Woodchip Media
	Proposed 6" Perforated CPT
	Proposed 6" Non-Perforated CPT
	Existing 10" CPT Main
	Proposed 10" Non-Perforated CPT
	Plastic Liner
	Geotextile Fabric
	Existing Ground Surface
	Bioreactor Footprint

NOTES:

1. All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
2. Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
3. Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1" long by 1/2" thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
4. Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
5. Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
6. See Plan Map for benchmark coordinates.






SECTION A-A

DATE	9/5/23
DESIGNED BY ANDY MACKRILL	9/5/23
DRAWN BY ANDY MACKRILL	9/5/23
CHECKED BY ANDY CRAIG	9/15/23
APPROVED BY	


BIOREACTOR DETAIL




FILE NAME	
DRAWING SET	
SHEET 5 OF 7	



**TYPICAL SECTION
UPSTREAM STRUCTURE**



**TYPICAL SECTION
DOWNSTREAM STRUCTURE**



- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, on all lines: upstream, downstream and center. Pipe must be PVC, dual-wall CPT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745. Check valve must conform to ASTM D 3034 with SDR35 pipe or stronger.
 3. Couplings between the water control structures and the non-perforated tile must be watertight.
 4. Stop boards must provide must tight seals under a minimum of 1 foot pressure head (except notched board).
 5. Appropriately mark bioreactor perimeter to avoid vehicle, implement, or livestock traffic.
 6. Place structure and pipe coupler on a stable base. A stable base may be compacted earth, compacted fill sand, or a concrete pad. Extend the stable base no less than 1 foot beyond structure.
 7. Excavated material placed around structure and pipes shall be hand compacted in 4" lifts.

QUANTITIES*	
Water Control Structure, 3 Chamber $H_1 = 6$ ft. $d_1 = 10$ in. $d_2 = 6$ in.	1
Water Control Structure, 2 Chamber $H_2 = 6$ ft. $d_3 = 6$ in.	1
10" Non-perforated Pipe (ft)	40
10" CMP Outlet Pipe with Rodent Guard (ft)	20
6" Non-perforated Pipe (ft)	135
6" Perforated CPT (ft)	40
6" End Cap	2
Wood Chips (cu. yd.)	281
4 Mil Plastic (sq. yd.)**	324
Geotextile (sq. yd.)	178
Excavation (cu. yd.)	332
Earth Fill (cu. yd.)	107
6" Backflow Check Valve	1

* Quantities do not include tile/pipe couplers or extra material for geotextile/plastic overlap
 ** Accounts for 1 ft. overhang around perimeter

DATE 9/5/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

STRUCTURE DETAIL



FILE NAME
 DRAWING SET
 SHEET 6 OF 7

CONSTRUCTION NOTES

1. Tile elevations are based on Maverick tile probe depths and are to be considered accurate within margin of error of the instrument.
2. If any surface inlets are currently attached to the tile main or plan to be in the future, they shall be replaced with water quality inlets to minimize trash entry into the tile line before construction of the bioreactor begins.
3. Avoid excessive disturbance of any buffers or grassed water ways during construction. However, if re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded within 14 days according to NRCS Conservation Practice Standard IA-342 Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
4. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion.
5. All carbon media to be placed in the bioreactor shall come from an ESE approved vendor or approved with ESE staff prior to transportation and placement.
6. Contact an ESE representative for inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the bioreactor chamber and tile line trenches
 - b. After placing the water control structures and bioreactor manifolds
 - c. After placement of carbon media, before backfilling with soil
 - d. After connections to existing tile and final grading
7. Any product planned for use in construction must be approved by ESE prior to construction. Save and provide documentation to an ESE representative of all materials used in construction including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths
 - b. Photos and invoices for quantity and quality of woodchips/carbon media
 - c. Photos and invoices or product information to detail quantity and quality of plastic and geotextile fabric
 - d. Photos and invoices or product information for water control structures
8. Construction tolerances are ± 0.5 ft on bioreactor chamber dimensions, and ± 0.1 ft. on all elevations. Outlet WCS sump (bottom) must be below the elevation of the bioreactor chamber at the outlet end. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by a representative from ESE and will be noted in the as-built plan.
9. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.
10. All work shall be performed according to the IA construction and practice specifications in the table below.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-95	Geotextile
IA-605	Denitrifying Bioreactor
IA-620	Underground Outlet

DESIGNED BY	ANDY MACKRILL	DATE	9/5/23
DRAWN BY	ANDY MACKRILL		9/5/23
CHECKED BY	ANDY CRAIG		9/15/23
APPROVED BY			

CONSTRUCTION NOTES



FILE NAME
bc
DRAWING SET
SHEET 7 OF 7

DENITRIFYING BIOREACTOR CONSTRUCTION PLANS

CEDAR COUNTY, IOWA
SECTION 06- T79N - R03W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. CROSS SECTION VIEW
 4. PROFILE ALONG CENTERLINE
 5. BIOREACTOR DETAIL
 6. STRUCTURE DETAIL
 7. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	9/15/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: All

ENGINEERING CLASS 3

DESIGNED BY	ANDY MACKRILL, TSP	DATE	9/5/2023
DRAWN BY	ANDY MACKRILL, TSP	DATE	9/5/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	9/15/2023
APPROVED BY			




COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 7

Benchmark:
 Top of Outlet (NAD 1983 State
 Plane Iowa South US Survey Feet)
 Northing: 619356.3
 Easting: 2259875.8
 Elevation: 735.7



Staking Control Points (NAD 1983 State Plane Iowa South US SURVEY FEET)				
Point	Description	Northing	Easting	Elevation
1	Southeast Corner BID	619417.7	2259780.1	740.8
2	Southwest Corner BID	619417.5	2259760.0	741.2
3	Northwest Corner BID	619497.7	2259759.2	741.8
4	Northeast Corner BID	619497.9	2259779.3	741.0
5	Inlet WCS (3-chamber)	619359.2	2259785.7	741.2
6	Outlet WCS (2-chamber)	619495.9	2259782.8	740.8
7	Benchmark	619356.3	2259875.8	735.7

DATE 9/5/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY _____

PLAN MAP



Approx. Grade 0.2%
 Connecting to
 Existing Outlet.

New 8" CMP Outlet
 With Rodent Guard

Legend

- Proposed 6" Perforated CPT
- Proposed 6" Non-Perforated CPT
- Existing 8" CPT Main
- Proposed 8" Non-Perf CPT Main
- Proposed 8" CMP Outlet
- Bioreactor Footprint
- Water Control Structure
- Benchmark
- 2 Foot Contours









FILE NAME

DRAWING SET
 SHEET 2 OF 7

Cross-Section

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface



DESIGNED BY	ANDY MACKRILL	DATE	9/5/23
DRAWN BY	ANDY MACKRILL	DATE	9/5/23
CHECKED BY	ANDY CRAIG	DATE	9/15/23
APPROVED BY			









CROSS SECTION VIEW



FILE NAME	
DRAWING SET	
SHEET 3 OF 7	

Profile Along Centerline

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface
-  6" Non-Perforated CPT Pipe
-  Water Control Structure
-  6" Perforated CPT Manifold Pipe

Grade backfill with existing ground to not create a channelized flow path

Lowest Cropped Elev 743.5

Inlet WCS Lid Elev. 743.3

Outlet WCS Lid Elev. 742.0

Existing ground surface

Mound backfill approximately 1 ft. to allow for settling and shed water

Place geotextile fabric at woodchip/soil interface.

Elevation

Earth fill

Inlet WCS stoplog Elev. 740.0

Woodchip fill

738

Inlet WCS stoplog Elev. 738.2

Inlet WCS Sump Elev. 737.3

6" perforated CPT collection manifold

6" perforated CPT distribution manifold

Outlet WCS SUMP ELEV. 736.0

735

Sta. 0+90 Elev. 736.2

Sta. 0+10 Elev. 736.4

0+00

0+30

0+60

0+90

1+00

Station


DATE
DESIGNED BY ANDY MACKFILL 9/5/23
DRAWN BY ANDY MACKFILL 9/5/23
CHECKED BY ANDY CRAIG 9/15/23
APPROVED BY

PROFILE ALONG CENTERLINE



FILE NAME
DRAWING SET
SHEET 4 OF 7

PLAN




Legend


- Earth Fill
- Woodchip Media
- Proposed 6" Perforated CPT
- Proposed 6" Non-Perforated CPT
- Existing 8" CPT Main
- Proposed 8" Non-Perforated CPT
- Proposed 8" CMP Outlet
- Plastic Liner
- Geotextile Fabric
- Existing Ground Surface
- Bioreactor Footprint

NOTES:

1. All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
2. Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
3. Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1" long by 1/2" thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
4. Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
5. Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
6. See Plan Map for benchmark coordinates.



ELEVATION



SECTION A-A



DATE	9/5/23
DESIGNED BY ANDY MACKRILL	9/5/23
DRAWN BY ANDY MACKRILL	9/5/23
CHECKED BY ANDY CRAIG	9/15/23
APPROVED BY	

BIOREACTOR DETAIL



FILE NAME	
DRAWING SET	
SHEET 5 OF 7	


LANDOWNER		LOCATION	SECTION 03 - T79N - R03W
-----------	--	----------	--------------------------



Legend

- Earth Fill
- 6" Non-Perforated CPT
- Existing 8" CPT Main
- Proposed 8" CPT Main
- Existing Ground Surface

**TYPICAL SECTION
UPSTREAM STRUCTURE**




**TYPICAL SECTION
DOWNSTREAM STRUCTURE**

Side Port Is On The (Circle One) **Left** / Right Side Of Structure, Looking Downstream

NOTES:

1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, on all lines: upstream, downstream and center. Pipe must be PVC, dual-wall CPT, or CMP.
2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745. Check valve must conform to ASTM D 3034 with SDR35 pipe or stronger.
3. Couplings between the water control structures and the non-perforated tile must be watertight.
4. Stop boards must provide must tight seals under a minimum of 1 foot pressure head (except notched board).
5. Appropriately mark bioreactor perimeter to avoid vehicle, implement, or livestock traffic.
6. Place structure and pipe coupler on a stable base. A stable base may be compacted earth, compacted fill sand, or a concrete pad. Extend the stable base no less than 1 foot beyond structure.
7. Excavated material placed around structure and pipes shall be hand compacted in 4" lifts.



IN-LINE CONTROL STRUCTURES

QUANTITIES*	
Water Control Structure, 3 Chamber $H_1 = 6$ ft. $d_1 = 8$ in. $d_2 = 6$ in.	1
Water Control Structure, 2 Chamber $H_2 = 6$ ft. $d_3 = 6$ in.	1
8" Non-perforated Pipe (ft)	40
8" CMP Outlet Pipe With Rodent Guard (ft)	20
6" Non-perforated Pipe (ft)	235
6" Perforated CPT (ft)	40
6" End Cap	2
Wood Chips (cu. yd.)	242
4 Mil Plastic (sq. yd.)**	307
Geotextile (sq. yd.)	178
Excavation (cu. yd.)	279
Earth Fill (cu. yd.)	89
6" Backflow Check Valve	1

* Quantities do not include tile/pipe couplers or extra material for geotextile/plastic overlap
 ** Accounts for 1 ft. overhang around perimeter

DATE	9/5/23
DESIGNED BY ANDY MACKRILL	9/5/23
DRAWN BY ANDY MACKRILL	9/5/23
CHECKED BY ANDY CRAIG	9/15/23
APPROVED BY	

STRUCTURE DETAIL



FILE NAME	
DRAWING SET	
SHEET 6 OF 7	

CONSTRUCTION NOTES

1. Tile elevations are based on Maverick tile probe depths and are to be considered accurate within margin of error of the instrument.
2. If any surface inlets are currently attached to the tile main or plan to be in the future, they shall be replaced with water quality inlets to minimize trash entry into the tile line before construction of the bioreactor begins.
3. Avoid excessive disturbance of any buffers or grassed water ways during construction. However, if re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded within 14 days according to NRCS Conservation Practice Standard IA-342 Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
4. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion.
5. All carbon media to be placed in the bioreactor shall come from an ESE approved vendor or approved with ESE staff prior to transportation and placement.
6. Contact an ESE representative for inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the bioreactor chamber and tile line trenches
 - b. After placing the water control structures and bioreactor manifolds
 - c. After placement of carbon media, before backfilling with soil
 - d. After connections to existing tile and final grading
7. Any product planned for use in construction must be approved by ESE prior to construction. Save and provide documentation to an ESE representative of all materials used in construction including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths
 - b. Photos and invoices for quantity and quality of woodchips/carbon media
 - c. Photos and invoices or product information to detail quantity and quality of plastic and geotextile fabric
 - d. Photos and invoices or product information for water control structures
8. Construction tolerances are ± 0.5 ft on bioreactor chamber dimensions, and ± 0.1 ft. on all elevations. Outlet WCS sump (bottom) must be below the elevation of the bioreactor chamber at the outlet end. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by a representative from ESE and will be noted in the as-built plan.
9. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.
10. All work shall be performed according to the IA construction and practice specifications in the table below.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-95	Geotextile
IA-605	Denitrifying Bioreactor
IA-620	Underground Outlet

DESIGNED BY	ANDY MACKRILL	DATE	9/5/23
DRAWN BY	ANDY MACKRILL		9/5/23
CHECKED BY	ANDY CRAIG		9/15/23
APPROVED BY			

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
SHEET 7 OF 7

LANDOWNER

LOCATION

SECTION 03 - T79N - R03W


SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 03 - T79N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 8/10/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: _____ All

ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	8/10/2023
DRAWN BY	ANDREW MACKRILL	DATE	8/10/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	8/10/2023
APPROVED BY			



COVER SHEET

FILE NAME


DRAWING SET

SHEET 1 OF 6

Staking Control Points(NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	620747.0	2243014.6	714.8
2	Distribution Line	620833.5	2243050.5	714.6
3	Distribution Line	620955.0	2243042.1	714.8
4	Distribution Line	621018.9	2243002.3	714.8
5	Distribution Line	621297.6	2242971.6	715.5
6	Distribution Line	621599.4	2242938.5	716.3
7	Benchmark	621088.2	2243032.1	716.1

PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 621088.2
 Easting: 2243032.1
 Elevation: 716.1



Legend	
	Proposed 6" Perforated CPT Distribution Line
	Proposed 6" Non-Perforated CPT
	Proposed 6" CMP Outlet
	Existing 6" CPT Main
	Gas Pipeline
	Proposed Water Control Structure
	2' Contours
	Benchmark
	Staking Point

875' of 6" CPT at 0.0% Grade Gas Line Under the Ditch to be Located Prior to Construction

Benchmark

Existing 6" Tile

Buffer Cross Section, See Sheet 3

New 6" CMP Outlet With Rodent Guard

DATE	DESIGNED BY	DRAWN BY	CHECKED BY	APPROVED BY
8/10/23	ANDREW MACKRILL	ANDREW MACKRILL	ANDY CRAIG, PE, TSP	


PLAN MAP



FILE NAME

DRAWING SET
 SHEET 2 OF 6

Cross-Section



DESIGNED BY ANDREW MACKRILL 8/10/23
 DRAWN BY ANDREW MACKRILL 8/10/23
 CHECKED BY ANDY CRAIG, PE, TSP 8/10/23
 APPROVED BY _____

BUFFER AND BANK CROSS SECTION



FILE NAME


DRAWING SET
 SHEET 3 OF 6

LANDOWNER



LOCATION

SECTION 03 - T79N - R4W

Profile Along Distribution Line



Legend

-  All Season Water Table
-  Proposed Water Control Structure
- Proposed 6" CPT Distribution Line
- Existing Ground Surface
- Lowest Farmed Elevation

DESIGNED BY	ANDREW MACKRILL	DATE	8/10/23
DRAWN BY	ANDREW MACKRILL	DATE	8/10/23
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	8/10/23
APPROVED BY			

PROFILE ALONG DISTRIBUTION LINE



FILE NAME


a

DRAWING SET
SHEET 4 OF 6


LANDOWNER

LOCATION

SECTION 03 - T79N - R4W




TYPICAL SECTION



QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 6 in.	1	IA-21, IA-26, CPS-587
6" Non-perforated Pipe (ft)	40	IA-21, IA-45
6" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	875	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587


*Quantities Do Not Include Couplers



PLAN

NOTES:

1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
3. Couplings between the water control section and the non-perforated tile shall be water tight.
4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.



IN-LINE CONTROL STRUCTURE

DESIGNED BY	ANDREW MACKRILL	DATE	8/10/23
DRAWN BY	ANDREW MACKRILL		
CHECKED BY	ANDY CRAIG, PE, TSP		
APPROVED BY			

3 CHAMBER STRUCTURE DETAIL



FILE NAME	8
DRAWING SET	
SHEET 5 OF 6	

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE 8/10/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 03 - T79N - R4W

SATURATED BUFFER CONSTRUCTION PLANS

MUSCATINE CO, IOWA
SECTION 03- T78N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 6/21/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: All

ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	6/21/2023
DRAWN BY	ANDREW MACKRILL	DATE	6/21/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	6/21/2023
APPROVED BY			









COVER SHEET

FILE NAME

DRAWING SET




SHEET 1 OF 6

Legend

-  Proposed 6" Perforated CPT Distribution Line
-  Proposed 6" Non-Perforated CPT
-  Proposed 6" CMP Outlet
-  Existing 6" CPT Main
-  2 Foot Contours
-  Proposed Water Control Structure

Staking Control Points (NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	585508.1	2242975.9	553.0
2	Distribution Line	585519.8	2243087.4	552.7
3	Distribution Line	585602.7	2243336.9	552.8
4	Distribution Line	585706.7	2243500.5	550.2
5	Distribution Line	585864.2	2243739.8	551.1
6	Distribution Line	586056.9	2244025.1	552.1

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 585487.0
 Easting: 2243078.1
 Elevation: 552.6


DATE	DATE
DESIGNED BY ANDREW MACKRILL 6/21/23	
DRAWN BY ANDREW MACKRILL 6/21/23	
CHECKED BY ANDY CRAIG, PE, TSP 6/21/23	
APPROVED BY	

PLAN MAP



FILE NAME	
DRAWING SET	SHEET 2 OF 6

Cross-Section



DESIGNED BY	ANDREW MACKRILL	DATE	6/21/23
DRAWN BY	ANDREW MACKRILL		6/21/23
CHECKED BY	ANDY CRAIG, PE, TSP		6/21/23
APPROVED BY			

BUFFER AND BANK CROSS SECTION




FILE NAME

DRAWING SET
SHEET 3 OF 6






LANDOWNER

LOCATION

SECTION 03 - T78N - R4W



Legend

-  All Season Water Table
-  Proposed Water Control Structure
-  Proposed 6" CPT Distribution Line
-  Existing Ground Surface
-  Lowest Crop Elevation


DATE
 DESIGNED BY ANDREW MACKRILL 6/21/23
 DRAWN BY ANDREW MACKRILL 6/21/23
 CHECKED BY ANDY CRAIG, PE, TSP 6/21/23
 APPROVED BY _____

PROFILE ALONG DISTRIBUTION LINE



FILE NAME

DRAWING SET
 SHEET 4 OF 6









TYPICAL SECTION


NOTES:

1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
3. Couplings between the water control section and the non-perforated tile shall be water tight.
4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.


Legend

-  Earth Fill
-  6" Perforated CPT
-  Proposed 6" Non-Perforated CPT
-  Proposed 6" CMP Outlet
-  Ditch Bank
-  Existing Ground Surface

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 6 in.	1	IA-21, IA-26, CPS-587
6" Non-perforated Pipe (ft)	40	IA-21, IA-45
6" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	1200	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587



PLAN



IN-LINE CONTROL STRUCTURE

*Quantities Do Not Include Couplers

DATE 6/21/23
DESIGNED BY ANDREW MACKRILL
DRAWN BY ANDREW MACKRILL
CHECKED BY ANDY CRAIG, PE, TSP
APPROVED BY

3 CHAMBER STRUCTURE DETAIL



FILE NAME

DRAWING SET
SHEET 5 OF 6

LANDOWNER

LOCATION

SECTION 03 - T78N - R4W

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE 6/21/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 03 - T78N - R4W


SATURATED BUFFER CONSTRUCTION PLANS

MUSCATINE CO, IOWA
SECTION 03- T78N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa
	_____ 6/14/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: _____ All

ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	6/21/2023
DRAWN BY	ANDREW MACKRILL	DATE	6/21/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	6/21/2023
APPROVED BY			









COVER SHEET

FILE NAME _____

DRAWING SET



SHEET 1 OF 6

Legend

-  Proposed 6" Perforated CPT Distribution Line
-  Proposed 12" Non-Perforated CPT
-  Existing 12" CPT Main
-  Proposed 12" CMP
-  2 Foot Contours
-  Proposed Water Control Structure

Staking Control Points (NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	585599.7	2243486.4	551.4
2	Distribution Line	585533.5	2243438.9	551.7
3	Distribution Line	585372.8	2242991.8	552.4
4	Distribution Line	585340.4	2242965.7	552.5
5	Distribution Line	585272.9	2242935.5	552.9
6	Distribution Line	584964.5	2242877.8	553.2

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 585487.0
 Easting: 2243078.1
 Elevation: 552.6


DATE 6/21/23
DESIGNED BY ANDREW MACKRILL
DRAWN BY ANDREW MACKRILL
CHECKED BY ANDY CRAIG, PE, TSP
APPROVED BY

PLAN MAP



FILE NAME
DRAWING SET
 SHEET 2 OF 6

Cross-Section



DESIGNED BY ANDREW MACKRILL 6/21/23
 DRAWN BY ANDREW MACKRILL 6/21/23
 CHECKED BY ANDY CRAIG, PE, TSP 6/21/23
 APPROVED BY _____

BUFFER AND BANK CROSS SECTION




FILE NAME






DRAWING SET
 SHEET 3 OF 6

LANDOWNER

LOCATION

SECTION 03 - T78N - R4W



- Legend**
-  All Season Water Table
 -  Proposed Water Control Structure
 -  Proposed 6" CPT Distribution Line
 -  Existing Ground Surface
 -  Lowest Crop Elevation

DESIGNED BY	ANDREW MACKRILL	DATE	6/21/23
DRAWN BY	ANDREW MACKRILL		6/21/23
CHECKED BY	ANDY CRAIG, PE, TSP		6/21/23
APPROVED BY			


PROFILE ALONG DISTRIBUTION LINE



FILE NAME



DRAWING SET
SHEET 4 OF 6

LANDOWNER		LOCATION	SECTION 03 - T78N - R4W
-----------	--	----------	-------------------------




TYPICAL SECTION

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.



PLAN



IN-LINE CONTROL STRUCTURE

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 12 in.	1	IA-21, IA-26, CPS-587
12" Non-perforated Pipe (ft)	40	IA-21, IA-45
12" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	984	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE 6/21/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 03 - T78N - R4W

SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 18 - T79N - R4W




**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



INDEX OF SHEETS

1. COVER SHEET
2. PLAN MAP
3. BUFFER AND BANK CROSS SECTION
4. PROFILE ALONG DISTRIBUTION LINE
5. STRUCTURE DETAILS
6. CONSTRUCTION NOTES



ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE 6/27/2023
DRAWN BY	ANDREW MACKRILL	6/27/2023
CHECKED BY	ANDY CRAIG, PE, TSP	6/30/2023
APPROVED BY		



COVER SHEET

FILE NAME



DRAWING SET

SHEET 1 OF 6










Staking Control Points(NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	605659.3	2228440.2	591.3
2	Distribution Line	606085.5	2228449.3	591.8
3	Distribution Line	606380.9	2228455.0	592.7
4	Distribution Line	606626.1	2228459.6	593.0
5	Distribution Line	606915.9	2228465.0	593.0
6	Distribution Line	607258.9	2228471.4	593.7
7	Benchmark	605598.3	2228463.9	595.6


PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 605598.3
 Easting: 2228463.9
 Elevation: 595.6

Legend

-  Proposed 6" Perforated CPT Distribution Line
-  Proposed 12" Non-Perforated CPT
-  Proposed 12" CMP Outlet
-  Existing 8" CPT Main
-  Proposed 8" Non-Perforated CPT
-  Proposed Water Control Structure
-  2' Contours
-  Benchmark
-  Staking Point




DATE: 6/27/23
 DESIGNED BY: ANDREW MACKRILL
 DRAWN BY: ANDREW MACKRILL
 CHECKED BY: ANDY CRAIG, PE, TSP
 APPROVED BY:

PLAN MAP



FILE NAME:
 DRAWING SET:
 SHEET 2 OF 6

Cross-Section





DESIGNED BY ANDREW MACKRILL 6/27/23
 DRAWN BY ANDREW MACKRILL 6/27/23
 CHECKED BY ANDY CRAIG, PE, TSP 6/30/23
 APPROVED BY _____

BUFFER AND BANK CROSS SECTION



FILE NAME _____
 DRAWING SET SHEET 3 OF 6



DESIGNED BY ANDREW MACKRILL	DATE 6/27/23
DRAWN BY ANDREW MACKRILL	6/27/23
CHECKED BY ANDY CRAIG, PE, TSP	6/30/23
APPROVED BY	


PROFILE ALONG DISTRIBUTION LINE



FILE NAME


LANDOWNER	LOCATION	SECTION 18 - T79N - R4W
------------------	-----------------	--------------------------------

DRAWING SET
SHEET 4 OF 6




TYPICAL SECTION

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.




QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 12 in.	1	IA-21, IA-26, CPS-587
12" Non-perforated Pipe (ft)	25	IA-21, IA-45
12" CMP Outlet Pipe with Rodent Guard (ft)	20	IA-604, IA-620
8" Non-perforated Pipe (ft)	50	IA-21, IA-45
6" Perforated CPT (ft) Buffer Tile Line	1600	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers



PLAN



IN-LINE CONTROL STRUCTURE

DATE 6/27/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

3 CHAMBER STRUCTURE DETAIL



FILE NAME
 DRAWING SET
 SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE 6/27/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6