

SCHEDULE OF PRICES

Flo971523B Project
 Contract No. 25-14

Section 23, Township 97 North, Range 15 West, Floyd County, Iowa

Name of Bidder:

Item No.	Work or Material	Spec No.	Estimated Quantity	Unit Price	Total
1	Site Stripping & Preparation	1	LS		
2	Structure & Channel Seeding	1.9	AC		
3	Buffer Seeding	11.4	AC		
4	Mobilization and Demobilization	1	LS		
5	Drain tile Investigation and Removal	8	HR		
6	Steel Sheet Piling	1063	SF		
7	Excavation (General)	7050	CY		
8	Earthfill (General)	935	CY		
9	Earthfill (General Dam)	2641	CY		
10	Earthfill (Dam Core)	950	CY		
11	Drainfill, Fine	28.5	CY		
12	Topsoil Strip, Stockpile, Salvage	4460	CY		
13	Toe Drain - 6" Diameter	358	LF		
14	Reinforced Concrete Pipe - 12"	145	LF		
15	Dual-Wall HDPE Pipe				
A	12" Diameter	139	LF		
B	24" Diameter	1343	LF		
16	SW-402 Water Control Structure	1	EA		
17	12" Apron, Footing, Bar Guard	2	EA		
18	8" x 20' CMP Tile Outlet	2	EA		
19	Riprap (Class E)	735	TN		
20	Erosion Stone	105	TN		
21	Concrete Grout	90	CY		
22	Anti-Seep Collars	4	EA		
23	Culvert Crossing	1	EA		
24	Crop Damage	0	AC		

TOTAL BASE BID.....\$ _____

Worksheet purposes only. Bids will only be accepted through the on-line Iowa Management of Procurement & Contracts System (IMPACS).

To register and learn about IMPACS, go to: <https://das.iowa.gov/state-employees/procurement/iowa-management-procurement-and-contracts-system-impacs>