



Addendum 02 for RFB 944900-01

Project Name: Terrace Hill Carriage House Roof Replacement
DAS RFB #: 944900-01
DAS Project #: 9449.00
Date: 03/10/2025

Bids Due: March 13, 2025 at 2:00 PM CST

Contents:

- Cover Page – Questions and Revisions (1 page)

1. Questions:

- 1.1. Confirm Valley metal and flashing material. Some notes mention new painted valley sheet metal and then copper valley metals and flashing.
 - 1.1.1. See below drawing revisions for clarification
- 1.2. Confirm Ventilation mat on entire roof surface.
 - 1.2.1. See below drawing revisions for clarification.

2. Revisions:

DRAWING CHANGES

Item #	Detail /Sheet	Description of Change
1.	A301	Detail H1/A301 Revise note “NEW COPPER FLASHING WITH 1" "V" CRIMP, HPC-1” to add HPC-1 to the new copper flashing.
2.	A301	Detail H9/A301 Revise note “EXISTING TRIM TO BE REMOVED AND SALVAGED FOR INSTALLATION, HPC-2” add HPC-2 to the existing metal.
3.	A101	Add the following general note “7. Install ice and water shield per N16/A102 and A13/A102. Install underlayment for the entire roof area intended for wood shingles or flashing areas. Install ventilation mat for entire area under the wood shingles.”

END OF ADDENDUM #2