IOWA COMMUNICATIONS NETWORK

CONSTRUCTION DRAWINGS FOR: WINTERSET COMMUNITY SCHOOL DISTRICT CONNECTIONS (MADISON COUNTY)

PROJECT OVERVIEW:

The ICN intends to extend the ICN Backbone from the corner of East Jefferson Street and North 10th Street to the Winterset Community School District (WCSD) High School. Also, ICN will extend fiber to the WCSD School Bus Garage and to the WCSD administrative offices currently under construction. The project will be in four phases:

Phase 1

Extend a 12-strand armored fiber connection from the existing ICN Backbone cable at the northwest corner of N 10th Street and E Jefferson Street to an existing ICN handhole in the Right of Way in front of 814 South 4th Avenue, a distance of approximately 7,043 feet. At 814 S. 4th Ave, the new cable will be spliced to an existing ICN cable to the High School.

Phase 2 (Hot Cut)

A mid-span insertion is to be performed on the ICN backbone, north of E. Jefferson Street along the west side of N. 10th Street. A bore of approximately 128 feet and two handholes will be required for the insertion. Contractor shall also expose the duct/cable at the mid-point of the insertion, cut the duct and pull the existing fiber back to the two handholes during the midnight splice window. Contractor shall provide a pulling crew to be on site at midnight on the night of the cut-over.

Phase :

Extend a 12-strand dielectric fiber and tracer wire to the WCSD School Bus Garage first floor data location. A second mid-span insertion is required at the Bus Garage, 923 East Lane Street. The location of the mid-span insertion is on the west side of N. 10th Street north of East Lane St. A bore of approximately 183 feet and two handholes will be required for the insertion. Contractor shall also expose the cable at the mid-point of the insertion, cut the duct and pull the existing fiber back to the two handholes. Another bore of approximately 71 feet will be required to serve the building. See Building Entry detail for installation of T-Adapter, Tracer and Ground Rod. Phase 3 will take place after the mid-span insertion in Phase 2. The existing cable will be dead at that point, so all work will be performed during the day.

Phase 4

Extend a new 12-strand armored from an existing ICN handhole on the southeast corner of 4th Avenue and US Highway 169/lowa Highway 92, to the new WCSD administrative office at 303 Wambold Drive (the frontage road along the north side of US Hwy 169/lowa 92). This will require new conduit of approximately 331 feet to the Owner's handhole and installing fiber in the Owners new conduit approximately 200 feet from the Owner's handhole into the building first floor data room.

It is located approximately 1000 feet west of the intersection of US Highway 169 and Iowa Highway 92.

CONTRACTOR REQUIREMENTS FOR WINTERSET:

THE CONTRACTOR SHALL COMPLY WITH ALL CITY OF WINTERSET REQUIREMENTS.

THE CONTRACTOR SHALL POTHOLE ALL UTILITIES.

POTHOLES SHALL BE BACKFILLED WITH SAND UP TO 6 INCHES BELOW GRADE.

THE TOP 6 INCHES SHALL BE COMPACTED BLACK DIRT WITH THE ORIGINAL SOD ON TOP.

THE CONTRACTOR SHALL MEET WITH THE CITY OF WINTERSET PRIOR TO BEGINNING WORK.


THE CONTRACTOR SHALL COORDINATE WITH THE CITY THROUGHOUT THE PROJECT AND SHALL ARRANGE FOR A FINAL INSPECTION, BY THE CITY, OF ALL WORK, INCLUDING ANY DAMAGE CAUSED BY THE CONTRACTOR.

THE CONTRACTOR SHALL PROVIDE ICN WITH A WRITTEN STATEMENT FROM THE CITY, THAT THE CITY HAS INSPECTED AND APPROVES OF THE CONTRACTOR'S WORK.


CONTACTS*						
COMPANY	TYPE	NAME	PHONE	timothy.flickinger@iowa.gov paul.damge@iowa.gov		
Iowa Communications Network (ICN)	OSP Engineer	Tim Flickinger	515-725-4699			
Iowa Communications Network (ICN)	ICN Materials	Paul Damge	515-725-4749			
Fiber Network Services (FNS)	Splicing Coordination	Chris Harris	515-725-8929	chris.harris@iowa.gov		
City of Winterset	Assistant City Administrator	Bob Hendricks	515-462-1422	bhendricks@cwmu.net		

^{*}THIS CONTACT LIST IS NOT ALL-INCLUSIVE. CONTRACTOR IS RESPONSIBLE FOR REQUESTING LOCATES OF ALL UTILITIES.

PROJECT LOCATION



	SHEET INDEX			
1 TITLE PAGE (THIS SHEET)				
2 MATERIALS				
3-15	CONSTRUCTION DRAWING			
16-17	DETAILS			
-	ICN STANDARD DETAIL ATTACHMENTS			





WINTERSE	T IOWA	STRICT CON	INECTIONS
1	PRELIMINARY		IOWA COMMUNICATIONS NETWORK
2	FINAL	5-29-19	400 EAST 14TH STREET
3	3		GRIMES STATE OFFICE BUILDING DES MOINES, IOWA 50319
4			ICN © 2019, COPY WITH PERMISSION
SCALE: NONE SIZE: 11 x 17		TITLE PAGE	PAGE 1 OF 17

ITEM -	ICN PART NUMBER -	QTY -	NOTES -
ICN PROVIDED MATERIALS			
FIBER CABLE			
12 strand Armored SM fiber		9800	
12 strand Indoor/Outdoor OFNR Dielectric SM fiber	Corning-C 012E8F-31131-29	300	
HANDHOLES AND LIDS			
Bulk 24"x36"x36" with lid Tier 22	BULKU2436360061001	10	
Bulk Puck ICN Logo Black	ACC7734-125	8	
Bulk Puck ICN Logo Orange	ACC7334OR-125	2	Locate point only
LOCATE FACILITIES			
LOCATE STATIONS			
TRIVIEW Test Station w/ Isolever 72" ORANGE (with 3 ICN decals applied) (Walker)	TVT172OB-EM9125	1	
IsoLever (Rhino Marker Isolation Lever only, no post)	EM9125-OR	2	Mount in handhole
ISO Lever Locate Box (pre-fabricated unit)	ISOLOCBOX	1	
GROUNDING			
Erico 1/2" x 6' Ground Rod (Graybar)	611360	4	
Burndy 1/2" Ground Rod Clamp (Anixter)	GRC12	4	
MARKERS FLAGS DECALS			
ICN Snap Around Vulcan 4"X4" 15Mil Coiled Pvc (ICN-4X4-Sa)	1502345 (ICN-4x4-SA)	20	
TERMINATION ITEMS: FDP, BULKHEADS, TRAYS, & RELATED			
Wall-Mountable Connector Housing (WCH), Holds 2 CCH connector panels	WCH-02P	2	
CCH Pigtailed Splice Cassette, 6 F, SC UPC Simplex, SM PRE-ASSEMBLED	CCH-CS06-3C-P00RE	2	
Leviton storage ring 24-inch	48900-OFR	1	
Leviton storage ring 11.5-inch	48900-IFR	1	
SPLICING MATERIALS			
SPLICE CLOSURES			
450BS FOSC450-BS-6-NT-0-B0V	F34112-000	4	
TRAY	FOSC450-B6-6-NT-0-B3V	1	
SPLICE TRAYS			
A TRAY 12 FOSC-ACC-A-TRAY-12 TRAY WITH 12 FUSION SPLICE HOLDER	497817-000	4	BS case
B TRAY 24 FOSC-ACC-B-TRAY-24-KIT	863927-000	1	B case
BONDING & TRACING HARDWARE			
FOSC Closure Sealing Kit FAK-MULDRP-45-4P/CBL-ATT	1F6818-000	3	
3M Scotchlok Shield Bond Connector 4460-D	4460-D	12	
CONTRACTOR PROVIDED MATERIALS			
HDPE Conduit (13.5 SDR)	2"	7628	
6 AWG Bare Solid Copper Ground Wire (Graybar) - 315' reel		1	
12 AWG Copperhead 30 MIL Insulated Orange Copper Clad Steel Tracer Wire***		210	
Contractor shall supply all other materials required for proper installation, including			
but not limited to: HDPE, Duct Splices, Grounding and Tracer Wires, Rock, Wire			
Mesh, etc.		Χ	

NOTE ON HDPE CONDUIT AND SPLICES:

- 1. HDPE SHALL BE ORANGE SMOOTH WALL SDR 13.5
- 2. DUCT SPLICES SHALL BE MADE OF THE FOLLOWING (IN ORDER OF PREFERENCE.)
 - -CRIMP ON
 - -CLAMP ON / BOLT ON (SPLIT COUPLINGS)
 - -PUSH ON
- 3. ALL SPLICES SHALL BE AIR AND WATER TIGHT
- 4. DUCT SPLICES SHALL BE OF A TYPE MADE SPECIFICALLY FOR JOINING HDPE CONDUIT
- 5. ALL DUCT SPLICES SHALL BE MADE IN SUCH MANNER AS TO ALLOW CONTINUOUS PULLING OF CABLE THROUGH DUCT.


ANY EXCEPTIONS MUST BE AGREED UPON IN WRITING PRIOR TO CONSTRUCTION:



	CINIAL	E 00	10	4
1	PRELIMINARY	5-22	-19	IOWA COM
WIN	TERSET IOWA			
CO	MMUNITY SCHOOL	DISTRICT	CONN	NECTIONS

COMMUNICATIONS NETWORK
400 EAST 14TH STREET
GRIMES STATE OFFICE BUILDING DES MOINES, IOWA 50319
ICN © 2019, COPY WITH PERMISSION PAGE 2 OF 17

ICN



1. STA. 0+00

EXISTING ICN HANDHOLE (24"X36"X36") SPLICE LS507


1 EA. ISO-LEVER LOCATE STATION

1 EA. FOSC 450B FIBER OPTIC SPLICE CLOSURE FOR MIDSHEATH SPLICE

1 EA. GROUND ROD

150' COIL OF 12 F/A LINK 1126B

2. 837' FROM STA. 0+00 TO STA. 8+37 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A



GENERAL NOTES:


OSP PROJECT LOG #:61190105 LINK NAME: 1126A, 1126B, 1126C, 1125C

- 1. DUCT TO BE INSTALLED MINIMUM 48" DEPTH EXCEPT WHERE NOTED
- 2. THIS SHEET IS PART OF PHASE 1 OF THE PROJECT

	COMMUNITY SCHOOL DISTRICT CONNECTIONS WINTERSET IOWA						
	1	PREL	IMINARY	5-22-19	IOWA COMMUNICATIONS NETWORK		
	2	FINAL		5-29-19	400 EAST 14TH STREET		
	3			·	GRIMES STATE OFFICE BUILDING DES MOINES, IOWA 50319		
	4				ICN © 2019, COPY WITH PERMISSION		
٦	SCAL	E: 1" = 50'	SIZE: 11 x 17	CONSTRUCTION	PAGE 3 OF 17		



- 1. 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A
- 2. STA. 8+37 1 EA. INSTALL HANDHOLE (24"X36"X36") 3' NORTH OF BOC 150' COIL OF 12 F/A LINK 1126B
- 3. 1,091' FROM STA. 8+37 TO STA. 19+28 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A




GENERAL NOTES:


OSP PROJECT LOG #:61190105 LINK NAME:1126A, 1126B, 1126C, 1125C

- 1. DUCT TO BE INSTALLED MINIMUM 48" DEPTH EXCEPT WHERE NOTED
- 2. THIS SHEET IS PART OF PHASE 1 OF THE PROJECT

COI	ICN				
1	PREL	IMINARY	5-22-19	IOWA COMMUNICATI	ONS NETWORK
2	FINAL		5-29-19	400 EAST 14TH S	
3				GRIMES STATE OFFIC DES MOINES, IOW	
4				ICN © 2019, COPY WITH	
SCAL	SCALE: 1" = 50' SIZE: 11 x 17		CONSTRUCTION		PAGE 4 OF 17



1. 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A




GENERAL NOTES:


OSP PROJECT LOG #:61190105 LINK NAME:1126A, 1126B, 1126C, 1125C

- 1. DUCT TO BE INSTALLED MINIMUM 48" DEPTH EXCEPT WHERE NOTED
- 2. THIS SHEET IS PART OF PHASE 1 OF THE PROJECT

	COMMUNITY SCHOOL DISTRICT CONNECTIONS WINTERSET IOWA						
	1	PRELIMINARY		5-22-19	IOWA COMMUNICATIONS NETWORK		
	2	FINAL		5-29-19	400 EAST 14TH STREET		
	3			·	GRIMES STATE OFFICE BUILDING DES MOINES, IOWA 50319		
	4				ICN © 2019, COPY WITH PERMISSION		
٦	SCAL	E: 1" = 50'	SIZE: 11 x 17	CONSTRUCTION	PAGE 5 OF 17		



- 1. 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A
- 2. STA. 19+28 1 EA. INSTALL HANDHOLE, (24"X36"X36") 11' NORTH OF BOC AND 7' EAST OF BOC 150' COIL OF 12 F/A LINK 1126B
- 3. 827' FROM STA. 19+28 TO STA. 27+55 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A




GENERAL NOTES:


OSP PROJECT LOG #:61190105 LINK NAME: 1126A, 1126B, 1126C, 1125C

- 1. DUCT TO BE INSTALLED MINIMUM 48" DEPTH EXCEPT WHERE NOTED
- 2. THIS SHEET IS PART OF PHASE 1 OF THE PROJECT

COI	NECTIONS			
1	PRELI	IMINARY	5-22-19	IOWA COMMUNICATIONS NETWORK
2	FINAL		5-29-19	400 EAST 14TH STREET
3				GRIMES STATE OFFICE BUILDING DES MOINES, IOWA 50319
4				ICN © 2019, COPY WITH PERMISSION
SCAL	SCALE: 1" = 50' SIZE: 11 x 17		CONSTRUCTION	PAGE 6 OF 17



- 1. 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A
- 2. STA. 27+55 1 EA. INSTALL HANDHOLE (24"X36"X36") 8' NORTH OF BOC AND 11' EAST OF BOC 150' COIL OF 12 F/A LINK 1126B
- 3. 1,314' FROM STA. 27+55 TO STA. 40+69 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A



GENERAL NOTES:


OSP PROJECT LOG #:61190105 LINK NAME: 1126A, 1126B, 1126C, 1125C

- 1. DUCT TO BE INSTALLED MINIMUM 48" DEPTH EXCEPT WHERE NOTED
- 2. THIS SHEET IS PART OF PHASE 1 OF THE PROJECT

COMMUNITY SCHOOL DISTRICT CONNECTIONS WINTERSET IOWA						
1	PREL	IMINARY	5-22-19	IOWA COMMUNICATI	ONS NETWORK	
2	FINAL		5-29-19	400 EAST 14TH S		
3				GRIMES STATE OFFIC DES MOINES. IOW		
4				ICN © 2019, COPY WITH		
SCAL	SCALE: 1" = 50' SIZE: 11 x 17		CONSTRUCTION		PAGE 7 OF 17	




1. 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A




GENERAL NOTES:

- 1. DUCT TO BE INSTALLED MINIMUM 48" DEPTH EXCEPT WHERE NOTED
- 2. THIS SHEET IS PART OF PHASE 1 OF THE PROJECT

COMMUNITY SCHOOL DISTRICT CONNECTIONS WINTERSET IOWA						
1	PREL	IMINARY	5-22-19	IOWA COMMUNICATIONS NETWORK		
2	FINAL		5-29-19	400 EAST 14TH STREET		
3				GRIMES STATE OFFICE BUILDING DES MOINES, IOWA 50319		
4				ICN © 2019, COPY WITH PERMISSION		
SCAL	E: 1" = 50'	SIZE: 11 x 17	CONSTRUCTION	PAGE 8 OF 17		



- 1. 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A
- 2. STA. 40+69
 1 EA. INSTALL HANDHOLE (24"X36"X36")
 13' NORTH OF BOC AND 7' EAST OF BOC
 150' COIL OF 12 F/A LINK 1126B
- 3. 1,186' FROM STA. 40+69 TO STA. 52+55 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A



GENERAL NOTES:


OSP PROJECT LOG #:61190105 LINK NAME:1126A, 1126B, 1126C, 1125C

- 1. DUCT TO BE INSTALLED MINIMUM 48" DEPTH EXCEPT WHERE NOTED
- 2. THIS SHEET IS PART OF PHASE 1 OF THE PROJECT

WIN	ICN				
1	PREL	IMINARY	5-22-19	IOWA COMMUNICATI	ONS NETWORK
2	FINAL		5-29-19	400 EAST 14TH S	
3				GRIMES STATE OFFIC DES MOINES, IOW	
4				ICN © 2019, COPY WITH	
SCAL	SCALE: 1" = 50' SIZE: 11 x 17		CONSTRUCTION		PAGE 9 OF 17



1. 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A




GENERAL NOTES:


OSP PROJECT LOG #:61190105 LINK NAME:1126A, 1126B, 1126C, 1125C

- 1. DUCT TO BE INSTALLED MINIMUM 48" DEPTH EXCEPT WHERE NOTED
- 2. THIS SHEET IS PART OF PHASE 1 OF THE PROJECT

	COMMUNITY SCHOOL DISTRICT CONNECTIONS WINTERSET IOWA					
	1	PRELIMINARY FINAL		5-22-19	IOWA COMMUNICATIONS NETWORK	
	2			5-29-19	400 EAST 14TH STREET	
	3			·	GRIMES STATE OFFICE BUILDING DES MOINES, IOWA 50319	
	4				ICN © 2019, COPY WITH PERMISSION	
٦	SCALE: 1" = 50' SIZE: 11 x 17		CONSTRUCTION	PAGE 10 OF 17		



- 1. 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A
- 2. STA. 52+55 1 EA. INSTALL HANDHOLE (24"X36"X36") 13' NORTH OF BOC AND 9' EAST OF BOC 150' COIL OF 12 F/A LINK 1126B
- 3. 1,052' FROM STA. 52+55 TO STA. 63+07 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A




GENERAL NOTES:


OSP PROJECT LOG #:61190105 LINK NAME:1126A, 1126B, 1126C, 1125C

- 1. DUCT TO BE INSTALLED MINIMUM 48" DEPTH EXCEPT WHERE NOTED
- 2. THIS SHEET IS PART OF PHASE 1 OF THE PROJECT

CON	ICN							
1	PREL	MINARY	5-22-19	IOWA COMMUNICATIONS NETWORK				
2	FINAL		5-29-19	400 EAST 14TH STREET				
3				GRIMES STATE OFFIC DES MOINES, IOW				
4				ICN © 2019, COPY WITH PERMISSION				
SCALE: 1" = 50' SIZE: 11 x 17		CONSTRUCTION		PAGE 11 OF 17				



- 1. 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A
- 2. STA. 63+07 1 EA. INSTALL HANDHOLE (24"X36"X36") 6' NORTH OF BOC AND 6' EAST OF BOC 150' COIL OF 12 F/A LINK 1126B
- 3. 608' FROM STA. 63+07 TO STA. 69+15 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A




GENERAL NOTES:

OSP PROJECT LOG #:61190105 | LINK NAME:1126A, 1126B, 1126C, 1125C

- 1. DUCT TO BE INSTALLED MINIMUM 48" DEPTH EXCEPT WHERE NOTED
- 2. THIS SHEET IS PART OF PHASE 1 OF THE PROJECT

	COMMUNITY SCHOOL DISTRICT CONNECTIONS VINTERSET IOWA						
1	PRELIMINARY FINAL		5-22-19	IOWA COMMUNICATIONS NETWOR			
2			5-29-19				
3				GRIMES STATE OFFIC DES MOINES. IOW			
4				ICN © 2019, COPY WITH			
SCAL	E: 1" = 50'	SIZE: 11 x 17	CONSTRUCTION	·	PAGE 12 OF 17		



1. 1-2" CONDUIT (BORED) LINK 1126B - 12 F/A

SPLICE LS506

2. STA. 69+15

- 1 EA. INSTALL HANDHOLE, (24"X36"X36")
 27' NORTH OF BOC AND 21' WEST OF BOC
 150' COIL OF 12 F/A
 (2 75' SPLICE TAILS FOR LINKS 1126A 1126B)
 CAPTURE EXISTING ICN 1.25" BLACK CONDUIT
 (POTHOLED AT 48" DEPTH)
 1 EA. ISO-LEVER LOCATE STATION (MOUNT IN HH)
 1 EA. GROUND ROD
 1 EA. FOSC 450BS FIBER OPTIC SPLICE CLOSURE
- 3. 128' FROM STA. 69+15 TO STA. 70+43 1-2" CONDUIT (BORED) LINK 1126A - 12 F/A

- 4. STA. 70+43

 1 EA. INSTALL HANDHOLE, (24"X36"X36")

 3' SOUTH OF DRIVEWAY


 150' COIL OF 12 F/A LINK 1126A

 CAPTURE EXISTING ICN 1.25" BLACK CONDUIT

 (POTHOLED AT 40" DEPTH)

 1 EA. FOSC 450BS FIBER OPTIC SPLICE CLOSURE


 SPLICE MS1126A-M
- 5. MID-POINT OF MID-SPAN INSERTION
 EXISTING 1.25" BLACK DUCT
 POTHOLED AT 39" DEPTH
 39" EAST OF FENCE
 CUT DUCT AND FIBER
 PULL BACK FIBER AND ROUTE TO HANDHOLES AT
 STA. 69+15 AND STA. 70+43
 WARNING HOT CUT
 TO BE COORDINATED WITH ICN DURING
 A PLANNED MAINTANCE WINDOW



GENERAL NOTES:

- 1. DUCT TO BE INSTALLED MINIMUM 48" DEPTH EXCEPT WHERE NOTED
- 2. THIS SHEET IS PART OF PHASE 1 AND PHASE 2 OF THE PROJECT. PHASE 2 IS THE MID-SPAN INSERTION.


HICN DURING WINDOW				COMMUNITY SCHOOL DISTRICT CONNECTIONS WINTERSET IOWA				ic	N
			1 2		IMINARY INAL	5-22-19 5-29-19	IOWA COMMUNICATIONS NETWO 400 EAST 14TH STREET GRIMES STATE OFFICE BUILDING DES MOINES, IOWA 50319 ICN © 2019, COPY WITH PERMISSION		ιK
			3						
	OSP PROJECT LOG #:61190105	LINK NAME:1126A, 1126B, 1126C, 1125C	SCAL	E: 1" = 50'	SIZE: 11 x 17	CONSTRUCTION		PAGE 13 OF	17



- 1. STA. 0+00
 - 1 EA. INSTALL HANDHOLE, (24"X36"X36") 9' NORTH AND 3' EAST OF MCI MARKER 150' COIL OF 12 F/A LINK 1126A CAPTURE EXISTING ICN 1.25" ORANGE CONDUIT (POTHOLED AT 48" DEPTH) 1 EA. FOSC 450BS FIBER OPTIC SPLICE CLOSURE SPLICE MS1126A-N
- 2. 183' FROM STA. 0+00 TO STA. 1+83 1-2" CONDUIT (BORED) LINK 1126A - 12 F/A
- 3. STA. 1+83

1 EA. INSTALL HANDHOLE, (24"X36"X36") 6' NORTH AND 3' EAST OF I-BEAM 75' COIL OF 12 F/A FOR SPLICE - LINK 1126A 75' COIL OF 12 F/D FOR SPLICE - LINK 1126C CAPTURE EXISTING ICN 1.25" ORANGE CONDUIT (POTHOLED AT 37" DEPTH) 1 EA. FOSC 450BS FIBER OPTIC SPLICE CLOSURE SPLICE LS508

- 71' FROM STA. 1+83 TO STA. 2+54 1-2" CONDUIT (BORED) LINK 1126C - 12 F/D 2-#12 TRACER WIRE (1 NORTH/1 SOUTH)
- STA. 2+54 **BUILDING ENTRANCE** SEE DETAILS ON SHEET 16
- MID-POINT OF MID-SPAN INSERTION 6' EAST AND 8' NORTH OF TRANSFORMER PAD EXISTING 1.25" ORANGE DUCT POTHOLED AT 45" DEPTH CUT DUCT AND FIBER PULL BACK AND ROUTE TO HANDHOLES AT STA. 0+00 AND STA. 1+83 EXISTING CABLE IS IN-ACTIVE AFTER PHASE 1 & 2 CUTOVER. ACCESSING EXISTING CABLE CAN BE DONE DURING THE DAY AFTER THE CUTOVER



GENERAL NOTES:


- 1. DUCT TO BE INSTALLED MINIMUM 48" DEPTH EXCEPT WHERE NOTED
- 2. THIS SHEET IS PART OF PHASE 3 OF THE PROJECT

CONSTRUCTION DOCUMENT

	COI	ICN					
	1 PRELIMINARY		5-22-19	IOWA COMMUNICATI	ONS NETWORK		
	2	FINAL		5-29-19	400 EAST 14TH STREET		
	3				GRIMES STATE OFFICE DES MOINES, IOWA		
	4				ICN © 2019, COPY WITH		
;	SCALE: 1" = 50' SIZE: 11 x 17		SIZE: 11 x 17	CONSTRUCTION		PAGE 14 OF 17	

FILE: F: \2016\0501-1000\016-0760\40-Design\Microstation\016-0760_Winterset Community School District Connections\Base\Winterset Schools_Design (1).dwg

OSP PROJECT LOG #: 61190105 LINK NAME:1126A, 1126B, 1126C, 1125C




- 1. STA. 0+00
 EXISTING ICN HANDHOLE
 EXISTING SPLICE LS509
 1 EA. TRIVIEW LOCATE STATION
 (WITH 3 #12 TRACER WIRE)
 1 EA. GROUND ROD
 150' COIL OF 12 F/A LINK 1125C
- 2. 331' FROM STA. 0+00 TO STA. 3+31 1 - 2" CONDUIT (BORED) LINK 1125C - 12 F/A
- HANDHOLE TO BE PLACED BY BUILDING OWNER, 30"X48"
 CONTRACTOR TO VERIFY EXACT LOCATION OF HANDHOLE
 BEFORE BORING CONDUIT
 IF HANDHOLE IS NOT INSTALLED, STUB 2" HDPE CONDUIT
 4' ABOVE GRADE AND PLUG DUCT. STUB CONDUIT APPROX.
 45' NORTH OF WAMBOLD DR. CURB AND 30' EAST OF
 DOLLAR GENERAL PARKING LOT.
 COORDINATE EXACT LOCATION WITH CONTRACTOR AND OWNER
- 4. 196' FROM STA. 3+31 TO STA. 4+27 2" BUILDING OWNER CONDUIT LINK 1125C - 12 F/A

50' COIL OF 12 F/A - LINK 1125C

3. STA. 3+31

5. STA. 4+27
FIRST FLOOR DATA ROOM
80' COIL OF 12 F/A
COORDINATE WITH ICN AND BUILDING OWNER
SEE DETAILS ON SHEET 17




GENERAL NOTES:

OSP PROJECT LOG #: 61190105 LINK NAME:1126A, 1126B, 1126C, 1125C


- 1. DUCT TO BE INSTALLED MINIMUM 48" DEPTH EXCEPT WHERE NOTED
- 2. THIS SHEET IS PART OF PHASE 4 OF THE PROJECT

COMMUNITY SCHOOL DISTRICT CONNECTIONS WINTERSET IOWA						ICN		
	1	PRELI	MINARY	5-22-19	IOWA COMMUNICATIONS NETWO			
	2	FINAL		5-29-19	400 EAST 14TH STREET			
	3					ES STATE OFFICE BUILDING ES MOINES, IOWA 50319		
	4				ICN © 2019, COPY WITH			
	SCALE: 1" = 50' SIZE: 11 x 17		CONSTRUCTION		PAGE 15 OF 17			

WCSD SCHOOL BUS GARAGE



16.1 INTERIOR EAST WALL



CONSTRUCTION DOCUMENT

COMMUNITY SCHOOL DISTRICT CONNECTIONS

WINTERSET IOWA


1 PRELIMINARY 5-22-19
2 FINAL 5-29-19
3 UWA COMMUNICATIONS NETWORK
400 EAST 14TH STREET
GRIMES STATE OFFICE BUILDING
DES MOINES, IOWA 50319
4 USE: 11 x 17 CONSTRUCTION

OSP PROJECT LOG #:61190105 LINK NAME:1126A, 1126B, 1126C, 1125C SCALE: NONE SIZE: 11 x 17 CONSTRUCTION

PAGE 16 0F 17

WCSD ADMINISTRATIVE OFFICE

OSP PROJECT LOG #:61190105 LINK NAME:1126A, 1126B, 1126C, 1125C SCALE: NONE




CONSTRUCTION DOCUMENT

PAGE 17 OF 17

COMMUNITY SCHOOL DISTRICT CONNECTIONS
WINTERSET IOWA

1 PRELIMINARY 5-22-19
2 FINAL 5-29-19
3 IOWA COMMUNICATIONS NETWORK
400 EAST 14TH STREET
GRIMES STATE OFFICE BUILDING
DES MOINES, IOWA 50319
ION © 2019, COPY WITH PERMISSION

SIZE: 11 x 17 CONSTRUCTION





INSTALLATION INSTRUCTION

Install Channell BULK Vaults

Date: 5/12/15

Installation Considerations

This Installation Instruction provides general information useful for installing the Channell BULK line of below-grade handhole vaults. This guide cannot anticipate all situations that could be encountered in the field and thus represents information applicable to common installation conditions. Please consult local company practice for proper product configuration for each application.

Site Preparation

- 1. Ensure that all local, state, federal, OSHA and company-specific regulations are met prior to beginning and throughout the installation process.
- 2. Plan the excavation approximately 12 to 16 inches in length and width larger than the actual dimensions of the handhole to be installed. (See Figure 1)
- 3. Excavate the hole 6 to 8 inches in depth more than the overall height dimension of the handhole with the cover in place. Tamp the floor of excavated pit using either a hand tamp tool and/or a mechanical tamper. (Remember: if the handhole is to be set in concrete, the polymer ring must be included in this dimension.)
- 4. Place 5 to 6 inches of 3/4" crushed rock over the entire floor. The rock should be free of soil and other organic matter. This important step prevents subsistence of the vault over time, aids in drainage, and provides a solid foundation for the handhole. (See Figure 2)
 - a. As an alternative, a dry mix of cement and crushed rock ina 1:10 ratio may be used to form a higher strength foundation.
 - b. NOTE: Do not use "pea gravel" or other "round stone" for this step.
- 5. a. Place the handhole body into the pit. (See Figure 3)
 - b. Center the handhole body in the excavated pit parallel to the sidewalk and/or curb if applicable.
 - c. Level and adjust the height of the handhole body to grade, as required, by adding more crushed rock.

FOR THE PURPOSE OF THIS ILLUSTRATION, THIS HANDHOLE IS BEING PLACED AT A SITE THAT WILL HAVE A FUTURE SIDEWALK; THEREFORE, THE COMPOSITE RING IS REQUIRED. THE RING IS ONLY REQUIRED AT SITES WHERE THE HANDHOLE IS BEING PLACED IN AND SURROUNDED BY CONCRETE.

- 6. Place the cover on the handhole body to prevent the backfill dirt from entering the inside of the handhole. The cover should be level with the ground. Bolting of the cover is recommend but is not a requirement for this step; however, the cover must always be bolted down prior to departure of the site. (See Figure 4)
- 7. The excess soil removed from the excavated pit shall be used during the backfill of the pit.

 The backfill shall be tamped continuously during the filling process to prevent settling around the sides of the handhole. (See Figure 5)
 - During the filling process of the soil around the handhole, stones that are 3" and larger shall be removed from the soil and not used.
- 8. The final backfill shall be tamped with a slope away from the handhole. All excess backfill material shall be removed from the installation site. (See Figure 6)

Install Channell BULK Vaults

Figure 1





Figure 3








Figure 5




Figure 6





TYPICAL ABOVE GROUND BUILDING ENTRANCE WITH LOCATE TERMINAL



NOTES:


- 1. PLACE 2" G.I.P. WITH SWEEP TOWARDS NEW PULL BOX
- 2. (1) CORE HOLE THROUGH EXTERIOR WALL TO ACCOMMODATE 2" G.I.P.
- 3. PLUG ALL DUCTS WITH JACK MOON OR EQUIVALENT
- 4. BUILDING ENTRANCE SHALL HAVE WATER-TIGHT SEAL
- 5. ANCHOR 2" G.I.P. TO WALL WITH 2-HOLE STRAPS, SPACED NO MORE THAN 5-FEET APART
- 6. ALL COMPONENTS SHALL BE G.I.P. OR DIE CAST ALUMINUM
- 7. EMT AND PLASTIC ARE NOT ALLOWED
- 8. MOUNT LOCATE STATION A MINIMUM OF 18" ABOVE GRADE
- 9. SEAL ANY ACCESS HOLES DRILLED IN THE LOCATE STATION TO ROUTE WIRES WITH SILICONE
- 10. ALL COUPLINGS MUST ALLOW FOR BLOWING OR PULLING WITH NO OBSTRUCTION

TRACER WIRE TERMINATION DETAIL

TERMINATION OF THE LOCATE WIRE AT A LOCATE PEDESTAL, LOCATE TERMINAL, OR IN A SPLICE CASE SHALL BE MADE IN THE FOLLOWING FASHION:

STRIP OFF A MINIMUM OF 3/4" OF INSULATION. USING A NEEDLE NOSE PLIERS, BEND A WIRE "EYELET" ON THE WIRE END IN A CLOCKWISE MANNER. USE A FLAT WASHER ON BOTH SIDES OF THE WIRE EYELET WHEN CINCHING IT DOWN ON THE STUD. FLAT WASHERS SHALL BE OF APPROPRIATE SIZE SUCH THAT THE HOLE MATCHES THE DIAMETER OF THE STUD AND THE OUTSIDE OF DIAMETER OF THE FLAT WASHER MATCHES REASONBLY CLOSE TO THE EYELET DIAMETER.





*NOTE: ISOLOCBOX ASSEMBLY INCLUDES: BOX, ISOLEVER, PVC STAND-OFF, AND 1-FT OF FLEXIBLE CONDUIT WITH CONNECTORS



IOWA COMMUNICATIONS NETWORK GRIMES STATE OFFICE BUILDING 400 EAST 14TH STREET DES MOINES, IOWA 50319 ICN® 2014, COPY WITH PERMISSION

THIS DRAWING IS PROVIDED FOR GENERAL THIS DRAWING IS PROVIDED FOR GENERAL NFORMATION ONLY AND IS NOT TO BE USED TO DETERMINE PRECISE ICN PLACEMENT.


CALL ONE CALL BEFORE EXCAVATION (1-800-292-8989 OR 811)

ABOVE GROUND BUILDING ENTRANCE WITH LOCATE TERMINAL

DOCUMENT CREATED REVISION (ISOLOCBOX) 1-16-19

SCALE: NONE

SIZE: 11 x 17 0:\AutoCAD Standards\TYPICALS\ITYPBLDGENTRABOVE.dwg




TRACER WIRE TERMINATION DETAIL

Termination of the locate wire at either a pedestal, puck, or in a splice case shall be made in the following fashion:

Strip off a minimum of 3/4" of insulation. Using a needle nose pliers bend a wire "eyelet" on the wire end in a clockwise manner. Use a flat washer on both sides of the wire eyelet when cinching it down on the stud. Flat washers shall be of appropriate size such that the hole matches the diameter of the stud and the outside diameter of the flat washer matches reasonably close to the eyelet diameter.





THIS DRAWING IS PROVIDED FOR GENERAL INFORMATION ONLY AND IS NOT TO BE USED TO DETERMINE PRECISE ICN PLACEMENT. CALL ONE CALL BEFORE EXCAVATION (1-800-292-8989 OR 811)

CONSTRUCTION DETAIL LOCATE PEDESTAL TYPICAL TRI-VIEW W/ISO LEVER TYPICAL LOCATE PEDESTAL

SCALE: NONE

	1	FOR
	2	
	3	
	4	
SIZE: 11 x 17	O:\Au	toCAD Standards

UPDATE

REVISION

8-21-1 s\TYPICALS\TYP_LOCATE PEDS.dwg