

Iowa Communications Network		Date:	04/09/19
Project Name: Davenport, IA National Guard, 5300 W. Kimberly Road			
Project Number: 82180305			
ICN Provided Material List (Warehouse Contact Paul Damage 515.725.4749)			
Item	ICN Part Number	Qty	Notes
FIBER CABLE			
48 strand Armored SM fiber		19,000	
HANDHOLES AND LIDS			
Bulk 24"x36"x36" with lid Tier 22	BULKU2436360061001	11	
Bulk Puck ICN Logo Black	ACC7734-125	10	
Bulk Puck ICN Logo Orange	ACC7334OR-125	1	Locate point only
LOCATE FACILITIES			
LOCATE STATIONS			
TRIVIEW Test Station w/ Isolever 72" ORANGE (with 3 ICN decals applied) (Walker)	TVT172OB-EM9125	2	
GROUNDING			
Erico 1/2" x 6' Ground Rod (Graybar)	611360	2	
Burndy 1/2" Ground Rod Clamp (Anixter)	GRC12	2	
MARKERS FLAGS DECALS			
ICN Snap Around Vulcan 4"X4" 15Mil Coiled Pvc (ICN-4X4-Sa)	1502345 (ICN-4x4-SA)	20	
T Post 6-ft Steel Studded	(provided with TriViews)	22	
TriView Warning Marker 78" with Orange Cap (with 3 decals - part number SD-9007K)	TVFL7800	22	
TERMINATION ITEMS: FDP, BULKHEADS, TRAYS, & RELATED			
Closet Connector Housing (CCH), 1 rack unit, holds 2 CCH cassettes	CCH-01U	1	FNS - Splicer
CCH Pigtailed Splice Cassette, 12 F, SC UPC Duplex, SM, SF PRE-ASSEMBLED	CCH-CS12-59-P00RE	1	FNS - Splicer
Leviton storage ring 24-inch	48900-OFR	1	Contractor
SPlicing MATERIALS			
SPlice CLOSURES			
450B FOSC 450 FIBER SPLICE CLOSURE B SIZE-6 CABLE PORTS-3 GROUNDSWITHOUT TRAY	FOSC450-B6-6-NT-0-B3V	2	FNS - Splicer
SPlice TRAYS			
B TRAY 24 FOSC-ACC-B-TRAY-24-KIT	863927-000	1	B case - FNS Splicer
BONDING & TRACING HARDWARE			
FOSC Closure Sealing Kit FAK-MULDRP-45-4P/CBL-ATT	1F6818-000	2	FNS Splicer
3M Scotchlok Shield Bond Connector 4460-D	4460-D	5	FNS Splicer