Iowa Department of Natural Resources Yellow River State Forest, Allamakee County 25CRDPBDDETT-0003 – Yellow River State Forest - New Fence Installation Project Description: Install approximately 2640 liner feet of new fence on boundary line.

## GENERAL NOTES:

Verify actual locations and elevations with DNR Engineer.
4 Strands of 12 ½ gauge steel wire with 4-point barbs spaced approximately 12 inches apart
6 foot steel fence posts at 8-10 feet spacing.
No wooden posts needed along the main line
8 inch treated wood of 2 inch galvanized pipe for corners. Brace wires from brace post to brace post. Excavate or drive to 3 ½ feet below grade.

## Alternate 1

If wooden posts are not able to be excavated or pounded 3 ½ feet into ground, install concrete base.

Site has limited access for vehicles, machinery and equipment.

All work shall conform to and be performed in accordance with all applicable codes and ordinances The contractor shall visit the site and inspect the project area and thoroughly familiarize themselves with the actual job conditions prior to bidding and start of work. Failure to visit the project site shall not relieve contractor from performing the work in accordance to the plans, specifications, special provisions and contract.

The contractor shall verify, at the site, all dimension and conditions shown on the plans and shall notify the DNR Engineer of any discrepancies, omissions, and/or conflicts prior to proceeding with the work. It shall be the contractor's responsibility to provide waste areas or disposal sites for excess material which is not desirable to be incorporated into the work involved on this project. No material shall be placed within the right-of-way, unless specifically stated in the plans or approved by the DNR Engineer. The contractor shall not disturb desirable grass areas or desirable trees outside the construction limits. The contractor shall not be permitted to park or service vehicles and equipment or use these areas for storage of materials. Storage, parking and service areas will be subject to the approval of the DNR Engineer.

Where utilities and fixtures are encountered within the construction area, it shall be the responsibility of the contractor to notify DNR Engineer of those utilities prior to the beginning of any construction. No claims for additional compensation will be allowed to the contractor for any interference or delay.

## **Yellow River State Forest**

New Fence Installation



Fence



mage © 2024 Airbus

Fence

600 ft

## **Yellow River State Forest**

- 🛆

New Fence Installation



Yellow River State Forest - Paint Creek Unit

Legend Fence Untitled Path

, 😇 p

N

3000 ft

Fence

Fence

-

Google Earth

Image © 2024 Airbus



