


SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 18 - T79N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



INDEX OF SHEETS

1. COVER SHEET
2. PLAN MAP
3. BUFFER AND BANK CROSS SECTION
4. PROFILE ALONG DISTRIBUTION LINE
5. STRUCTURE DETAILS
6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 6/30/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: All

ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	6/27/2023
DRAWN BY	ANDREW MACKRILL	DATE	6/27/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	6/30/2023
APPROVED BY			



COVER SHEET

FILE NAME



DRAWING SET

SHEET 1 OF 6








Staking Control Points(NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	607684.1	2228485.8	594.5
2	Distribution Line	608194.2	2228503.6	596.3
3	Distribution Line	608023.3	2228497.2	595.2
4	Distribution Line	607867.1	2228492.2	595.4
5	Distribution Line	607491.7	2228480.4	593.6
6	Distribution Line	607294.6	2228475.1	593.3
7	Benchmark	605598.3	2228463.9	595.6


PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 605598.3
 Easting: 2228463.9
 Elevation: 595.6
 Note: Benchmark is along the road in the southern part of the field

Legend

-  Proposed 6" Perforated CPT Distribution Line
-  Proposed 6" Non-Perforated CPT
-  Proposed 6" CMP Outlet
-  Existing 6" CPT Main
-  Proposed Water Control Structure
-  2' Contours
-  Staking Point




DESIGNED BY	ANDREW MACKRILL	DATE	6/27/23
DRAWN BY	ANDREW MACKRILL		6/27/23
CHECKED BY	ANDY CRAIG, PE, TSP		6/30/23
APPROVED BY			

PLAN MAP



FILE NAME	
DRAWING SET	SHEET 2 OF 6

Cross-Section



DESIGNED BY	ANDREW MACKRILL	DATE	6/27/23
DRAWN BY	ANDREW MACKRILL		6/27/23
CHECKED BY	ANDY CRAIG, PE, TSP		6/30/23
APPROVED BY			

BUFFER AND BANK CROSS SECTION



FILE NAME


DRAWING SET
SHEET 3 OF 6

LANDOWNER






LOCATION

SECTION 18 - T79N - R4W

Profile Along Distribution Line



Legend

-  All Season Water Table
-  Proposed Water Control Structure
-  Proposed 6" CPT Distribution Line
-  Existing Ground Surface
-  Lowest Farmed Elevation

DESIGNED BY	ANDREW MACKRILL	DATE	6/27/23
DRAWN BY	ANDREW MACKRILL		6/27/23
CHECKED BY	ANDY CRAIG, PE, TSP		6/30/23
APPROVED BY			

PROFILE ALONG DISTRIBUTION LINE



FILE NAME

DRAWING SET
SHEET 4 OF 6

LANDOWNER	-----	LOCATION	SECTION 18 - T79N - R4W
-----------	-------	----------	-------------------------


DATE 6/27/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

3 CHAMBER STRUCTURE DETAIL




FILE NAME
 DRAWING SET SHEET 5 OF 6

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.




TYPICAL SECTION




QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 6 in.	1	IA-21, IA-26, CPS-587
6" Non-perforated Pipe (ft)	20	IA-21, IA-45
6" CMP Outlet Pipe with Rodent Guard (ft)	35	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	900	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers



PLAN



IN-LINE CONTROL STRUCTURE

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE 6/27/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

CONSTRUCTION NOTES



FILE NAME

PA

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 18 - T79N - R4W

DENITRIFYING BIOREACTOR CONSTRUCTION PLANS

CEDAR COUNTY, IOWA
SECTION 15- T79N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. CROSS SECTION VIEW
 4. PROFILE ALONG CENTERLINE
 5. BIOREACTOR DETAIL
 6. STRUCTURE DETAIL
 7. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	8/28/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: All

ENGINEERING CLASS 3

DESIGNED BY	ANDY MACKRILL, TSP	DATE	8/28/2023
DRAWN BY	ANDY MACKRILL, TSP	DATE	8/28/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	8/28/2023
APPROVED BY			



COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 7

Staking Control Points (NAD 1983 State Plane Iowa South US SURVEY FEET)

Point	Description	Northing	Easting	Elevation
1	Southeast Corner B10	609875.1	2244512.9	697.8
2	Southwest Corner B10	609881.9	2244494.0	698.0
3	Northwest Corner B10	609957.4	2244521.0	697.4
4	Northeast Corner B10	609950.6	2244539.9	697.5
5	Inlet WCS (3-chamber)	609856.0	2244497.4	697.8
6	Outlet WCS (2-chamber)	609947.9	2244543.3	697.5
7	Benchmark	609751.8	2244469.1	701.9


DATE 8/28/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY _____

PLAN MAP

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 609751.8
 Easting: 2244469.1
 Elevation: 701.9

Legend


- Proposed 6" Perforated CPT
- Proposed 6" Non-Perforated CPT
- Existing 10" CPT Main
- Proposed 10" Non-Perf CPT Main
- Proposed 10" CMP Outlet
- Bioreactor Footprint
- Water Control Structure
- Benchmark
- 2 Foot Contours








FILE NAME

DRAWING SET
 SHEET 2 OF 7

Cross-Section



Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface

DATE 8/28/23
 DESIGNED BY ANDY MACKFILL
 DRAWN BY ANDY MACKFILL
 CHECKED BY ANDY CRAIG
 APPROVED BY _____

CROSS SECTION VIEW



FILE NAME

DRAWING SET
 SHEET 3 OF 7










LANDOWNER

LOCATION

SECTION 15 - T79N - R4W

Profile Along Centerline

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface
-  6" Non-Perforated CPT Pipe
-  Water Control Structure
-  6" Perforated CPT Manifold Pipe
-  Lowest Cropped Area

Grade backfill with existing ground to not create a channelized flow path

Lowest Cropped Elev 697.5

Inlet WCS Lid Elev. 700.0

Outlet WCS Lid Elev. 699.4

Existing ground surface

Mound backfill approximately 1 ft. to allow for settling and shed water

Place geotextile fabric at woodchip/soil interface.

Earth fill

Elevation

Woodchip fill

Inlet WCS stoplog Elev. 696.3

6" perforated CPT collection manifold

6" perforated CPT distribution manifold

Inlet WCS stoplog Elev. 694.6

Inlet WCS Sump Elev. 694.0

Outlet WCS SUMP ELEV. 693.4

0+00

0+30

0+60

0+90

1+00

Sta. 0+10 Elev. 693.8

Sta. 0+90 Elev. 693.6

Station

DATE 8/28/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY


PROFILE ALONG CENTERLINE



FILE NAME

DRAWING SET SHEET 4 OF 7

PLAN




Legend


- Earth Fill
- Woodchip Media
- Proposed 6" Perforated CPT
- Proposed 6" Non-Perforated CPT
- Existing 10" CPT Main
- Proposed 10" CMP Outlet
- Proposed 10" Non-Perforated CPT
- Plastic Liner
- Geotextile Fabric
- Existing Ground Surface
- Bioreactor Footprint

NOTES:

1. All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
2. Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
3. Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1" long by 1/2" thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
4. Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
5. Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
6. See Plan Map for benchmark coordinates.



ELEVATION



SECTION A-A



DATE	8/28/23
DESIGNED BY	ANDY MACKRILL
DRAWN BY	ANDY MACKRILL
CHECKED BY	ANDY CRAIG
APPROVED BY	

BIOREACTOR DETAIL



FILE NAME	
DRAWING SET	
SHEET 5 OF 7	


LANDOWNER		LOCATION	SECTION 15 - T79N - R4W
-----------	--	----------	-------------------------



Legend

	Earth Fill
	6" Non-Perforated CPT
	Existing 10" CPT Main
	Proposed 10" CPT Main
	Proposed 10" CMP Outlet
	Existing Ground Surface

**TYPICAL SECTION
UPSTREAM STRUCTURE**




**TYPICAL SECTION
DOWNSTREAM STRUCTURE**

Side Port Is On The (Circle One) Left / Right Side Of Structure, Looking Downstream

NOTES:

1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, on all lines: upstream, downstream and center. Pipe must be PVC, dual-wall CPT, or CMP.
2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745. Check valve must conform to ASTM D 3034 with SDR35 pipe or stronger.
3. Couplings between the water control structures and the non-perforated tile must be watertight.
4. Stop boards must provide must tight seals under a minimum of 1 foot pressure head (except notched board).
5. Appropriately mark bioreactor perimeter to avoid vehicle, implement, or livestock traffic.
6. Place structure and pipe coupler on a stable base. A stable base may be compacted earth, compacted fill sand, or a concrete pad. Extend the stable base no less than 1 foot beyond structure.
7. Excavated material placed around structure and pipes shall be hand compacted in 4" lifts.



IN-LINE CONTROL STRUCTURES

QUANTITIES*	
Water Control Structure, 3 Chamber $H_1 = 6$ ft. $d_1 = 10$ in. $d_2 = 6$ in.	1
Water Control Structure, 2 Chamber $H_2 = 6$ ft. $d_3 = 6$ in.	1
10" Non-perforated Pipe (ft)	40
10 CMP Outlet Pipe With Rodent Guard (ft)	25
6" Non-perforated Pipe (ft)	135
6" Perforated CPT (ft)	40
6" End Cap	2
Wood Chips (cu. yd.)	203
4 Mil Plastic (sq. yd.)**	291
Geotextile (sq. yd.)	178
Excavation (cu. yd.)	243
Earth Fill (cu. yd.)	89
6" Backflow Check Valve	1

* Quantities do not include tile/pipe couplers or extra material for geotextile/plastic overlap
 ** Accounts for 1 ft. overhang around perimeter

DATE	8/28/23
DESIGNED BY ANDY MACKRILL	8/28/23
DRAWN BY ANDY MACKRILL	8/28/23
CHECKED BY ANDY CRAIG	8/28/23
APPROVED BY	

STRUCTURE DETAIL



FILE NAME	
DRAWING SET	
SHEET 6 OF 7	

CONSTRUCTION NOTES

1. Tile elevations are based on Maverick tile probe depths and are to be considered accurate within margin of error of the instrument.
2. If any surface inlets are currently attached to the tile main or plan to be in the future, they shall be replaced with water quality inlets to minimize trash entry into the tile line before construction of the bioreactor begins.
3. Avoid excessive disturbance of any buffers or grassed water ways during construction. However, if re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded within 14 days according to NRCS Conservation Practice Standard IA-342 Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
4. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion.
5. All carbon media to be placed in the bioreactor shall come from an ESE approved vendor or approved with ESE staff prior to transportation and placement.
6. Contact an ESE representative for inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the bioreactor chamber and tile line trenches
 - b. After placing the water control structures and bioreactor manifolds
 - c. After placement of carbon media, before backfilling with soil
 - d. After connections to existing tile and final grading
7. Any product planned for use in construction must be approved by ESE prior to construction. Save and provide documentation to an ESE representative of all materials used in construction including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths
 - b. Photos and invoices for quantity and quality of woodchips/carbon media
 - c. Photos and invoices or product information to detail quantity and quality of plastic and geotextile fabric
 - d. Photos and invoices or product information for water control structures
8. Construction tolerances are ± 0.5 ft on bioreactor chamber dimensions, and ± 0.1 ft. on all elevations. Outlet WCS sump (bottom) must be below the elevation of the bioreactor chamber at the outlet end. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by a representative from ESE and will be noted in the as-built plan.
9. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.
10. All work shall be performed according to the IA construction and practice specifications in the table below.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-95	Geotextile
IA-605	Denitrifying Bioreactor
IA-620	Underground Outlet

DATE
8/28/23
DESIGNED BY ANDY MACKRILL
DRAWN BY ANDY MACKRILL
CHECKED BY ANDY CRAIG
APPROVED BY

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
SHEET 7 OF 7


SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 14 - T79N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa _____ 6/30/2023
	Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: _____ All


ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	6/24/2023
DRAWN BY	ANDREW MACKRILL	DATE	6/24/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	6/30/2023
APPROVED BY			



<h2>COVER SHEET</h2>	FILE NAME	
	DRAWING SET	SHEET 1 OF 6

PLAN VIEW



Staking Control Points(NAD 1983 State Plane South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	609246.9	2246533.9	694.7
2	Distribution Line	609133.5	2246603.7	694.5
3	Distribution Line	609048.5	2246656.8	694.1
4	Distribution Line	6078921.6	2246729.6	694.6
5	Distribution Line	608735.0	2247065.9	694.0
6	Distribution Line	608578.6	2247165.6	694.0
7	Benchmark	609359.8	2246203.8	695.0

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 609359.8
 Easting: 2246203.8
 Elevation: 695.0

Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 12" Non-Perforated CPT
- Proposed 12" CMP Outlet
- Existing 10" CPT Main
- Existing 6" CPT Main
- Proposed 10" Non-Perf CPT
- Proposed Water Control Structure
- 2' Contours
- Benchmark
- Staking Point

DATE: 6/24/23
 DESIGNED BY: ANDREW MACKRILL
 DRAWN BY: ANDREW MACKRILL
 CHECKED BY: ANDY CRAIG
 APPROVED BY:


PLAN MAP



FILE NAME

DRAWING SET
 SHEET 2 OF 6

Buffer Cross-Section




DESIGNED BY ANDREW MACKRILL 6/24/23
 DRAWN BY ANDREW MACKRILL 6/24/23
 CHECKED BY ANDY CRAIG 6/30/23
 APPROVED BY _____

BUFFER AND BANK CROSS SECTION



FILE NAME

DRAWING SET
 SHEET 3 OF 6



Proposed 3 Chamber WCS

Lowest Cropped
Elevation: 694.1 Ft.

Existing Ground Surface
Along Distribution Line

6" Perforated Pipe at 0.0% Grade.

Proposed
Management Weir
Elevation For All
Seasons: 692.1 Ft.

Existing 6" main with no flow.
Place 10' of non-per on each side

Legend

- All Season Water Table
- Proposed Water Control Structure
- Proposed 6" CPT Distribution Line
- Existing Ground Surface
- Lowest Farmed Elevation

DATE	DESIGNED BY	DATE
6/24/23	ANDREW MACKRILL	6/24/23
6/24/23	ANDREW MACKRILL	6/24/23
6/30/23	ANDY CRAIG	6/30/23
	APPROVED BY	

PROFILE ALONG DISTRIBUTION LINE



FILE NAME

DRAWING SET
SHEET 4 OF 6

LANDOWNER

LOCATION

SECTION 14 - T79N - R4W


DATE 6/24/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

3 CHAMBER STRUCTURE DETAIL




FILE NAME
 DRAWING SET
 SHEET 5 OF 6

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.




TYPICAL SECTION




QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 12 in.	1	IA-21, IA-26, CPS-587
10" Non-perforated Pipe (ft)	155	IA-21, IA-45
6" Non-perforated Pipe (ft)	20	IA-21, IA-45
12" Non-perforated Pipe (ft)	30	IA-21, IA-45
12" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	930	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers



PLAN



IN-LINE CONTROL STRUCTURE

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE 6/24/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
SHEET 6 OF 6


SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 14 - T79N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 7. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: <u> All </u>

ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE 6/24/2023
DRAWN BY	ANDREW MACKRILL	6/24/2023
CHECKED BY	ANDY CRAIG	6/30/2023
APPROVED BY		



COVER SHEET

FILE NAME

DRAWING SET



SHEET 1 OF 6

Staking Control Points(NAD 1983 State Plane South US Survey Feet)

Point	Description	Northing	Easting	Elevation
1	WCS	609375.0	2246258.0	693.8
2	Distribution Line	609355.5	2246122.6	694.3
3	Distribution Line	609158.8	2245759.9	695.2
4	Distribution Line	609135.3	2245607.9	696.5
5	Distribution Line	609157.2	2245550.2	696.4
6	Distribution Line	609673.3	2244851.3	696.9
7	Benchmark	609359.8	2246203.8	695.0

PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD 1983 State
 Plane Iowa South US Survey Feet)
 Northing: 609359.8
 Easting: 2246203.8
 Elevation: 695.0



DATE 6/24/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

PLAN MAP




Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 12" Non-Perforated CPT
- Proposed 12" CMP Outlet
- Existing 10" CPT Main
- Existing 6" CPT Main
- Proposed 6" CPT
- Proposed Water Control Structure
- 2' Contours
- Benchmark
- Staking Point



FILE NAME
 DRAWING SET
 SHEET 2 OF 6

Buffer Cross-Section




DESIGNED BY	ANDREW MACKRILL	DATE	6/24/23
DRAWN BY	ANDREW MACKRILL		6/24/23
CHECKED BY	ANDY CRAIG		6/30/23
APPROVED BY			

BUFFER AND BANK CROSS SECTION



FILE NAME	
DRAWING SET	SHEET 3 OF 6

LANDOWNER		LOCATION	SECTION 14 - T79N - R4W
-----------	--	----------	-------------------------



Legend

	All Season Water Table
	Proposed Water Control Structure
	Proposed 6" CPT Distribution Line
	Existing Ground Surface
	Lowest Farmed Elevation


DESIGNED BY ANDREW MACKRILL	DATE 6/24/23
DRAWN BY ANDREW MACKRILL	6/24/23
CHECKED BY ANDY CRAIG	6/30/23
APPROVED BY	

PROFILE ALONG DISTRIBUTION LINE



FILE NAME	
DRAWING SET	
SHEET 4 OF 6	

LANDOWNER	LOCATION	SECTION 14 - T79N - R4W
------------------	-----------------	--------------------------------




TYPICAL SECTION


- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 12 in.	1	IA-21, IA-26, CPS-587
6" Non-perforated Pipe (ft)	145	IA-21, IA-45
12" Non-perforated Pipe (ft)	32	IA-21, IA-45
12" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	1616	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers



PLAN



IN-LINE CONTROL STRUCTURE

DATE 6/24/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

3 CHAMBER STRUCTURE DETAIL



FILE NAME
 DRAWING SET
 SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE 6/24/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 7 OF 7

LANDOWNER

LOCATION

SECTION 14 - T79N - R4W


SATURATED BUFFER CONSTRUCTION PLANS

SCOTT CO, IOWA
SECTION 07 - T78N - R2E



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 8/3/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: _____ All

ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	8/3/2023
DRAWN BY	ANDREW MACKRILL	DATE	8/3/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	8/3/2023
APPROVED BY			



COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 6


Staking Control Points(NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	583890.8	2386401.3	724.4
2	Distribution Line	583816.5	2386599.4	725.1
3	Distribution Line	583879.0	2386451.4	724.6
4	Distribution Line	583911.1	2386375.0	724.4
5	Distribution Line	583970.2	2386237.3	724.1
6	Distribution Line	584051.1	2386048.8	723.7
7	Benchmark	584044.6	2386028.2	720.4

DATE 8/3/23
DESIGNED BY ANDREW MACKRILL
DRAWN BY ANDREW MACKRILL
CHECKED BY ANDY CRAIG, PE, TSP
APPROVED BY

PLAN MAP



FILE NAME
DRAWING SET SHEET 2 OF 6



PLAN VIEW


Benchmark:
Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
Northing: 584044.6
Easting: 2386028.2
Elevation: 720.4

Legend	
	Proposed 6" Perforated CPT Distribution Line
	Proposed 8" Non-Perforated CPT
	Proposed 8" CMP Outlet
	Existing 8" CPT Main
	Proposed Water Control Structure
	2' Contours
	Benchmark
	Staking Point

600' of 6" CPT at 0.0% Grade

New 8" CMP Outlet With Rodent Guard

Cross-Section



BUFFER AND BANK CROSS SECTION



FILE NAME


DRAWING SET
SHEET 3 OF 6

DESIGNED BY ANDREW MACKRILL 8/3/23
 DRAWN BY ANDREW MACKRILL 8/3/23
 CHECKED BY ANDY CRAIG, PE, TSP 8/3/23
 APPROVED BY _____

LANDOWNER

LOCATION

SECTION 07 - T78N - R2E



- #### Legend
- All Season Water Table
 - Proposed Water Control Structure
 - Proposed 6" CPT Distribution Line
 - Existing Ground Surface
 - Lowest Farmed Elevation


DATE
 DESIGNED BY ANDREW MACKRILL 8/3/23
 DRAWN BY ANDREW MACKRILL 8/3/23
 CHECKED BY ANDY CRAIG, PE, TSP 8/3/23
 APPROVED BY _____

PROFILE ALONG DISTRIBUTION LINE




FILE NAME

DRAWING SET
 SHEET 4 OF 6




TYPICAL SECTION




- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 8 in.	1	IA-21, IA-26, CPS-587
8" Non-perforated Pipe (ft)	30	IA-21, IA-45
8" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	600	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers



PLAN



IN-LINE CONTROL STRUCTURE

DATE 8/3/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

3 CHAMBER STRUCTURE DETAIL



FILE NAME
 DRAWING SET
 SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE
 DESIGNED BY ANDREW MACKRILL 8/3/23
 DRAWN BY ANDREW MACKRILL 8/3/23
 CHECKED BY ANDY CRAIG, PE, TSP 8/3/23
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 07 - T78N - R2E


DENITRIFYING BIOREACTOR CONSTRUCTION PLANS

CEDAR COUNTY, IOWA
SECTION 03- T79N - R04W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. CROSS SECTION VIEW
 4. PROFILE ALONG CENTERLINE
 5. BIOREACTOR DETAIL
 6. STRUCTURE DETAIL
 7. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	8/15/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: All

ENGINEERING CLASS 2

DESIGNED BY	ANDY MACKRILL, TSP	DATE	8/15/2023
DRAWN BY	ANDY MACKRILL, TSP	DATE	8/15/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	8/15/2023
APPROVED BY			





COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 7

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Located approx. 420 Ft. North of outlet
 Northing: 621088.2
 Easting: 2243032.1
 Elevation: 716.1













Staking Control Points (NAD 1983 State Plane Iowa South US SURVEY FEET)				
Point	Description	Northing	Easting	Elevation
1	Southeast Corner BID	620616.7	2243058.1	716.5
2	Southwest Corner BID	620606.8	2243046.7	716.9
3	Northwest Corner BID	620652.8	2243007.8	717.9
4	Northeast Corner BID	620662.7	2243019.3	717.4
5	Inlet WCS (3-chamber)	620679.3	2243003.3	717.8
6	Outlet WCS (2-chamber)	620620.7	2243058.7	716.5
7	Benchmark	621088.2	2243032.1	716.1

DATE 8/15/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY _____

PLAN MAP

Legend

-  Proposed 6" Perforated CPT
-  Proposed 6" Non-Perforated CPT
-  Existing 6" CPT Main
-  Proposed 6" CMP Outlet
-  Bioreactor Footprint
-  Water Control Structure
-  Benchmark
-  2 Foot Contours








New 6" CMP Outlet
 With Rodent Guard


Approx. Grade 4.2%
 Connecting to
 Existing Outlet.



Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface

Cross-Section



DESIGNED BY	ANDY MACKRILL	DATE	8/15/23
DRAWN BY	ANDY MACKRILL	DATE	8/15/23
CHECKED BY	ANDY CRAIG	DATE	8/15/23
APPROVED BY			


CROSS SECTION VIEW



FILE NAME	
DRAWING SET	
SHEET 3 OF 7	

Profile Along Centerline

Grade backfill with existing ground to not create a channelized flow path



Legend

- Earth Fill
- Woodchip Media
- Plastic Liner
- Geotextile Fabric
- Existing Ground Surface
- 6" Non-Perforated CPT Pipe
- Water Control Structure
- 6" Perforated CPT Manifold Pipe
- Lowest Cropped Elevation

DATE	8/15/23
DESIGNED BY ANDY MACKFILL	8/15/23
DRAWN BY ANDY MACKFILL	8/15/23
CHECKED BY ANDY CRAIG	8/15/23
APPROVED BY	


PROFILE ALONG CENTERLINE



FILE NAME	
DRAWING SET	
SHEET 4 OF 7	

LANDOWNER		LOCATION	SECTION 03 - T79N - R04W
-----------	--	----------	--------------------------

Station



Legend



- Earth Fill
- Woodchip Media
- Proposed 6" Perforated CPT
- Proposed 6" Non-Perforated CPT
- Existing 6" CPT Main
- Proposed 6" CMP Outlet
- Plastic Liner
- Geotextile Fabric
- Existing Ground Surface
- Bioreactor Footprint




NOTES:

1. All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
2. Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
3. Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1" long by 1/2" thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
4. Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
5. Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
6. See Plan Map for benchmark coordinates.


DATE	8/15/23	8/15/23
DESIGNED BY ANDY MACKRILL	DRAWN BY ANDY MACKRILL	CHECKED BY ANDY CRAIG
		APPROVED BY

BIOREACTOR DETAIL






**TYPICAL SECTION
UPSTREAM STRUCTURE**



**TYPICAL SECTION
DOWNSTREAM STRUCTURE**

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, on all lines: upstream, downstream and center. Pipe must be PVC, dual-wall CPT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745. Check valve must conform to ASTM D 3034 with SDR35 pipe or stronger.
 3. Couplings between the water control structures and the non-perforated tile must be watertight.
 4. Stop boards must provide must tight seals under a minimum of 1 foot pressure head (except notched board).
 5. Appropriately mark bioreactor perimeter to avoid vehicle, implement, or livestock traffic.
 6. Place structure and pipe coupler on a stable base. A stable base may be compacted earth, compacted fill sand, or a concrete pad. Extend the stable base no less than 1 foot beyond structure.
 7. Excavated material placed around structure and pipes shall be hand compacted in 4" lifts.



IN-LINE CONTROL STRUCTURES

QUANTITIES*	
Water Control Structure, 3 Chamber $H_1 = 6$ ft. $d_1 = 6$ in. $d_2 = 6$ in.	1
Water Control Structure, 2 Chamber $H_2 = 6$ ft. $d_3 = 6$ in.	1
6" Non-perforated Pipe (ft)	125
6" CMP Outlet Pipe With Rodent Guard (ft)	20
6" Perforated CPT (ft)	30
6" End Cap	2
Wood Chips (cu. yd.)	110
4 Mil Plastic (sq. yd.)**	183
Geotextile (sq. yd.)	100
Excavation (cu. yd.)	134
Earth Fill (cu. yd.)	50
6" Backflow Check Valve	1

* Quantities do not include tile/pipe couplers or extra material for geotextile/plastic overlap
 ** Accounts for 1 ft. overhang around perimeter

DATE 8/15/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

STRUCTURE DETAIL



CONSTRUCTION NOTES

1. Tile elevations are based on Maverick tile probe depths and are to be considered accurate within margin of error of the instrument.
2. If any surface inlets are currently attached to the tile main or plan to be in the future, they shall be replaced with water quality inlets to minimize trash entry into the tile line before construction of the bioreactor begins.
3. Avoid excessive disturbance of any buffers or grassed water ways during construction. However, if re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded within 14 days according to NRCS Conservation Practice Standard IA-342 Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
4. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion.
5. All carbon media to be placed in the bioreactor shall come from an ESE approved vendor or approved with ESE staff prior to transportation and placement.
6. Contact an ESE representative for inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the bioreactor chamber and tile line trenches
 - b. After placing the water control structures and bioreactor manifolds
 - c. After placement of carbon media, before backfilling with soil
 - d. After connections to existing tile and final grading
7. Any product planned for use in construction must be approved by ESE prior to construction. Save and provide documentation to an ESE representative of all materials used in construction including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths
 - b. Photos and invoices for quantity and quality of woodchips/carbon media
 - c. Photos and invoices or product information to detail quantity and quality of plastic and geotextile fabric
 - d. Photos and invoices or product information for water control structures
8. Construction tolerances are ± 0.5 ft on bioreactor chamber dimensions, and ± 0.1 ft. on all elevations. Outlet WCS sump (bottom) must be below the elevation of the bioreactor chamber at the outlet end. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by a representative from ESE and will be noted in the as-built plan.
9. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.
10. All work shall be performed according to the IA construction and practice specifications in the table below.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-95	Geotextile
IA-605	Denitrifying Bioreactor
IA-620	Underground Outlet

DATE
8/15/23
DESIGNED BY ANDY MACKRILL
DRAWN BY ANDY MACKRILL
CHECKED BY ANDY CRAIG
APPROVED BY

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
SHEET 7 OF 7


DENITRIFYING BIOREACTOR CONSTRUCTION PLANS

CEDAR COUNTY, IOWA
SECTION 33- T79N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. CROSS SECTION VIEW
 4. PROFILE ALONG CENTERLINE
 5. BIOREACTOR DETAIL
 6. STRUCTURE DETAIL
 7. CONSTRUCTION NOTES

ENGINEERING CLASS 3

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 09/08/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2023. Pages or sheets covered by this seal: <u>All</u>

DESIGNED BY	BEN REINHART	DATE	09/08/2023
DRAWN BY	BEN REINHART	DATE	09/08/2023
CHECKED BY	ANDY CRAIG, PE	DATE	09/08/2023
APPROVED BY			





COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 7

Benchmark:
 Top of Lath Hub, located approx. 320 ft. southeast of
 planned outlet structure on north side of railroad ditch
 (NAD83, Iowa South, USFt)
 Northing: 590861.645
 Easting: 2238550.906
 Elevation: 669.6



Staking Control Points (NAD83, Iowa South, USFt)				
Point	Description	Northing	Easting	Elevation
1	Benchmark	590861.645	2238550.906	669.6
2	Inlet WCS (3-chamber)	591167.285	2238340.485	667.1
3	Outlet WCS (2-chamber)	591060.953	2238311.689	669.0
4	Northwest Corner BID	591111.247	2238244.863	669.1
5	Northeast Corner BID	591126.983	2238257.206	669.4
6	Southeast Corner BID	591077.610	2238320.153	668.3
7	Southwest Corner BID	591061.873	2238307.810	669.1

DATE 09/08/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY _____


PLAN MAP



FILE NAME
 .4
 DRAWING SET
 SHEET 2 OF 7

Legend

- Existing 8" CPT Main
- Proposed 8" Non-Perf CPT Main
- Proposed 6" Non-Perf CPT
- Proposed 6" Perf CPT
- Proposed 8" CMP Outlet
- Bioreactor Footprint
- Staking Points
- Water Control Structure
- 2-Ft Contours



Bioreactor Cross Section

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface

Grade backfill with existing ground to not create a channelized flow path


Ensure positive drainage away from the bioreactor to prevent ponding or creation of flow paths for surface water

Existing ground surface

Recommend placing approximately 1 ft. of plastic liner outside of chamber and hold in place with stakes

Place geotextile fabric at woodchip/soil interface. Elev. 667.5

4 mil plastic liner to line bioreactor chamber





DATE 09/08/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY _____

CROSS SECTION VIEW




FILE NAME
 DRAWING SET
 SHEET 3 OF 7






PLAN

SECTION A-A



ELEVATION



Legend

- Earth Fill
- Woodchip Media
- Existing 8" Perf CPT Main
- Proposed 8" Non-Perf CPT
- Proposed 6" Non-Perf CPT
- Proposed 6" Perf CPT
- Proposed 8" CMP Outlet
- Plastic Liner
- Geotextile Fabric
- Existing Ground Surface
- Bioreactor Footprint

NOTES:

1. All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
2. Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
3. Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1-inch long by 1/2-inch thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
4. Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
5. Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
6. See Plan Map for benchmark coordinates.

DATE	09/08/23
DESIGNED BY BEN REINHART	09/08/23
DRAWN BY BEN REINHART	09/08/23
CHECKED BY ANDY CRAIG, PE	09/08/23
APPROVED BY	


BIOREACTOR DETAIL




FILE NAME	
DRAWING SET	
SHEET 5 OF 7	

LANDOWNER		LOCATION	SECTION 33 - T79N - R4W
-----------	--	----------	-------------------------

TYPICAL SECTION UPSTREAM 3-COMPARTMENT STRUCTURE



TYPICAL SECTION DOWNSTREAM 2-COMPARTMENT STRUCTURE



QUANTITIES*

Water Control Structure, 3 Chamber ($H_1 = 6$ ft. $d_1 = 8$ in. $d_2 = 6$ in.)	1
Water Control Structure, 2 Chamber ($H_2 = 8$ ft. $d_3 = 6$ in.)	1
8" Non-perforated Pipe (ft)	40
6" Non-perforated Pipe (ft)	165
6" Perforated CPT (ft)	40
8" CMP Outlet with Rodent Guard (ft)	20
6" End Cap (each)	3
Wood Chips (cu. yd.)	242
4 Mil Plastic (sq. yd.)**	307
Geotextile (sq. yd.)	178
Excavation (cu. yd.)	309
Earth Fill (cu. yd.)	119
6" Backflow Check Valve (each)	1


* Quantities do not include tile/pipe couplers or extra material for geotextile/plastic overlap
 ** Accounts for 1 ft. overhang around perimeter

NOTES:

1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, on all lines: upstream, downstream and center. Pipe must be PVC, dual-wall CPT, or CMP.
2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745. Check valve must conform to ASTM D 3034 with SDR35 pipe or stronger.
3. Couplings between the water control structures and the non-perforated tile must be watertight.
4. Stop boards must provide must tight seals under a minimum of 1 foot pressure head (except notched board).
5. Appropriately mark bioreactor perimeter to avoid vehicle, implement, or livestock traffic.
6. Place structure and pipe coupler on a stable base. A stable base may be compacted earth, compacted fill sand, or a concrete pad. Extend the stable base no less than 1 foot beyond structure.
7. Excavated material placed around structure and pipes shall be hand compacted in 4" lifts.

DETAIL 1

Cut 1" Notch In Bottom Of The Bottom Board On The Downstream Structure




Legend

- Earth Fill
- Existing 8" Perf CPT Main
- Proposed 8" Non-Perf CPT
- Proposed 6" Non-Perf CPT
- Existing Ground
- Control Structure Stoplogs

IN-LINE CONTROL STRUCTURES

Side Port Is On The (Circle One) Left/Right Side Of Structure, Looking Downstream



DATE 09/08/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY

STRUCTURE DETAIL



FILE NAME

DRAWING SET
 SHEET 6 OF 7

LANDOWNER

LOCATION

SECTION 33 - T79N - R4W

CONSTRUCTION NOTES

1. Tile elevations are based on Maverick tile probe depths and are to be considered accurate within margin of error of the instrument.
2. If any surface inlets are currently attached to the tile main or plan to be in the future, they shall be replaced with water quality inlets to minimize trash entry into the tile line before construction of the bioreactor begins.
3. Avoid excessive disturbance of any buffers or grassed water ways during construction. However, if re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded within 14 days according to NRCS Conservation Practice Standard IA-342 Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
4. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion.
5. All carbon media to be placed in the bioreactor shall come from an ESE approved vendor or approved with ESE staff prior to transportation and placement.
6. Contact an NRCS representative for inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the bioreactor chamber and tile line trenches
 - b. After placing the water control structures and bioreactor manifolds
 - c. After placement of carbon media, before backfilling with soil
 - d. After connections to existing tile and final grading
7. Any product planned for use in construction must be approved by ESE prior to construction. Save and provide documentation to an NRCS representative of all materials used in construction including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths
 - b. Photos and invoices for quantity and quality of woodchips/carbon media
 - c. Photos and invoices or product information to detail quantity and quality of plastic and geotextile fabric
 - d. Photos and invoices or product information for water control structures
8. Construction tolerances are ± 0.5 ft on bioreactor chamber dimensions, and ± 0.1 ft. on all elevations. Outlet WCS sump (bottom) must be below the elevation of the bioreactor chamber at the outlet end. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by a representative from ESE or NRCS and will be noted in the as-built plan.
9. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.
10. All work shall be performed according to the IA construction and practice specifications in the table below.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-95	Geotextile
IA-605	Denitrifying Bioreactor
IA-620	Underground Outlet

DATE
 09/08/23
 DESIGNED BY BEN REINHART
 09/08/23
 DRAWN BY BEN REINHART
 09/08/23
 CHECKED BY ANDY CRAIG, PE
 09/08/23
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME
 .
 DRAWING SET
 SHEET 7 OF 7


DENITRIFYING BIOREACTOR CONSTRUCTION PLANS

CEDAR COUNTY, IOWA
SECTION 33- T79N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. CROSS SECTION VIEW
 4. PROFILE ALONG CENTERLINE
 5. BIOREACTOR DETAIL
 6. STRUCTURE DETAIL
 7. CONSTRUCTION NOTES

ENGINEERING CLASS 5

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 09/08/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2023. Pages or sheets covered by this seal: <u>All</u>

DESIGNED BY	BEN REINHART	DATE	09/07/2023
DRAWN BY	BEN REINHART	DATE	09/07/2023
CHECKED BY	ANDY CRAIG, PE	DATE	09/08/2023
APPROVED BY			





COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 7

Benchmark:
 Top of Lath Hub (NAD83, Iowa South, USFt)
 Northing: 590014.512
 Easting: 2237384.267
 Elevation: 667.7




Staking Control Points (NAD83, Iowa South, USFt)				
Point	Description	Northing	Easting	Elevation
1	Benchmark	590014.512	2237384.267	667.7
2	Inlet WCS (3-chamber)	590093.9491'	2237190.5790'	665.5
3	Outlet WCS (2-chamber)	589985.6505'	2237259.1809'	665.9
4	Northwest Corner BID	590038.5199'	2237180.6080'	665.3
5	Northeast Corner BID	590060.8792'	2237203.5004'	665.6
6	Southeast Corner BID	590003.6480'	2237259.3985'	666.2
7	Southwest Corner BID	589981.2888'	2237236.5061'	665.8

DATE: 09/07/23
 DESIGNED BY: BEN REINHART
 DRAWN BY: BEN REINHART
 CHECKED BY: ANDY CRAIG, PE
 APPROVED BY:

PLAN MAP

Legend

- Existing 12" CPT Main
- Proposed 12" Non-Perf CPT Main
- Proposed 8" Non-Perf CPT
- Proposed 6" Non-Perf CPT
- Proposed 6" Perf CPT
- Proposed 12" CMP Outlet
- Bioreactor Footprint
- Staking Points
- Water Control Structure
- Benchmark
- 2-Ft Contours



FILE NAME

DRAWING SET
 SHEET 2 OF 7

Bioreactor Cross Section

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface

Grade backfill with existing ground to not create a channelized flow path


Existing ground surface

Place geotextile fabric at woodchip/soil interface. Elev. 664.0

Ensure positive drainage away from the bioreactor to prevent ponding or creation of flow paths for surface water

Recommend placing approximately 1 ft. of plastic liner outside of chamber and hold in place with stakes

4 mil plastic liner to line bioreactor chamber




DATE
DESIGNED BY BEN REINHART 09/07/23
DRAWN BY BEN REINHART 09/07/23
CHECKED BY ANDY CRAIG, PE 09/08/23
APPROVED BY _____

CROSS SECTION VIEW



FILE NAME
DRAWING SET
SHEET 3 OF 7




- Legend**
- Earth Fill
 - Woodchip Media
 - Existing Ground Surface
 - Lowest Crop Elevation
 - Geotextile Fabric
 - 6" Non-Perforated CPT Pipe
 - 8" Non-Perforated CPT Pipe
 - 6" Perforated CPT Manifold Pipe
 - Water Control Structure
 - Stoplogs

DATE
 09/07/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY

PROFILE ALONG CENTERLINE



FILE NAME
 DRAWING SET
 SHEET 4 OF 7



PLAN

Legend

- Earth Fill
- Woodchip Media
- Existing 12" Perf CPT Main
- Proposed 12" Non-Perf CPT
- Proposed 8" Non-Perf CPT
- Proposed 6" Non-Perf CPT
- Proposed 6" Perf CPT
- Proposed 12" CMP Outlet
- Plastic Liner
- Geotextile Fabric
- Existing Ground Surface
- Bioreactor Footprint

NOTES:

1. All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
2. Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
3. Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1-inch long by 1/2-inch thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
4. Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
5. Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
6. See Plan Map for benchmark coordinates.

DATE	09/07/23
DESIGNED BY	BEN REINHART
DRAWN BY	BEN REINHART
CHECKED BY	ANDY CRAIG, PE
APPROVED BY	

BIOREACTOR DETAIL

ELEVATION


SECTION A-A




FILE NAME	
DRAWING SET	
SHEET 5 OF 7	

LANDOWNER		LOCATION	SECTION 33 - T79N - R4W
-----------	--	----------	-------------------------

TYPICAL SECTION UPSTREAM 3-COMPARTMENT STRUCTURE




TYPICAL SECTION DOWNSTREAM 2-COMPARTMENT STRUCTURE



QUANTITIES*	
Water Control Structure, 3 Chamber (H ₁ = 8 ft. d ₁ = 12 in. d ₂ = 6 in.)	1
Water Control Structure, 2 Chamber (H ₂ = 8 ft. d ₃ = 8 in.)	1
12" Non-perforated Pipe (ft)	40
8" Non-perforated Pipe (ft)	80
6" Non-perforated Pipe (ft)	60
6" Perforated CPT (ft)	64
12" CMP Outlet with Rodent Guard (ft)	20
6" End Cap (each)	4
Wood Chips (cu. yd.)	439
4 Mil Plastic (sq. yd.)**	448
Geotextile (sq. yd.)	285
Excavation (cu. yd.)	541
Earth Fill (cu. yd.)	190
8" Backflow Check Valve (each)	1

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, on all lines: upstream, downstream and center. Pipe must be PVC, dual-wall CPT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745. Check valve must conform to ASTM D 3034 with SDR35 pipe or stronger.
 3. Couplings between the water control structures and the non-perforated tile must be watertight.
 4. Stop boards must provide must tight seals under a minimum of 1 foot pressure head (except notched board).
 5. Appropriately mark bioreactor perimeter to avoid vehicle, implement, or livestock traffic.
 6. Place structure and pipe coupler on a stable base. A stable base may be compacted earth, compacted fill sand, or a concrete pad. Extend the stable base no less than 1 foot beyond structure.
 7. Excavated material placed around structure and pipes shall be hand compacted in 4" lifts.


DETAIL 1



Legend	
	Earth Fill
	Existing 12" Perf CPT Main
	Proposed 12" Non-Perf CPT
	Proposed 8" Non-Perf CPT
	Existing Ground
	Control Structure Stoplogs

IN-LINE CONTROL STRUCTURES

Side Port Is On The (Circle One) Left, Right Side Of Structure, Looking Downstream



DATE 09/07/23
DESIGNED BY BEN REINHART
DRAWN BY BEN REINHART
CHECKED BY ANDY CRAIG, PE
APPROVED BY

STRUCTURE DETAIL



FILE NAME
DRAWING SET
SHEET 6 OF 7

CONSTRUCTION NOTES

1. Tile elevations are based on Maverick tile probe depths and are to be considered accurate within margin of error of the instrument.
2. If any surface inlets are currently attached to the tile main or plan to be in the future, they shall be replaced with water quality inlets to minimize trash entry into the tile line before construction of the bioreactor begins.
3. Avoid excessive disturbance of any buffers or grassed water ways during construction. However, if re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded within 14 days according to NRCS Conservation Practice Standard IA-342 Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
4. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion.
5. All carbon media to be placed in the bioreactor shall come from an ESE approved vendor or approved with ESE staff prior to transportation and placement.
6. Contact an NRCS representative for inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the bioreactor chamber and tile line trenches
 - b. After placing the water control structures and bioreactor manifolds
 - c. After placement of carbon media, before backfilling with soil
 - d. After connections to existing tile and final grading
7. Any product planned for use in construction must be approved by ESE prior to construction. Save and provide documentation to an NRCS representative of all materials used in construction including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths
 - b. Photos and invoices for quantity and quality of woodchips/carbon media
 - c. Photos and invoices or product information to detail quantity and quality of plastic and geotextile fabric
 - d. Photos and invoices or product information for water control structures
8. Construction tolerances are ± 0.5 ft on bioreactor chamber dimensions, and ± 0.1 ft. on all elevations. Outlet WCS sump (bottom) must be below the elevation of the bioreactor chamber at the outlet end. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by a representative from ESE or NRCS and will be noted in the as-built plan.
9. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.
10. All work shall be performed according to the IA construction and practice specifications in the table below.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-95	Geotextile
IA-605	Denitrifying Bioreactor
IA-620	Underground Outlet

DATE
 09/07/23
 DESIGNED BY BEN REINHART
 09/07/23
 DRAWN BY BEN REINHART
 09/08/23
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 7 OF 7


DENITRIFYING BIOREACTOR CONSTRUCTION PLANS

CEDAR COUNTY, IOWA
SECTION 33- T79N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. CROSS SECTION VIEW
 4. PROFILE ALONG CENTERLINE
 5. BIOREACTOR DETAIL
 6. STRUCTURE DETAIL
 7. CONSTRUCTION NOTES

ENGINEERING CLASS 4

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 09/08/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2023. Pages or sheets covered by this seal: <u>All</u>

DESIGNED BY	BEN REINHART	DATE	09/06/2023
DRAWN BY	BEN REINHART	DATE	09/06/2023
CHECKED BY	ANDY CRAIG, PE	DATE	09/08/2023
APPROVED BY			





COVER SHEET

FILE NAME

DRAWING SET
SHEET 1 OF 7

Benchmark:
 Top of Lath Hub (NAD83, Iowa South, USFt)
 Northing: 590014.512
 Easting: 2237384.267
 Elevation: 667.7



Staking Control Points (NAD83, Iowa South, USFt)				
Point	Description	Northing	Easting	Elevation
1	Benchmark	590014.512	2237384.267	667.7
2	Inlet WCS (3-chamber)	590041.832	2237245.005	665.9
3	Outlet WCS (2-chamber)	590005.404	2237323.116	666.1
4	Northwest Corner BID	590050.600	2237250.118	665.7
5	Northeast Corner BID	590069.713	2237266.233	665.7
6	Southeast Corner BID	590018.146	2237327.395	666.1
7	Southwest Corner BID	589999.033	2237311.280	666.0

DATE
 09/06/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY _____

PLAN MAP



Reconnect to new section of 8" non-perforated CPT, ensuring positive drainage to outlet

New 8" CMP Outlet with Rodent Guard

Legend

- Existing 8" CPT Main
- Proposed 8" Non-Perf CPT Main
- Proposed 6" Non-Perf CPT
- Proposed 6" Perf CPT
- Proposed 8" CMP Outlet
- Bioreactor Footprint
- ⊗ Staking Points
- Water Control Structure
- Benchmark
- 2-Ft Contours



FILE NAME

DRAWING SET
 SHEET 2 OF 7

Bioreactor Cross Section


Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface

Grade backfill with existing ground to not create a channelized flow path

Existing ground surface

Place geotextile fabric at woodchip/soil interface. Elev. 664.0



Ensure positive drainage away from the bioreactor to prevent ponding or creation of flow paths for surface water

Recommend placing approximately 1 ft. of plastic liner outside of chamber and hold in place with stakes

4 mil plastic liner to line bioreactor chamber

DATE
 09/06/23
 DESIGNED BY BEN REINHART
 09/06/23
 DRAWN BY BEN REINHART
 09/08/23
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY _____

CROSS SECTION VIEW



FILE NAME
 4
 DRAWING SET
 SHEET 3 OF 7

DATE 09/06/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY

PROFILE ALONG CENTERLINE





FILE NAME
 DRAWING SET
 SHEET 4 OF 7

Legend

- Earth Fill
- Woodchip Media
- Existing Ground Surface
- Lowest Crop Elevation
- Plastic Liner
- Geotextile Fabric
- 6" Non-Perforated CPT Pipe
- 6" Perforated CPT Manifold Pipe
- Water Control Structure
- Stoplogs

Profile Along Centerline





- NOTES:
1. All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
 2. Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
 3. Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1-inch long by 1/2-inch thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
 4. Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
 5. Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
 6. See Plan Map for benchmark coordinates.


DATE
 DESIGNED BY BEN REINHART 09/06/23
 DRAWN BY BEN REINHART 09/06/23
 CHECKED BY ANDY CRAIG, PE 09/08/23
 APPROVED BY

BIOREACTOR DETAIL




FILE NAME
 DRAWING SET
 SHEET 5 OF 7

TYPICAL SECTION UPSTREAM 3-COMPARTMENT STRUCTURE



TYPICAL SECTION DOWNSTREAM 2-COMPARTMENT STRUCTURE




QUANTITIES*	
Water Control Structure, 3 Chamber (H ₁ = 6 ft. d ₁ = 8 in. d ₂ = 6 in.)	1
Water Control Structure, 2 Chamber (H ₂ = 8 ft. d ₃ = 6 in.)	1
8" Non-perforated Pipe (ft)	50
6" Non-perforated Pipe (ft)	40
6" Perforated CPT (ft)	50
8" CMP Outlet with Rodent Guard (ft)	20
6" End Cap (each)	3
Wood Chips (cu. yd.)	318
4 Mil Plastic (sq. yd.)**	365
Geotextile (sq. yd.)	223
Excavation (cu. yd.)	430
Earth Fill (cu. yd.)	178
6" Backflow Check Valve (each)	1

NOTES:

1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, on all lines: upstream, downstream and center. Pipe must be PVC, dual-wall CPT, or CMP.
2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745. Check valve must conform to ASTM D 3034 with SDR35 pipe or stronger.
3. Couplings between the water control structures and the non-perforated tile must be watertight.
4. Stop boards must provide must tight seals under a minimum of 1 foot pressure head (except notched board).
5. Appropriately mark bioreactor perimeter to avoid vehicle, implement, or livestock traffic.
6. Place structure and pipe coupler on a stable base. A stable base may be compacted earth, compacted fill sand, or a concrete pad. Extend the stable base no less than 1 foot beyond structure.
7. Excavated material placed around structure and pipes shall be hand compacted in 4" lifts.

DETAIL 1

Cut 1" Notch In Bottom Of The Bottom Board On The Downstream Structure




Legend

- Earth Fill
- Existing 8" Perf CPT Main
- Proposed 8" Non-Perf CPT
- Proposed 6" Non-Perf CPT
- Existing Ground
- Control Structure Stoplogs

IN-LINE CONTROL STRUCTURES

Side Port Is On The (Circle One) Left/Right Side Of Structure, Looking Downstream



DATE
DESIGNED BY BEN REINHART 09/06/23
DRAWN BY BEN REINHART 09/06/23
CHECKED BY ANDY CRAIG, PE 09/08/23
APPROVED BY

STRUCTURE DETAIL



FILE NAME
DRAWING SET
SHEET 6 OF 7

CONSTRUCTION NOTES

1. Tile elevations are based on Maverick tile probe depths and are to be considered accurate within margin of error of the instrument.
2. If any surface inlets are currently attached to the tile main or plan to be in the future, they shall be replaced with water quality inlets to minimize trash entry into the tile line before construction of the bioreactor begins.
3. Avoid excessive disturbance of any buffers or grassed water ways during construction. However, if re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded within 14 days according to NRCS Conservation Practice Standard IA-342 Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
4. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion.
5. All carbon media to be placed in the bioreactor shall come from an ESE approved vendor or approved with ESE staff prior to transportation and placement.
6. Contact an NRCS representative for inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the bioreactor chamber and tile line trenches
 - b. After placing the water control structures and bioreactor manifolds
 - c. After placement of carbon media, before backfilling with soil
 - d. After connections to existing tile and final grading
7. Any product planned for use in construction must be approved by ESE prior to construction. Save and provide documentation to an NRCS representative of all materials used in construction including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths
 - b. Photos and invoices for quantity and quality of woodchips/carbon media
 - c. Photos and invoices or product information to detail quantity and quality of plastic and geotextile fabric
 - d. Photos and invoices or product information for water control structures
8. Construction tolerances are ± 0.5 ft on bioreactor chamber dimensions, and ± 0.1 ft. on all elevations. Outlet WCS sump (bottom) must be below the elevation of the bioreactor chamber at the outlet end. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by a representative from ESE or NRCS and will be noted in the as-built plan.
9. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.
10. All work shall be performed according to the IA construction and practice specifications in the table below.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-95	Geotextile
IA-605	Denitrifying Bioreactor
IA-620	Underground Outlet

DATE
 09/06/23
 DESIGNED BY BEN REINHART
 09/06/23
 DRAWN BY BEN REINHART
 09/08/23
 CHECKED BY ANDY CRAIG, PE
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 7 OF 7


DENITRIFYING BIOREACTOR CONSTRUCTION PLANS

CEDAR COUNTY, IOWA
SECTION 04- T80N - R02W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. CROSS SECTION VIEW
 4. PROFILE ALONG CENTERLINE
 5. BIOREACTOR DETAIL
 6. STRUCTURE DETAIL
 7. CONSTRUCTION NOTES



I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa

Andy J. Craig 9/22/2023
 Andy J. Craig, P.E.
 License number: 20832
 My license renewal date is December 31, 2025.
 Pages or sheets covered by this seal: All

ENGINEERING CLASS 3

DESIGNED BY	ANDY MACKRILL, TSP	DATE	9/18/2023
DRAWN BY	ANDY MACKRILL, TSP	DATE	9/18/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	9/22/2023
APPROVED BY			




COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 7

Benchmark:
 Top of Lath (NAD 1983 State
 Plane Iowa South US Survey Feet)
 Northing: 650901.3
 Easting: 2297078.6
 Elevation: 739.1



Staking Control Points (NAD 1983 State Plane Iowa South US SURVEY FEET)				
Point	Description	Northing	Easting	Elevation
1	Southeast Corner BID	650763.5	2297074.7	737.7
2	Southwest Corner BID	650765.3	2297054.7	737.7
3	Northwest Corner BID	650845.2	229706.2	738.2
4	Northeast Corner BID	650843.3	2297082.0	738.1
5	Inlet WCS (3-chamber)	650771.2	2297051.9	737.7
6	Outlet WCS (2-chamber)	650714.9	2297054.0	737.1
7	Benchmark	650901.3	2297078.6	739.1









DATE 9/18/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY _____


PLAN MAP

New 6" CMP Outlet
 With Rodent Guard


Replace existing outlet
 New Elev : 731.5

Legend






-  Proposed 6" Perforated CPT
-  Proposed 6" Non-Perforated CPT
-  Existing 6" CPT Main
-  Proposed 6" CMP Outlet
-  Bioreactor Footprint
-  Water Control Structure
-  Benchmark
-  2 Foot Contours



Cross-Section



Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface

DESIGNED BY	ANDY MACKFILL	DATE	9/18/23
DRAWN BY	ANDY MACKFILL	DATE	9/18/23
CHECKED BY	ANDY CRAIG	DATE	9/22/23
APPROVED BY			

CROSS SECTION VIEW



FILE NAME	
DRAWING SET	
SHEET 3 OF 7	

Profile Along Centerline

Grade backfill with existing ground to not create a channelized flow path

Inlet WCS Lid Elev. 740.4

Existing ground surface

Place geotextile fabric at woodchip/soil interface.

Inlet WCS stoplog Elev. 736.5

Inlet WCS Sump Elev. 734.4

6" perforated CPT distribution manifold

Sta. 0+10 Elev. 734.2

Lowest Cropped Elev 738.1

Outlet WCS Lid Elev. 739.8

Mound backfill approximately 1 ft. to allow for settling and shed water

Earth fill

Woodchip fill









Inlet WCS stoplog Elev. 734.6

6" perforated CPT collection manifold

Outlet WCS SUMP ELEV. 733.8

Sta. 0+90 Elev. 734.0

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface
-  6" Non-Perforated CPT Pipe
-  Water Control Structure
-  6" Perforated CPT Manifold Pipe

Elevation


Station

DATE
 9/18/23
 DESIGNED BY ANDY MACKFILL
 9/16/23
 DRAWN BY ANDY MACKFILL
 9/22/23
 CHECKED BY ANDY CRAIG
 APPROVED BY

PROFILE ALONG CENTERLINE





FILE NAME
 DRAWING SET
 SHEET 4 OF 7



Legend



	Earth Fill
	Woodchip Media
	Proposed 6" Perforated CPT
	Proposed 6" Non-Perforated CPT
	Existing 6" CPT Main
	Proposed 6" CMP Outlet
	Plastic Liner
	Geotextile Fabric
	Existing Ground Surface
	Bioreactor Footprint

- ### NOTES:
1. All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
 2. Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
 3. Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1" long by 1/2" thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
 4. Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
 5. Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
 6. See Plan Map for benchmark coordinates.



LANDOWNER	LOCATION	SECTION 04 - T80N - R02W
-----------	----------	--------------------------


DATE 9/18/23 DESIGNED BY ANDY MACKRILL 9/16/23 DRAWN BY ANDY MACKRILL 9/22/23 CHECKED BY ANDY CRAIG APPROVED BY	<h2 style="margin: 0;">BIOREACTOR DETAIL</h2>
FILE NAME # DRAWING SET SHEET 5 OF 7	



Legend


- Earth Fill
- Proposed 6" Non-Perforated CPT
- Proposed 6" CMP Outlet
- Existing 6" CPT Main
- Existing Ground Surface

TYPICAL SECTION UPSTREAM STRUCTURE



TYPICAL SECTION DOWNSTREAM STRUCTURE

Side Port Is On The (Circle One) Left / Right Side Of Structure, Looking Downstream



IN-LINE CONTROL STRUCTURES

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, on all lines: upstream, downstream and center. Pipe must be PVC, dual-wall CPT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745. Check valve must conform to ASTM D 3034 with SDR35 pipe or stronger.
 3. Couplings between the water control structures and the non-perforated tile must be watertight.
 4. Stop boards must provide must tight seals under a minimum of 1 foot pressure head (except notched board).
 5. Appropriately mark bioreactor perimeter to avoid vehicle, implement, or livestock traffic.
 6. Place structure and pipe coupler on a stable base. A stable base may be compacted earth, compacted fill sand, or a concrete pad. Extend the stable base no less than 1 foot beyond structure.
 7. Excavated material placed around structure and pipes shall be hand compacted in 4" lifts.

QUANTITIES*	
Water Control Structure, 3 Chamber $H_1 = 6$ ft. $d_1 = 6$ in. $d_2 = 6$ in.	1
Water Control Structure, 2 Chamber $H_2 = 6$ ft. $d_3 = 6$ in.	1
6" Non-perforated Pipe (ft)	175
6" CMP Outlet Pipe With Rodent Guard	20
6" Perforated CPT (ft)	40
6" End Cap	2
Wood Chips (cu. yd.)	190
4 Mil Plastic (sq. yd.)**	285
Geotextile (sq. yd.)	178
Excavation (cu. yd.)	232
Earth Fill (cu. yd.)	89
6" Backflow Check Valve	1

* Quantities do not include tile/pipe couplers or extra material for geotextile/plastic overlap
 ** Accounts for 1 ft. overhang around perimeter

DATE 9/18/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

STRUCTURE DETAIL



FILE NAME
 DRAWING SET
 SHEET 6 OF 7

CONSTRUCTION NOTES

1. Tile elevations are based on Maverick tile probe depths and are to be considered accurate within margin of error of the instrument.
2. If any surface inlets are currently attached to the tile main or plan to be in the future, they shall be replaced with water quality inlets to minimize trash entry into the tile line before construction of the bioreactor begins.
3. Avoid excessive disturbance of any buffers or grassed water ways during construction. However, if re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded within 14 days according to NRCS Conservation Practice Standard IA-342 Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
4. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion.
5. All carbon media to be placed in the bioreactor shall come from an ESE approved vendor or approved with ESE staff prior to transportation and placement.
6. Contact an ESE representative for inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the bioreactor chamber and tile line trenches
 - b. After placing the water control structures and bioreactor manifolds
 - c. After placement of carbon media, before backfilling with soil
 - d. After connections to existing tile and final grading
7. Any product planned for use in construction must be approved by ESE prior to construction. Save and provide documentation to an ESE representative of all materials used in construction including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths
 - b. Photos and invoices for quantity and quality of woodchips/carbon media
 - c. Photos and invoices or product information to detail quantity and quality of plastic and geotextile fabric
 - d. Photos and invoices or product information for water control structures
8. Construction tolerances are ± 0.5 ft on bioreactor chamber dimensions, and ± 0.1 ft. on all elevations. Outlet WCS sump (bottom) must be below the elevation of the bioreactor chamber at the outlet end. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by a representative from ESE and will be noted in the as-built plan.
9. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.
10. All work shall be performed according to the IA construction and practice specifications in the table below.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-95	Geotextile
IA-605	Denitrifying Bioreactor
IA-620	Underground Outlet

DATE
 9/18/23
 9/16/23
 9/22/23

DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 7 OF 7

DENITRIFYING BIOREACTOR CONSTRUCTION PLANS

CEDAR COUNTY, IOWA
SECTION 04- T80N - R02W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. CROSS SECTION VIEW
 4. PROFILE ALONG CENTERLINE
 5. BIOREACTOR DETAIL
 6. STRUCTURE DETAIL
 7. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	8/15/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: All

ENGINEERING CLASS 3

DESIGNED BY	ANDY MACKRILL, TSP	DATE	8/15/2023
DRAWN BY	ANDY MACKRILL, TSP	DATE	8/15/2023
CHECKED BY	ANDY CRAIG, PE	DATE	8/15/2023
APPROVED BY			



COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 7

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 651977.0
 Easting: 2300334.3
 Elevation: 738.6

Staking Control Points (NAD 1983 State Plane Iowa South US SURVEY FEET)				
Point	Description	Northing	Easting	Elevation
1	Southeast Corner BID	651941.0	2300524.3	737.6
2	Southwest Corner BID	651935.6	2300504.9	737.8
3	Northwest Corner BID	652012.9	2300483.5	737.6
4	Northeast Corner BID	652018.3	2300502.8	737.8
5	Inlet WCS (3-chamber)	652021.3	2300473.8	737.6
6	Outlet WCS (2-chamber)	651936.1	2300498.5	737.9
7	Benchmark	651977.0	2300334.3	738.6

DATE 8/15/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY _____


PLAN MAP



FILE NAME _____
 DRAWING SET _____
 SHEET 2 OF 7

Legend






- Proposed 6" Perforated CPT
- Proposed 6" Non-Perforated CPT
- Existing 10" CPT Main
- Proposed 10" Non-Perf CPT Main
- Proposed 10" CMP Outlet
- Bioreactor Footprint
- Water Control Structure
- Benchmark
- 2 Foot Contours




New 10" CMP Outlet
 With Rodent Guard

Approx. Grade 1.8%
 Connecting to
 Existing Outlet.

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface

Cross-Section



DATE 8/15/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

CROSS SECTION VIEW



FILE NAME

DRAWING SET
 SHEET 3 OF 7

Profile Along Centerline

Grade backfill with existing ground to not create a channelized flow path

Inlet WCS Lid Elev. 739.2

Existing ground surface

Place geotextile fabric at woodchip/soil interface.

Inlet WCS stoplog Elev. 735.7

Inlet WCS Sump Elev. 733.2

6" perforated CPT distribution manifold

Sta. 0+10 Elev. 733.0

Lowest Cropped Elev 737.6

Outlet WCS Lid Elev. 738.6

Mound backfill approximately 1 ft. to allow for settling and shed water

Earth fill

Woodchip fill









Inlet WCS stoplog Elev. 733.9

6" perforated CPT collection manifold

Outlet WCS SUMP ELEV. 732.6

Sta. 0+90 Elev. 732.8

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface
-  6" Non-Perforated CPT Pipe
-  Water Control Structure
-  6" Perforated CPT Manifold Pipe

Elevation

Station


DATE 8/15/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

PROFILE ALONG CENTERLINE



FILE NAME
 DRAWING SET
 SHEET 4 OF 7

PLAN





Legend

- Earth Fill
- Woodchip Media
- Proposed 6" Perforated CPT
- Proposed 6" Non-Perforated CPT
- Existing 10" CPT Main
- Proposed 10" Non-Perforated CPT
- Plastic Liner
- Geotextile Fabric
- Existing Ground Surface
- Bioreactor Footprint

NOTES:

1. All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
2. Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
3. Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1" long by 1/2" thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
4. Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
5. Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
6. See Plan Map for benchmark coordinates.





SECTION A-A

DATE	8/15/23
DESIGNED BY ANDY MACKRILL	8/15/23
DRAWN BY ANDY MACKRILL	8/15/23
CHECKED BY ANDY CRAIG	8/15/23
APPROVED BY	

BIOREACTOR DETAIL




FILE NAME	
DRAWING SET	
SHEET 5 OF 7	




Legend

- Earth Fill
- 6" Non-Perforated CPT
- Existing 10" CPT Main
- Proposed 10" CPT Main
- Existing Ground Surface

**TYPICAL SECTION
UPSTREAM STRUCTURE**



**TYPICAL SECTION
DOWNSTREAM STRUCTURE**



IN-LINE CONTROL STRUCTURES

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, on all lines: upstream, downstream and center. Pipe must be PVC, dual-wall CPT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745. Check valve must conform to ASTM D 3034 with SDR35 pipe or stronger.
 3. Couplings between the water control structures and the non-perforated tile must be watertight.
 4. Stop boards must provide must tight seals under a minimum of 1 foot pressure head (except notched board).
 5. Appropriately mark bioreactor perimeter to avoid vehicle, implement, or livestock traffic.
 6. Place structure and pipe coupler on a stable base. A stable base may be compacted earth, compacted fill sand, or a concrete pad. Extend the stable base no less than 1 foot beyond structure.
 7. Excavated material placed around structure and pipes shall be hand compacted in 4" lifts.

* Quantities do not include tile/pipe couplers or extra material for geotextile/plastic overlap
 ** Accounts for 1 ft. overhang around perimeter

QUANTITIES*	
Water Control Structure, 3 Chamber $H_1 = 6$ ft. $d_1 = 10$ in. $d_2 = 6$ in.	1
Water Control Structure, 2 Chamber $H_2 = 6$ ft. $d_3 = 6$ in.	1
10" Non-perforated Pipe (ft)	40
10" CMP Outlet Pipe with Rodent Guard (ft)	20
6" Non-perforated Pipe (ft)	115
6" Perforated CPT (ft)	40
6" End Cap	2
Wood Chips (cu. yd.)	209
4 Mil Plastic (sq. yd.)**	293
Geotextile (sq. yd.)	178
Excavation (cu. yd.)	291
Earth Fill (cu. yd.)	131
6" Backflow Check Valve	1

DATE 8/15/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

STRUCTURE DETAIL



FILE NAME
 DRAWING SET
 SHEET 6 OF 7

CONSTRUCTION NOTES

1. Tile elevations are based on Maverick tile probe depths and are to be considered accurate within margin of error of the instrument.
2. If any surface inlets are currently attached to the tile main or plan to be in the future, they shall be replaced with water quality inlets to minimize trash entry into the tile line before construction of the bioreactor begins.
3. Avoid excessive disturbance of any buffers or grassed water ways during construction. However, if re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded within 14 days according to NRCS Conservation Practice Standard IA-342 Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
4. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion.
5. All carbon media to be placed in the bioreactor shall come from an ESE approved vendor or approved with ESE staff prior to transportation and placement.
6. Contact an ESE representative for inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the bioreactor chamber and tile line trenches
 - b. After placing the water control structures and bioreactor manifolds
 - c. After placement of carbon media, before backfilling with soil
 - d. After connections to existing tile and final grading
7. Any product planned for use in construction must be approved by ESE prior to construction. Save and provide documentation to an ESE representative of all materials used in construction including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths
 - b. Photos and invoices for quantity and quality of woodchips/carbon media
 - c. Photos and invoices or product information to detail quantity and quality of plastic and geotextile fabric
 - d. Photos and invoices or product information for water control structures
8. Construction tolerances are ± 0.5 ft on bioreactor chamber dimensions, and ± 0.1 ft. on all elevations. Outlet WCS sump (bottom) must be below the elevation of the bioreactor chamber at the outlet end. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by a representative from ESE and will be noted in the as-built plan.
9. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.
10. All work shall be performed according to the IA construction and practice specifications in the table below.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-95	Geotextile
IA-605	Denitrifying Bioreactor
IA-620	Underground Outlet

DESIGNED BY	ANDY MACKRILL	DATE	8/15/23
DRAWN BY	ANDY MACKRILL		8/15/23
CHECKED BY	ANDY CRAIG		8/15/23
APPROVED BY			

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
SHEET 7 OF 7

LANDOWNER		LOCATION	SECTION 04 - T80N - R02W
-----------	--	----------	--------------------------

DENITRIFYING BIOREACTOR CONSTRUCTION PLANS

CEDAR COUNTY, IOWA
SECTION 04- T80N - R02W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. CROSS SECTION VIEW
 4. PROFILE ALONG CENTERLINE
 5. BIOREACTOR DETAIL
 6. STRUCTURE DETAIL
 7. CONSTRUCTION NOTES



I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa

Andy J. Craig
8/15/2023

Andy J. Craig, P.E.
License number: 20832

My license renewal date is December 31, 2025.

Pages or sheets covered by this seal: All

ENGINEERING CLASS 3

DESIGNED BY	ANDY MACKRILL, TSP	DATE	8/15/2023
DRAWN BY	ANDY MACKRILL, TSP	DATE	8/15/2023
CHECKED BY	ANDY CRAIG, PE	DATE	8/15/2023
APPROVED BY			



COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 7

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 650952.2
 Easting: 2299579.0
 Elevation: 736.0


Staking Control Points (NAD 1983 State Plane Iowa South US SURVEY FEET)				
Point	Description	Northing	Easting	Elevation
1	Southeast Corner BID	650977.4	2299657.0	736.9
2	Southwest Corner BID	650967.2	2299639.6	736.4
3	Northwest Corner BID	651036.3	2299599.0	736.4
4	Northeast Corner BID	651046.5	2299616.4	736.9
5	Inlet WCS (3-chamber)	651022.5	2299583.4	736.0
6	Outlet WCS (2-chamber)	650965.3	2299637.6	736.3
7	Benchmark	650952.2	2299579.0	736

DATE 8/15/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY _____

PLAN MAP






Legend

- Proposed 6" Perforated CPT
- Proposed 6" Non-Perforated CPT
- Existing 8" CPT Main
- Proposed 8" Non-Perf CPT Main
- Proposed 8" CMP Outlet
- Bioreactor Footprint
- Water Control Structure
- Benchmark
- 2 Foot Contours




FILE NAME _____
 DRAWING SET _____
 SHEET 2 OF 7

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface

Cross-Section



DATE 8/15/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

CROSS SECTION VIEW



FILE NAME

DRAWING SET
 SHEET 3 OF 7

LANDOWNER










LOCATION


SECTION 04 - T80N - R02W

Profile Along Centerline

Grade backfill with existing ground to not create a channelized flow path

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface
-  6" Non-Perforated CPT Pipe
-  Water Control Structure
-  6" Perforated CPT Manifold Pipe
-  Lowest Cropped Area



DATE	8/15/23
DESIGNED BY	ANDY MACKRILL
DRAWN BY	ANDY MACKRILL
CHECKED BY	ANDY CRAIG
APPROVED BY	


PROFILE ALONG CENTERLINE



FILE NAME	
DRAWING SET	
SHEET 4 OF 7	

LANDOWNER		LOCATION	SECTION 04 - T80N - R02W
-----------	--	----------	--------------------------

PLAN





Legend

- Earth Fill
- Woodchip Media
- Proposed 6" Perforated CPT
- Proposed 6" Non-Perforated CPT
- Existing 8" CPT Main
- Proposed 8" Non-Perforated CPT
- Proposed 8" CMP Outlet
- Plastic Liner
- Geotextile Fabric
- Existing Ground Surface
- Bioreactor Footprint

NOTES:

1. All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
2. Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
3. Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1" long by 1/2" thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
4. Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
5. Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
6. See Plan Map for benchmark coordinates.





SECTION A-A

DATE	8/15/23
DESIGNED BY ANDY MACKRILL	8/15/23
DRAWN BY ANDY MACKRILL	8/15/23
CHECKED BY ANDY CRAIG	8/15/23
APPROVED BY	

BIOREACTOR DETAIL




FILE NAME	
DRAWING SET	
SHEET 5 OF 7	



Legend


- Earth Fill
- 6" Non-Perforated CPT
- Existing 8" CPT Main
- Proposed 8" CPT Main
- Existing Ground Surface

**TYPICAL SECTION
UPSTREAM STRUCTURE**



**TYPICAL SECTION
DOWNSTREAM STRUCTURE**

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, on all lines: upstream, downstream and center. Pipe must be PVC, dual-wall CPT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745. Check valve must conform to ASTM D 3034 with SDR35 pipe or stronger.
 3. Couplings between the water control structures and the non-perforated tile must be watertight.
 4. Stop boards must provide must tight seals under a minimum of 1 foot pressure head (except notched board).
 5. Appropriately mark bioreactor perimeter to avoid vehicle, implement, or livestock traffic.
 6. Place structure and pipe coupler on a stable base. A stable base may be compacted earth, compacted fill sand, or a concrete pad. Extend the stable base no less than 1 foot beyond structure.
 7. Excavated material placed around structure and pipes shall be hand compacted in 4" lifts.



IN-LINE CONTROL STRUCTURES

QUANTITIES*	
Water Control Structure, 3 Chamber $H_1 = 6$ ft. $d_1 = 8$ in. $d_2 = 6$ in.	1
Water Control Structure, 2 Chamber $H_2 = 6$ ft. $d_3 = 6$ in.	1
8" Non-perforated Pipe (ft)	40
8" CMP Outlet Pipe With Rodent Guard (ft)	20
6" Non-perforated Pipe (ft)	80
6" Perforated CPT (ft)	40
6" End Cap	2
Wood Chips (cu. yd.)	255
4 Mil Plastic (sq. yd.)**	313
Geotextile (sq. yd.)	178
Excavation (cu. yd.)	320
Earth Fill (cu. yd.)	119
6" Backflow Check Valve	1

* Quantities do not include tile/pipe couplers or extra material for geotextile/plastic overlap
 ** Accounts for 1 ft. overhang around perimeter

DATE 8/15/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

STRUCTURE DETAIL



FILE NAME

DRAWING SET SHEET 6 OF 7

CONSTRUCTION NOTES

1. Tile elevations are based on Maverick tile probe depths and are to be considered accurate within margin of error of the instrument.
2. If any surface inlets are currently attached to the tile main or plan to be in the future, they shall be replaced with water quality inlets to minimize trash entry into the tile line before construction of the bioreactor begins.
3. Avoid excessive disturbance of any buffers or grassed water ways during construction. However, if re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded within 14 days according to NRCS Conservation Practice Standard IA-342 Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
4. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion.
5. All carbon media to be placed in the bioreactor shall come from an ESE approved vendor or approved with ESE staff prior to transportation and placement.
6. Contact an ESE representative for inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the bioreactor chamber and tile line trenches
 - b. After placing the water control structures and bioreactor manifolds
 - c. After placement of carbon media, before backfilling with soil
 - d. After connections to existing tile and final grading
7. Any product planned for use in construction must be approved by ESE prior to construction. Save and provide documentation to an ESE representative of all materials used in construction including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths
 - b. Photos and invoices for quantity and quality of woodchips/carbon media
 - c. Photos and invoices or product information to detail quantity and quality of plastic and geotextile fabric
 - d. Photos and invoices or product information for water control structures
8. Construction tolerances are ± 0.5 ft on bioreactor chamber dimensions, and ± 0.1 ft. on all elevations. Outlet WCS sump (bottom) must be below the elevation of the bioreactor chamber at the outlet end. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by a representative from ESE and will be noted in the as-built plan.
9. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.
10. All work shall be performed according to the IA construction and practice specifications in the table below.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-95	Geotextile
IA-605	Denitrifying Bioreactor
IA-620	Underground Outlet

DATE
8/15/23
DESIGNED BY ANDY MACKRILL
DRAWN BY ANDY MACKRILL
CHECKED BY ANDY CRAIG
APPROVED BY

CONSTRUCTION NOTES



FILE NAME
DRAWING SET
SHEET 7 OF 7


SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 08- T79N - R02W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 6/21/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: All

ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	6/21/2023
DRAWN BY	ANDREW MACKRILL	DATE	6/21/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	6/21/2023
APPROVED BY			




COVER SHEET

FILE NAME

DRAWING SET

SHEET 1 OF 6



Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 10" Non-Perforated CPT
- Proposed 10" CMP Outlet
- Existing 6" CPT Main
- Proposed 6" Non-Perforated CPT
- 2 Foot Contours
- Proposed Water Control Structure

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 616192.2
 Easting: 2297113.3
 Elevation: 584.2

Staking Control Points(NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	585599.7	2243486.4	551.4
2	Distribution Line	585533.5	2243438.9	551.7
3	Distribution Line	585372.8	2242991.8	552.4
4	Distribution Line	585340.4	2242965.7	552.5
5	Distribution Line	585272.9	2242935.5	552.9
6	Distribution Line	584964.5	2242877.8	553.2

DATE 6/21/23

DESIGNED BY ANDREW MACKRILL 6/21/23
 DRAWN BY ANDREW MACKRILL 6/21/23
 CHECKED BY ANDY CRAIG, PE, TSP 6/21/23
 APPROVED BY _____

PLAN MAP



FILE NAME _____


DRAWING SET _____

SHEET 2 OF 6

Bank Cross Section

Legend

- - - Existing Ground Surface
- 6" CPT Distribution Line



BUFFER AND BANK CROSS SECTION



FILE NAME

DRAWING SET
SHEET 3 OF 6


DATE 6/21/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

LANDOWNER






LOCATION

SECTION 08 - T79N - R2W

Profile Along Distribution Line



Legend

-  All Season Water Table
-  Proposed Water Control Structure
-  Proposed 6" CPT Distribution Line
-  Existing Ground Surface
-  Lowest Crop Surface

DESIGNED BY	ANDREW MACKRILL	DATE	6/21/23
DRAWN BY	ANDREW MACKRILL		6/21/23
CHECKED BY	ANDY CRAIG, PE, TSP		6/21/23
APPROVED BY			


PROFILE ALONG DISTRIBUTION LINE



FILE NAME

DRAWING SET
SHEET 4 OF 6


LANDOWNER	LOCATION	SECTION 08 - T79N - R2W
-----------	----------	-------------------------



TYPICAL SECTION

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 10 in.	1	IA-21, IA-26, CPS-587
10" Non-perforated Pipe (ft)	40	IA-21, IA-45
10" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	550	IA-21, IA-45, IA-46
6" Non-perforated Pipe (ft)	275	IA-21, IA-45
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers




PLAN

Legend

- Earth Fill
- 6" Perforated CPT
- Proposed 10" Non-Perforated CPT
- Proposed 10" CMP Outlet
- Ditch Bank
- Existing Ground Surface

NOTES:

1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
3. Couplings between the water control section and the non-perforated tile shall be water tight.
4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.



IN-LINE CONTROL STRUCTURE

DESIGNED BY	ANDREW MACKRILL	DATE	6/21/23
DRAWN BY	ANDREW MACKRILL		6/21/23
CHECKED BY	ANDY CRAIG, PE, TSP		6/21/23
APPROVED BY			

STRUCTURE DETAIL



FILE NAME

DRAWING SET
SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE 6/21/23
 DESIGNED BY ANDREW MACKRILL
 DRAWN BY ANDREW MACKRILL
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 08 - T79N - R2W


SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 14 - T79N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 8/10/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: All

ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	8/10/2023
DRAWN BY	ANDREW MACKRILL	DATE	8/10/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	8/10/2023
APPROVED BY			




COVER SHEET

FILE NAME
DRAWING SET
SHEET 1 OF 6

Staking Control Points(NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	608190.5	2247105.7	692.4
2	Distribution Line	607927.1	2247279.4	692.3
3	Distribution Line	608070.7	2247302.8	692.8
4	Distribution Line	608135.5	2247129.3	692.2
5	Distribution Line	608269.6	2247119.5	692.9
6	Distribution Line	608445.7	2246971.2	693.1
7	Distribution Line	608522.5	2246987.5	696.9
8	Benchmark	607731.9	2247379.2	692.8

PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 607731.9
 Easting: 2247379.2
 Elevation: 692.8



Legend	
	Proposed 6" Perforated CPT Distribution Line
	Proposed 8" Non-Perforated CPT
	Proposed 8" CMP Outlet
	Existing 8" CPT Main
	Proposed Water Control Structure
	2' Contours
	Benchmark
	Staking Point


Existing 8" Tile

800' of 6" CPT at 0.0% Grade

New 8" CMP Outlet With Rodent Guard

Buffer Cross Section, See Sheet 3

Benchmark




DATE	DESIGNED BY	DATE	DRAWN BY	DATE	CHECKED BY	DATE	APPROVED BY
8/10/23	ANDREW MACKRILL	8/10/23	ANDREW MACKRILL	8/10/23	ANDY CRAIG, PE, TSP	8/10/23	

PLAN MAP



FILE NAME	
DRAWING SET	SHEET 2 OF 6

Cross-Section



DESIGNED BY ANDREW MACKRILL 8/10/23
 DRAWN BY ANDREW MACKRILL 8/10/23
 CHECKED BY ANDY CRAIG, PE, TSP 8/10/23
 APPROVED BY _____


BUFFER AND BANK CROSS SECTION








FILE NAME
 ,
 DRAWING SET
 SHEET 3 OF 6

DESIGNED BY ANDREW MACKRILL 8/10/23
 DRAWN BY ANDREW MACKRILL 8/10/23
 CHECKED BY ANDY CRAIG, PE, TSP 8/10/23
 APPROVED BY _____

PROFILE ALONG DISTRIBUTION LINE




Legend

-  All Season Water Table
-  Proposed Water Control Structure
-  Proposed 6" CPT Distribution Line
-  Existing Ground Surface
-  Lowest Farmed Elevation



FILE NAME


DRAWING SET
 SHEET 4 OF 6



TYPICAL SECTION

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 8 in.	1	IA-21, IA-26, CPS-587
8" Non-perforated Pipe (ft)	40	IA-21, IA-45
8" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	800	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587


*Quantities Do Not Include Couplers



PLAN

NOTES:

1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
3. Couplings between the water control section and the non-perforated tile shall be water tight.
4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.



IN-LINE CONTROL STRUCTURE

DATE	DESIGNED BY	DRAWN BY	CHECKED BY	APPROVED BY
8/10/23	ANDREW MACKRILL	ANDREW MACKRILL	ANDY CRAIG, PE, TSP	

3 CHAMBER STRUCTURE DETAIL



FILE NAME	
DRAWING SET	
SHEET 5 OF 6	

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE
 DESIGNED BY ANDREW MACKRILL 8/10/23
 DRAWN BY ANDREW MACKRILL 8/10/23
 CHECKED BY ANDY CRAIG, PE, TSP 8/10/23
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
SHEET 6 OF 6


SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 34- T80N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 7/13/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: _____ All

ENGINEERING CLASS 2

DESIGNED BY	ANDREW MACKRILL	DATE	7/10/2023
DRAWN BY	ANDREW MACKRILL	DATE	7/10/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	7/13/2023
APPROVED BY			



COVER SHEET

FILE NAME



DRAWING SET
SHEET 1 OF 6

Staking Control Points (NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	622999.9	2241686.0	721.6
2	Distribution Line	623868.1	2241578.9	722.1
3	Distribution Line	623141.7	2241465.8	722.6
4	Distribution Line	623225.6	2241334.6	723.7
5	Distribution Line	623339.2	2241158.3	724.2
6	Distribution Line	623448.6	2240986.2	724.6
7	Benchmark	623045.0	2241697.6	721.6









DATE	DESIGNED BY	DRAWN BY	CHECKED BY	APPROVED BY
7/11/23	ANDREW MACKRILL	ANDREW MACKRILL	ANDY CRAIG	


PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 623045.0
 Easting: 2241697.6
 Elevation: 721.6

Legend

-  Proposed 6" Perforated CPT Distribution Line
-  Proposed 6" Non-Perforated CPT
-  Proposed 6" CMP Outlet
-  Existing 6" CPT Main
-  Proposed Water Control Structure
-  2' Contours
-  Benchmark
-  Staking Point




PLAN MAP



FILE NAME

DRAWING SET
SHEET 2 OF 6

Buffer Cross-Section



Legend

- Existing Ground Surface
- 6" CPT Distribution Line


DESIGNED BY	ANDREW MACKRILL	DATE	7/11/23
DRAWN BY	ANDREW MACKRILL		7/11/23
CHECKED BY	ANDY CRAIG		7/13/23
APPROVED BY			

BUFFER AND BANK CROSS SECTION








FILE NAME	L
DRAWING SET	SHEET 3 OF 6

LANDOWNER		LOCATION	SECTION 34 - T80N - R4W
-----------	--	----------	-------------------------



Legend

	All Season Water Table
	Proposed Water Control Structure
	Proposed 6" CPT Distribution Line
	Existing Ground Surface
	Lowest Cropped Elevation

DESIGNED BY	ANDREW MACKRILL	DATE	7/11/23
DRAWN BY	ANDREW MACKRILL		7/11/23
CHECKED BY	ANDY CRAIG		7/13/23
APPROVED BY			


PROFILE ALONG DISTRIBUTION LINE



FILE NAME


DRAWING SET
SHEET 4 OF 6

LANDOWNER	LOCATION	SECTION 34 - T80N - R4W
-----------	----------	-------------------------




TYPICAL SECTION


- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.



QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 6 in.	1	IA-21, IA-26, CPS-587
6" Non-perforated Pipe (ft)	40	IA-21, IA-45
6" CMP Outlet Pipe With Rodent Guard	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	831	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587



PLAN



IN-LINE CONTROL STRUCTURE

*Quantities Do Not Include Couplers

DATE	DESIGNED BY	DRAWN BY	CHECKED BY	APPROVED BY
7/11/23	ANDREW MACKRILL	ANDREW MACKRILL	ANDY CRAIG	
7/11/23				
7/13/23				

3 CHAMBER STRUCTURE DETAIL



FILE NAME
DRAWING SET
SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE
 DESIGNED BY ANDREW MACKRILL 7/11/23
 DRAWN BY ANDREW MACKRILL 7/11/23
 CHECKED BY ANDY CRAIG 7/13/23
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 34 - T80N - R4W

SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 19 - T79N - R4W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



- INDEX OF SHEETS
1. COVER SHEET
 2. PLAN MAP
 3. BUFFER AND BANK CROSS SECTION
 4. PROFILE ALONG DISTRIBUTION LINE
 5. STRUCTURE DETAILS
 6. CONSTRUCTION NOTES

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	_____ 7/13/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2025. Pages or sheets covered by this seal: All

ENGINEERING CLASS 2


DESIGNED BY	ANDREW MACKRILL	DATE	7/11/2023
DRAWN BY	ANDREW MACKRILL	DATE	7/11/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	7/13/2023
APPROVED BY			



COVER SHEET

FILE NAME
L

DRAWING SET
SHEET 1 OF 6



PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD 1983 State Plane Iowa South US Survey Feet)
 Northing: 605598.3
 Easting: 2228463.9
 Elevation: 595.6

Staking Control Points(NAD 1983 State Plane Iowa South US Survey Feet)				
Point	Description	Northing	Easting	Elevation
1	WCS	604849.4	2228817.8	588.4
2	Distribution Line	604947.0	2228757.1	589.0
3	Distribution Line	605059.8	2228686.7	589.5
4	Distribution Line	605168.1	2228619.1	589.7
5	Distribution Line	605364.4	2228479.3	589.6
6	Distribution Line	605514.5	2228373.3	590.7
7	Benchmark	605598.3	2228463.9	595.6

Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 10" Non-Perforated CPT
- Proposed 10" CMP Outlet
- Proposed 10" CPT Main
- Proposed Water Control Structure
- 2' Contours
- Benchmark
- Staking Point

800' of 6" CPT at 0.0% Grade

Buffer Cross Section, See Sheet 3

New 10" CMP Outlet With Rodent Guard

Existing 6" Tile to be Replaced by 10" Tile


DATE: 7/11/23
 DESIGNED BY: ANDREW MACKRILL
 DRAWN BY: ANDREW MACKRILL
 CHECKED BY: ANDY CRAIG, PE, TSP
 APPROVED BY:

PLAN MAP



FILE NAME:
 L:
 DRAWING SET SHEET 2 OF 6

Buffer Cross-Section



DESIGNED BY ANDREW MACKRILL 7/11/23
 DRAWN BY ANDREW MACKRILL 7/11/23
 CHECKED BY ANDY CRAIG, PE, TSP 7/13/23
 APPROVED BY _____

BUFFER AND BANK CROSS SECTION



FILE NAME


L

DRAWING SET
 SHEET 3 OF 6

LANDOWNER

LOCATION

SECTION 19 - T79N - R4W



Legend

- All Season Water Table
- Proposed Water Control Structure
- Proposed 6" CPT Distribution Line
- Existing Ground Surface
- Lowest Farmed Elevation

DESIGNED BY ANDREW MACKRILL	DATE 7/11/23
DRAWN BY ANDREW MACKRILL	7/11/23
CHECKED BY ANDY CRAIG, PE, TSP	7/13/23
APPROVED BY	


PROFILE ALONG DISTRIBUTION LINE




FILE NAME

DRAWING SET
SHEET 4 OF 6

LANDOWNER	LOCATION	SECTION 19 - T79N - R4W
------------------	-----------------	--------------------------------




TYPICAL SECTION




QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 10 in.	1	IA-21, IA-26, CPS-587
10" Non-perforated Pipe (ft)	40	IA-21, IA-45
10" CMP Outlet Pipe With Rodent Guard (ft)	20	IA-604, IA-605
6" Perforated CPT (ft) Buffer Tile Line	800	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers



PLAN

Place Anti-Seep Collar
Approximately 5 to 10 Ft.
Downstream of Structure



**IN-LINE CONTROL
STRUCTURE**

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.

DESIGNED BY	ANDREW MACKRILL	DATE	7/11/23
DRAWN BY	ANDREW MACKRILL		7/11/23
CHECKED BY	ANDY CRAIG, PE, TSP		7/13/23
APPROVED BY			

3 CHAMBER STRUCTURE DETAIL



FILE NAME	
DRAWING SET	SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE
 DESIGNED BY ANDREW MACKRILL 7/11/23
 DRAWN BY ANDREW MACKRILL 7/11/23
 CHECKED BY ANDY CRAIG, PE, TSP 7/13/23
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 19 - T79N - R4W


DENITRIFYING BIOREACTOR CONSTRUCTION PLANS

CEDAR COUNTY, IOWA
SECTION 03- T79N - R04W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



INDEX OF SHEETS

1. COVER SHEET
2. PLAN MAP
3. CROSS SECTION VIEW (N)
4. CROSS SECTION VIEW (S)
5. PROFILE ALONG CENTERLINE (N)
6. PROFILE ALONG CENTERLINE (S)
7. BIOREACTOR DETAIL (N)
8. BIOREACTOR DETAIL (S)
9. STRUCTURE DETAIL
10. CONSTRUCTION NOTES

ENGINEERING CLASS 5

	I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa.
	9/22/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2023. Pages or sheets covered by this seal: <u>All</u>

DESIGNED BY	ANDY MACKRILL, TSP	DATE	9/18/2023
DRAWN BY	ANDY MACKRILL, TSP	DATE	9/18/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	9/22/2023
APPROVED BY			




COVER SHEET

FILE NAME

DRAWING SET


SHEET 1 OF 10

Benchmark:
 Top of Lath Post 215 Feet North
 of Buffer Location (NAD 1983
 State Plane Iowa South US Survey
 Feet)
 Northing: 618658.2
 Easting: 2241927.9
 Elevation: 724.6



Staking Control Points (NAD 1983 State Plane Iowa South US SURVEY FEET)				
Point	Description	Northing	Easting	Elevation
N1	Southeast Corner BID	618453.7	2241911.8	719.1
N2	Southwest Corner BID	618453.9	2241831.6	718.7
N3	Northwest Corner BID	618474.0	2241831.7	720.2
N4	Northeast Corner BID	618473.8	2241911.9	720.3
5	Inlet WCS (3-chamber)	618443.4	2241831.8	718.3
N6	Outlet WCS (2-chamber)	618451.0	2241914.4	718.9

DATE 9/18/23
 DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY _____



PLAN MAP

Legend	
	Proposed 6" Perforated CPT
	Proposed 6" Non-Perforated CPT
	Existing 15" CPT Main
	Proposed 15" Non-Perf CPT Main
	Bioreactor Footprint
	Water Control Structure
	2 Foot Contours


Staking Control Points (NAD 1983 State Plane Iowa South US SURVEY FEET)				
Point	Description	Northing	Easting	Elevation
S1	Southeast Corner BID	618406.7	2241907.1	720.7
S2	Southwest Corner BID	618414.8	2241827.3	720.0
S3	Northwest Corner BID	618434.8	2241829.4	718.4
S4	Northeast Corner BID	618426.8	2241909.1	718.6
5	Inlet WCS (3-chamber)	618443.4	2241831.8	718.3
S6	Outlet WCS (2-chamber)	618430.4	2241911.2	718.1








FILE NAME

DRAWING SET
 SHEET 2 OF 10

Cross-Section (N)



Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface

DATE	9/18/23
DESIGNED BY ANDY MACKFILL	9/18/23
DRAWN BY ANDY MACKFILL	9/18/23
CHECKED BY ANDY CRAIG	9/22/23
APPROVED BY	

CROSS SECTION VIEW (N)



FILE NAME


DRAWING SET
SHEET 3 OF 10

LANDOWNER






LOCATION

SECTION 03 - T79N - R04W

Cross-Section (S)



Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface

DESIGNED BY	ANDY MACKFILL	DATE	9/18/23
DRAWN BY	ANDY MACKFILL	DATE	9/18/23
CHECKED BY	ANDY CRAIG	DATE	9/22/23
APPROVED BY			

CROSS SECTION VIEW (S)



FILE NAME	
DRAWING SET	
SHEET 4 OF 10	









Profile Along Centerline

Grade backfill with existing ground to not create a channelized flow path

Inlet WCS Lid Elev. 720.5

Lowest Cropped Elev 720.0

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface
-  6" Non-Perforated CPT Pipe
-  Water Control Structure
-  6" Perforated CPT Manifold Pipe

Existing ground surface

Place geotextile fabric at woodchip/soil interface.

Elevation

Outlet WCS Lid Elev. 720.6

Mound backfill approximately 1 ft. to allow for settling and shed water

Earth fill

Woodchip fill

Inlet WCS stoplog Elev. 718.0

Inlet WCS stoplog Elev. 716.0

Inlet WCS Sump Elev. 714.5

6" perforated CPT collection manifold

6" perforated CPT distribution manifold

Outlet WCS SUMP ELEV. 714.4

Sta. 0+10 Elev. 714.8

Sta. 0+90 Elev. 714.6

0+00

0+30

0+60

0+90

1+00

Station

DATE
DESIGNED BY ANDY MACKFILL 9/18/23
DRAWN BY ANDY MACKFILL 9/18/23
CHECKED BY ANDY CRAIG 9/22/23
APPROVED BY

PROFILE ALONG CENTERLINE (N)



FILE NAME
DRAWING SET
SHEET 5 OF 10









Profile Along Centerline


Grade backfill with existing ground to not create a channelized flow path

Inlet WCS Lid Elev. 720.5

Lowest Cropped Elev 720.0

Legend

-  Earth Fill
-  Woodchip Media
-  Plastic Liner
-  Geotextile Fabric
-  Existing Ground Surface
-  6" Non-Perforated CPT Pipe
-  Water Control Structure
-  6" Perforated CPT Manifold Pipe



Outlet WCS Lid Elev. 720.6

Mound backfill approximately 1 ft. to allow for settling and shed water

Earth fill

Woodchip fill

Inlet WCS stoplog Elev. 716.0

6" perforated CPT collection manifold

Outlet WCS SUMP ELEV. 714.4

Sta. 0+90 Elev. 714.6

Place geotextile fabric at woodchip/soil interface.

Inlet WCS stoplog Elev. 718.0

Inlet WCS Sump Elev. 714.5

6" perforated CPT distribution manifold

Sta. 0+10 Elev. 714.8

DATE	9/18/23
DESIGNED BY	ANDY MACKFILL
DRAWN BY	ANDY MACKFILL
CHECKED BY	ANDY CRAIG
APPROVED BY	


PROFILE ALONG CENTERLINE (S)



FILE NAME	
DRAWING SET	
SHEET 6 OF 10	

LANDOWNER	LOCATION	SECTION 03 - T79N - R04W
-----------	----------	--------------------------

PLAN




Legend


- Earth Fill
- Woodchip Media
- Proposed 6" Perforated CPT
- Proposed 6" Non-Perforated CPT
- Existing 15" CPT Main
- Proposed 15" Non-Perforated CPT
- Plastic Liner
- Geotextile Fabric
- Existing Ground Surface
- Bioreactor Footprint

NOTES:

1. All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
2. Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
3. Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1" long by 1/2" thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
4. Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
5. Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
6. See Plan Map for benchmark coordinates.



ELEVATION



SECTION A-A


DATE	9/18/23
DESIGNED BY	ANDY MACKRILL
DRAWN BY	ANDY MACKRILL
CHECKED BY	ANDY CRAIG
APPROVED BY	

BIOREACTOR DETAIL (N)



FILE NAME	
DRAWING SET	
SHEET 7 OF 10	

PLAN



Legend


- Earth Fill
- Woodchip Media
- Proposed 6" Perforated CPT
- Proposed 6" Non-Perforated CPT
- Existing 15" CPT Main
- Proposed 15" Non-Perforated CPT
- Plastic Liner
- Geotextile Fabric
- Existing Ground Surface
- Bioreactor Footprint

NOTES:


1. All disturbed non-crop construction areas shall be stabilized by seeding or mulching within 14 days of conclusion of construction activities. This seeding and seed mixture shall meet the NRCS Conservation Practice Standard IA-342 (Critical Area Seeding) or other program requirements to replace previous grass stand.
2. Line bottom and sides of bioreactor chamber with plastic, minimum 4 mil thickness. Overlap any splices at least 6 inches. Lap seams in direction of flow so water flows over top of seam. Wrap plastic carefully around tiles that enter/exit the chamber; no need to seal around tiles.
3. Woodchips shall not contain woods known to have tannin, such as oak, cedar, or redwood. Woodchips shall be reasonably free of soil and other contaminants nor contain loose composting materials. Wood chips shall be around 1" long by 1/2" thick with minimal fines. They shall be processed through a chipper and not through a grinder. Do not use any wood that has been treated for ground contact. ESE has the right to reject any woodchips which do not meet specifications.
4. Geotextile shall be non-woven, Class II, and meet the requirements of Iowa Construction Specification IA-95, Geotextile. Overlap a minimum of 6 inches at all seams.
5. Grade site for positive drainage away from the bioreactor chamber. Spread soil in designated location away from bioreactor.
6. See Plan Map for benchmark coordinates.

DATE	9/18/23
DESIGNED BY	ANDY MACKRILL
DRAWN BY	ANDY MACKRILL
CHECKED BY	ANDY CRAIG
APPROVED BY	

BIOREACTOR DETAIL (S)



ELEVATION




SECTION A-A

LANDOWNER	LOCATION	SECTION 03 - T79N - R04W
-----------	-------	----------	--------------------------




FILE NAME	
DRAWING SET	
SHEET 8 OF 10	

IN-LINE CONTROL STRUCTURES




One Side Port Each on LEFT AND RIGHT Sides Of Structure

TYPICAL SECTION




TYPICAL SECTION DOWNSTREAM STRUCTURE (ONE EACH OF BIOREACTORS N AND S)



DETAIL 1

Cut 1" Notch In Bottom Of The Bottom Board On The Downstream Structure



Legend

- Earth Fill
- 6" Non-Perforated CPT
- Existing 15" CPT Main
- Proposed 15" CPT Main
- Existing Ground Surface

NOTES:

1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, on all lines: upstream, downstream and center. Pipe must be PVC, dual-wall CPT, or CMP.
2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745. Check valve must conform to ASTM D 3034 with SDR35 pipe or stronger.
3. Couplings between the water control structures and the non-perforated tile must be watertight.
4. Stop boards must provide must tight seals under a minimum of 1 foot pressure head (except notched board).
5. Appropriately mark bioreactor perimeter to avoid vehicle, implement, or livestock traffic.
6. Place structure and pipe coupler on a stable base. A stable base may be compacted earth, compacted fill sand, or a concrete pad. Extend the stable base no less than 1 foot beyond structure.
7. Excavated material placed around structure and pipes shall be hand compacted in 4" lifts.

QUANTITIES*

Water Control Structure, 3 Chamber $H_1 = 6$ ft. $d_1 = 15$ in. $d_2 = 6$ in.	1
Water Control Structure, 2 Chamber $H_2 = 6$ ft. $d_3 = 6$ in.	2
15" Non-perforated Pipe (ft)	40
6" Non-perforated Pipe (ft)	60
6" Perforated CPT (ft)	80
6" End Cap	4
Wood Chips (cu. yd.)	431
4 Mil Plastic (sq. yd.)**	592
Geotextile (sq. yd.)	357
Excavation (cu. yd.)	546
Earth Fill (cu. yd.)	213
6" Backflow Check Valve	2

* Quantities do not include tile/pipe couplers or extra material for geotextile/plastic overlap
 ** Accounts for 1 ft. overhang around perimeter

DATE 9/18/23
 DESIGNED BY ANDY MACKFILL
 DRAWN BY ANDY MACKFILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

STRUCTURE DETAIL



FILE NAME
 DRAWING SET
 SHEET 9 OF 10

LANDOWNER

LOCATION

SECTION 03 - T79N - R04W

CONSTRUCTION NOTES

1. Tile elevations are based on Maverick tile probe depths and are to be considered accurate within margin of error of the instrument.
2. If any surface inlets are currently attached to the tile main or plan to be in the future, they shall be replaced with water quality inlets to minimize trash entry into the tile line before construction of the bioreactor begins.
3. Avoid excessive disturbance of any buffers or grassed water ways during construction. However, if re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded within 14 days according to NRCS Conservation Practice Standard IA-342 Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
4. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion.
5. All carbon media to be placed in the bioreactor shall come from an ESE approved vendor or approved with ESE staff prior to transportation and placement.
6. Contact an ESE representative for inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the bioreactor chamber and tile line trenches
 - b. After placing the water control structures and bioreactor manifolds
 - c. After placement of carbon media, before backfilling with soil
 - d. After connections to existing tile and final grading
7. Any product planned for use in construction must be approved by ESE prior to construction. Save and provide documentation to an ESE representative of all materials used in construction including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths
 - b. Photos and invoices for quantity and quality of woodchips/carbon media
 - c. Photos and invoices or product information to detail quantity and quality of plastic and geotextile fabric
 - d. Photos and invoices or product information for water control structures
8. Construction tolerances are ± 0.5 ft on bioreactor chamber dimensions, and ± 0.1 ft. on all elevations. Outlet WCS sump (bottom) must be below the elevation of the bioreactor chamber at the outlet end. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by a representative from ESE and will be noted in the as-built plan.
9. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.
10. All work shall be performed according to the IA construction and practice specifications in the table below.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-95	Geotextile
IA-605	Denitrifying Bioreactor
IA-620	Underground Outlet

DATE
 9/18/23
 9/16/23
 9/22/23

DESIGNED BY ANDY MACKRILL
 DRAWN BY ANDY MACKRILL
 CHECKED BY ANDY CRAIG
 APPROVED BY

CONSTRUCTION NOTES



FILE NAME
 SHEET 10 OF 10


SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 27 - T81N - R3W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



INDEX OF SHEETS

1. COVER SHEET
2. PLAN MAP
3. BUFFER AND BANK CROSS SECTION
4. PROFILE ALONG DISTRIBUTION LINE
5. STRUCTURE DETAILS
6. CONSTRUCTION NOTES

	<p>I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa</p>
	<p><i>Andy J. Craig</i> _____ 07/28/2023 Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2023. Pages or sheets covered by this seal: _____ All</p>

ENGINEERING CLASS 2

DESIGNED BY	BEN REINHART	DATE 07/26/2023
DRAWN BY	BEN REINHART	07/26/2023
CHECKED BY	ANDY CRAIG, PE, TSP	07/28/2023
APPROVED BY		



COVER SHEET



FILE NAME

DRAWING SET

SHEET 1 OF 6

PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD83, Iowa South, US Survey Feet)
 ● Located approx. 1300 feet south of buffer
 Northing: 659854.067
 Easting: 2273128.708
 Elevation: 780.7




Staking Control Points (NAD83, Iowa South, US Survey Feet)

Point	Description	Northing	Easting	Elevation
1	Benchmark	659854.067	2273128.708	780.7
2	Control Structure	661568.251	2273606.063	788.8
3	Distribution Line	661956.235	2273612.031	790.1
4	Distribution Line	661856.741	2273616.636	789.2
5	Distribution Line	661757.247	2273621.240	788.5
6	Distribution Line	661657.773	2273625.612	788.8
7	Distribution Line	661467.419	2273604.834	788.0
8	Distribution Line	661404.562	2273527.607	787.6
9	Distribution Line	661333.164	2273458.548	787.8
10	Distribution Line	661260.000	2273391.313	789.1
11	Distribution Line	661145.697	2273290.983	787.1

Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 6" Non-Perforated CPT
- Proposed 6" CMP Outlet
- Proposed Water Control Structure
- Existing 6" CPT Main
- Existing 4" CPT Main
- Benchmark
- Staking Points
- 2' Contours




DATE: 07/26/23
 DESIGNED BY: BEN REINHART
 DRAWN BY: BEN REINHART
 CHECKED BY: ANDY CRAIG, PE, TSP
 APPROVED BY:

PLAN MAP



FILE NAME:
 s
 DRAWING SET:
 SHEET 2 OF 6

Buffer Cross Section



DATE
 DESIGNED BY BEN REINHART 07/26/23
 DRAWN BY BEN REINHART 07/26/23
 CHECKED BY ANDY CRAIG, PE, TSP 07/28/23
 APPROVED BY _____

BUFFER AND BANK CROSS SECTION



FILE NAME

DRAWING SET
SHEET 3 OF 6






LANDOWNER

LOCATION


SECTION 27 - T81N - R3W

DATE
 DESIGNED BY BEN REINHART 07/26/23
 DRAWN BY BEN REINHART 07/26/23
 CHECKED BY ANDY CRAIG, PE, TSP 07/28/23
 APPROVED BY _____

Legend

-  All Season Water Table
-  Proposed Water Control Structure
-  Proposed 6" CPT Distribution Line
-  Existing Ground Surface
-  Lowest Crop Elevation


Profile Along Distribution Line





PROFILE ALONG DISTRIBUTION LINE



FILE NAME
 DRAWING SET
 SHEET 4 OF 6




TYPICAL SECTION



PLAN

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.



IN-LINE CONTROL STRUCTURE

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 6 in.	1	IA-21, IA-26, CPS-587
6" Non-perforated CPT (ft)	20	IA-21, IA-45
6" CMP Outlet with Rodent Guard	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	870	IA-21, IA-45, IA-46
6" Non-perforated CPT (ft) See Plan Map, Sheet 2	80	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers

DATE 07/26/23
DESIGNED BY BEN REINHART
DRAWN BY BEN REINHART
CHECKED BY ANDY CRAIG, PE, TSP
APPROVED BY

3 CHAMBER STRUCTURE DETAIL



FILE NAME
Sdt
DRAWING SET
SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE
 DESIGNED BY BEN REINHART 07/26/23
 DRAWN BY BEN REINHART 07/26/23
 CHECKED BY ANDY CRAIG, PE, TSP 07/28/23
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 27 - T81N - R3W


SATURATED BUFFER CONSTRUCTION PLANS

CEDAR CO, IOWA
SECTION 27 - T81N - R3W



**Know what's below.
Call before you dig.**

THE CONTRACTOR IS RESPONSIBLE FOR CALLING IOWA ONE CALL AT 1-800-292-8989 AT LEAST 48 HOURS PRIOR TO ANY CONSTRUCTION



INDEX OF SHEETS

1. COVER SHEET
2. PLAN MAP
3. BUFFER AND BANK CROSS SECTION
4. PROFILE ALONG DISTRIBUTION LINE
5. STRUCTURE DETAILS
6. CONSTRUCTION NOTES

	<p>I hereby certify that to the best of my professional knowledge, judgement and belief, these plans meet applicable NRCS conservation practice standards, that this engineering document was prepared by me or under my direct personal supervision, and that I am a duly licensed Professional Engineer under the laws of the State of Iowa</p>
	<p style="text-align: right;"><i>Andy J. Craig</i> _____ 07/28/2023</p> <p>Andy J. Craig, P.E. License number: 20832 My license renewal date is December 31, 2023. Pages or sheets covered by this seal: _____ All</p>

ENGINEERING CLASS 2

DESIGNED BY	BEN REINHART	DATE	07/26/2023
DRAWN BY	BEN REINHART	DATE	07/26/2023
CHECKED BY	ANDY CRAIG, PE, TSP	DATE	07/28/2023
APPROVED BY			





COVER SHEET

FILE NAME	
DRAWING SET	SHEET 1 OF 6

PLAN VIEW

Benchmark:
 Top of Lath Hub (NAD83, Iowa South, US Survey Feet)
 Northing: 659854.067
 Easting: 2273128.708
 Elevation: 780.7



DATE
 DESIGNED BY BEN REINHART 07/26/23
 DRAWN BY BEN REINHART 07/26/23
 CHECKED BY ANDY CRAIG, PE, TSP 07/28/23
 APPROVED BY _____

Staking Control Points (NAD83, Iowa South, US Survey Feet)

Point	Description	Northing	Easting	Elevation
1	Benchmark	659854.067	2273128.708	780.7
2	Control Structure	659684.503	2273169.259	779.5
3	Distribution Line	659399.224	2273159.985	779.5
4	Distribution Line	659485.379	2273211.153	779.3
5	Distribution Line	659585.720	2273217.773	779.3
6	Distribution Line	659770.048	2273135.854	780.0
7	Distribution Line	659868.559	2273145.583	780.8
8	Distribution Line	659968.414	2273163.918	780.1
9	Distribution Line	660066.667	2273139.388	780.3
10	Distribution Line	660148.697	2273083.603	781.0
11	Distribution Line	660226.757	2273019.869	782.0

Legend

- Proposed 6" Perforated CPT Distribution Line
- Proposed 6" Non-Perforated CPT
- Proposed 6" CMP Outlet
- Proposed Water Control Structure
- Existing 6" CPT Main
- Benchmark
- Staking Points
- 2' Contours



PLAN MAP



FILE NAME


DRAWING SET
 SHEET 2 OF 6

LANDOWNER

LOCATION

SECTION 27 - T81N - R3W

Buffer Cross Section



Legend

- - - Existing Ground Surface
- 6" CPT Distribution Line

DESIGNED BY	BEN REINHART	DATE	07/26/23
DRAWN BY	BEN REINHART		07/26/23
CHECKED BY	ANDY CRAIG, PE, TSP		07/28/23
APPROVED BY			






BUFFER AND BANK CROSS SECTION



FILE NAME
DRAWING SET	SHEET 3 OF 6

DATE 07/26/23
 DESIGNED BY BEN REINHART
 DRAWN BY BEN REINHART
 CHECKED BY ANDY CRAIG, PE, TSP
 APPROVED BY

Legend

-  All Season Water Table
-  Proposed Water Control Structure
-  Proposed 6" CPT Distribution Line
-  Existing Ground Surface
-  Lowest Crop Elevation


Profile Along Distribution Line





PROFILE ALONG DISTRIBUTION LINE



FILE NAME
 DRAWING SET
 SHEET 4 OF 6




TYPICAL SECTION



PLAN

- NOTES:
1. Install a minimum of 20 feet of non-perforated pipe adjacent to the water control structure, both upstream, and downstream. Pipe shall be PVC, dual-wall PT, or CMP.
 2. PVC pipe shall conform to ASTM Standard D2241 or D1785, with material 1120 or 1220. Dual wall CPT must conform to ASTM Standard F2306 or F2648. CMP must conform to ASTM Standard A760 or B745.
 3. Couplings between the water control section and the non-perforated tile shall be water tight.
 4. Stop boards shall provide water tight seals under a minimum of 1 foot pressure head.
 5. Mark location of structure using steel t-post or manufactured marker flag for safety in the field.
 6. Install buffer tile parallel to ditch or stream, according to profile provided with the construction plans. Pipe shall remain on grade and drain towards the WCS.
 7. Place structure and pipe coupler on a stable base. A stable base may be compacted earth or compacted fill sand.
 8. Excavated material placed around structure and pipes must be hand compacted in 4" lifts.



IN-LINE CONTROL STRUCTURE

QUANTITIES*		NRCS SPEC
Water Control Structure 3- Compartment H = 6 ft. d = 6 in.	1	IA-21, IA-26, CPS-587
6" Non-perforated CPT (ft)	20	IA-21, IA-45
6" CMP Outlet with Rodent Guard	20	IA-604, IA-620
6" Perforated CPT (ft) Buffer Tile Line	925	IA-21, IA-45, IA-46
3'x3' Anti Seep Collar	1	CPS-587

*Quantities Do Not Include Couplers

DATE
DESIGNED BY BEN REINHART 07/26/23
DRAWN BY BEN REINHART 07/26/23
CHECKED BY ANDY CRAIG, PE, TSP 07/28/23
APPROVED BY

3 CHAMBER STRUCTURE DETAIL



FILE NAME
DRAWING SET
SHEET 5 OF 6

CONSTRUCTION NOTES

1. Tile elevations are based Maverick Tile Finder probe depths. A fiberglass cable with imbedded wire is fed into the outlet and located with a utility device. These values may not be exact, but are believed to be accurate. Factors such as sediment in the pipe, flowing water in the pipe, and wire location within the pipe may affect depth readings. Notify ESE at least 48 hours before conducting the investigation so that a qualified ESE representative can be onsite during the investigation.
2. Avoid excessive disturbance of buffers or grassed water ways during construction. If re-vegetation is needed, contact the local NRCS Field Office for guidance. All disturbed areas that will not be cropped shall be seeded according to NRCS Conservation Practice Standard 342 – Critical Area Planting. Seeding adjacent to the grassed waterway shall match the waterway seeding to the closest extent practical.
3. Excavated material not used for backfill shall be removed from the site or spoiled in such a manner as to prevent flow disruption, channelizing, or erosion. Contact ESE for assistance with construction inspection after the following activities to ensure minimal effort is needed to correct potential errors:
 - a. After excavating the existing tile and setting WCS.
 - b. Distribution pipe has been laid and capped.
4. Any product planned for use in construction must be approved by ESE prior to construction. Provide documentation to ESE of all materials used in construction, including:
 - a. Tile tags, invoices, or photos detailing the product type and manufacturer, ASTM designations, and total lengths.
 - b. Photos and invoices or product information for water control structures.
5. Construction tolerances are ± 0.5 ft on distribution line location, and ± 0.1 ft. on all elevations. If circumstances during construction change dimensions or elevations outside of these tolerances they must be approved by ESE and will be noted in the as-built plan.
6. When installing the distribution line, pay special attention so that other outlets in the buffer are not damaged or broken. Although an investigation of the buffer will have already been completed, not all outlets are able to be located depending on site conditions at the time. If another tile line or outlet is encountered, contact an ESE representative for consultation. They will decide if the tile line is able to be incorporated into the system, or if a section of the distribution line needs to be replaced as non-perforated pipe to prevent water loss.
7. Proper cultural resources documentation shall be completed by the local NRCS office prior to construction. If any cultural resources are identified during construction, work will stop immediately and the NRCS Archeologist will be notified.

Iowa Construction and Practice Specifications	
Specification No.	Specification Description
IA-1	Site Preparation
IA-5	Pollution Control
IA-6	Seeding and Mulching for Protective Cover
IA-604	Saturated Buffer
IA-620	Underground Outlet

DATE
 DESIGNED BY BEN REINHART 07/26/23
 DRAWN BY BEN REINHART 07/26/23
 CHECKED BY ANDY CRAIG, PE, TSP 07/28/23
 APPROVED BY _____

CONSTRUCTION NOTES



FILE NAME

s

DRAWING SET
 SHEET 6 OF 6

LANDOWNER

LOCATION

SECTION 27 - T81N - R3W