

**Attachment 2
Initial Repairs and Maintenance Work**

Bidder is expected to include in bid a quote for initial repairs and maintenance needed to the cooling tower system. It is expected that the Bidder will utilize their bid rates to create an itemized quote. The following tasks have been identified as needing to be completed. If Bidder identifies additional tasks or has alternative solutions, include those in your quote. EVAPCO AT 19-214 repairs and maintenance:

Replacement of fill in all cells

- Parts
- Labor

Remove and replace corroded fill supports with new

- Parts
- Labor

Remove and replace drift eliminator media & supports

- Parts
- Labor

Remove and replace louver media

- Parts
- Labor

Remove and replace gearboxes

- Parts
- Labor

Remove and replace driveshafts

- Parts
- Labor

Remove and replace casing panel replacements

- Parts
- Labor

Clean branch arms header

- Labor

Remove and replace spray system nozzles

- Parts
- Labor

Other repairs or maintenance identified on site visit

- Parts
- Labor